


ar

(4444444







is now textured as well as smooth A sound inert material with a permanent blue-grey precision eminently suited to modern detailing. It's easy to fix, needs no maintenance, and lasts as long as the building.

### cladding

Architects' Journal Information
Sheet 5. B2 describes
Wincilate cladding, and can be
obtained, together with other data,
from the manufacturers:
The Bow Slate & Enamel Co. Ltd.
B.R. Bow Depot, Old Ford Rd. E.3.
tel: ADVance 2203, proprietors
of the Aberllefeni Slate Quarries.

## FORMICA



## SURFACES

Hundreds of thousands of Brussels fair-goers are calling at the Britannia Inn. Some talk Dutch, some talk deutsch and some talk Eskimo. But you don't need a dictionary to appreciate the striking, charming and practical aptness of the FORMICA decorative laminates on that long bar. The top is in Ivory Softglow. The side panels feature the Whitbread motif in blue on an ivory ground, carried out in FORMICA laminates by our special artwork process. Next time you want an individual design, colour and surface richness, smooth, hard, virtually everlasting and clean, get in touch with us. We can do just as good a job for you, on furniture, on fittings, wall or ceiling panelling . . .

<sup>\*</sup> FORMICA is a registered trademark. Formica Ltd, Dept F, De La Rue House, 84 86 Regent Street, London WI



The Swimming bath in the new University of London Student's Union Building—Malet St., W.C.1 Architect: Messrs. Adams, Holden & Pearson.

he whole of the glazed tiling, also the unglazed tiling to the circular columns for this elegant swimming bath in the new University of London Student's Union Building was carried out by the firm of W. B. Simpson.

Simpson's-founded a hundred and twentyfive years ago-provide and lay high quality tiles and terazzo mosaic for public buildings of every kind. Their first-class service and superb workmanship are known and valued throughout the architectural profession and the building industry.



### A. B. SIMPSON AND SONS LIMITED MARTIN'S HOUSE - 374 WANDSWORTH ROAD, S.W.S

## This is what you see in



Stainless steel valves and pipe lines—porcelain enamelled tanks. Conforms with all requirements of The Factory Act.

An average saving of 65% —75% in Soap.

So much simpler, so much cleaner, so much more hygienic, so much more economical, and so *much* of an improvement on the old tilt container! The modern LATHURVALV SOAP DISPENSER gives you at the inward push of the plunger not a dripping liquid but a *rich creamy soapy lather;* ready for use. You can have installed one Lathurvalv, or a hundred, in rows, circles, squares, or any other arrangement you may wish. Installation is quite uncomplicated. IN MODERN WASHROOMS FIT MODERN LATHURVALVS

### 400 washes from one half-pint filling

The individual LATHURN patent liquid soap dispenser for the smaller washroom or domestic use. Simple 2-screw pilfer-proof fixing. Unbreakable container with soap level always visible through slot in the Cast Metal Body. Attractive Anodised Satin Silver finish. Easily fitted by your own staff.



## CATHURVALU & LATHURN


Send Post Card for illustrated literature to:

VALBANIA LTD., CAVENDISH WORKS, WYVIL ROAD LONDON, S.W.8

'Phone: MACaulay 2323/4 (Direct Sales)

'Grams: Uvalbaniex, London, S.W.8

See our Exhibits at The Building Centre, Store Street, Tottenham Court Road, London, W.C.2, and at the Safety, Health and Welfare Museum, Horseferry Road, London, S.W.I



### Capped with a top hat

The weather tightness of the curtain wall illustrated above has been assured by the use of an extruded "top hat" section in Birmetal 055 aluminium alloy—a section specially designed by Henry Hope & Sons Ltd. to cap all the galvanised steel members which the 20,000 square feet of curtain wall contains. By their choice of aluminium alloy the school has, moreover, been endowed with a pleasant external appearance which will neither deteriorate with time nor require expensive maintenance.

The use of Birmetal aluminium alloys is


continually opening up fresh possibilities in architecture.
Why not get in touch with us now?



PIONEERS IN LIGHT ALLOYS

BIRMETALS LIMITED . WOODGATE WORKS . BIRMINGHAM 32






Alec F. French & Partners, Chartered Architects, Plymouth

Our Technical Advisory Department is always available, write, phone or call:

Gardiner, Sons & Co. Ltd., Midland Works, Willway Street, St. Philip's, Bristol 2, and 8 William IV Street, Strand, London W.C.2

## Lighting as you like it

Sieline Continuous Lighting Trunking is permanent—until you want to change it. Plan it as a whole, then alter it piecemeal to suit your changing needs. Reposition and adjust your lighting as often as you like. It is widely used in rented factories where the standard lighting power and distribution do not meet the requirements of the tenant, and it has already been supplied for installations costing from £20 to £20,000.




The trunking is delivered in an advanced state of assembly for easy erection. Control gear and lighting units can be spaced at any intervals. A complete range of suspensions (specimens illustrated) provides for erection under any type of roof. If you would like complete information about Sieline Continuous Lighting Trunking, write for leaflet F.22 or get in touch with your local Siemens Ediswan lighting engineer for advice—no obligation.

## SIELINE continuous lighting

SIEMENS EDISON SWAN LIMITED An A.E.I. Company
Lamps & Lighting Division: 38/39 Upper Thames Street, London, E.C.4
Telephone: CENtral 2332. Telegrams: Sieswan Westcent London

EDISWAN



trunking






FIRTH - VICKERS STAINLESS STEELS LTD., SHEFFIELD

Telephone No: Sheffield 42051

### NEW LOOK



### im ACOVSTICS!



Swiss pressed wood-fibre Perforated, Rilled and Chequered acoustic tiles and Rilled Boards 8'2' in length, all Factory Primed.



Contemporary acoustic wall and ceiling treatments in new and decorative materials.



High acoustic efficiency, absorption co-efficients increasing progressively from 0.45 at 250 c.p.s. up to 0.90 at 4,000 c.p.s.



Low thermal conductivity (0.35 B.T.U in sq.ft/hr. °F diff.) thus providing valuable heat conservation at no extra cost.

Surveys, estimates, designs & specifications without obligation

### HERMESEAL



HERMESEAL ACOUSTICS LIMITED

HEAD OFFICE: 4 PARK LANE, LONDON, W.1. Telephone: GROsvenor 4324 (5 lines).



### an architect asks questions about Sprayed 'Limpet' Asbestos by NEWALLS



"What do you consider is the major advantage of Sprayed 'Limpet' Asbestos?"

Probably the most important element is that the 'Limpet' process gives intimate surface contact, sealing all joints, covering rivets, irregularities and protrusions in a continuous coat that entirely eliminates air spaces—a significant factor in itself.



"I understand that Sprayed 'Limpet' Asbestos has two insulating properties?"

Correct. In addition to providing a high degree of thermal insulation, it is an excellent material for absorbing sound. Indeed, many firms have specified the process for correcting acoustic distortions alone.



"Being largely Asbestos, I suppose the process gives a measure of fire protection?"

Most certainly! Again, it is often used solely because of its fireproofing properties. In fact, this method was the first to be approved for Class A fireproofing of ships under the 1948 Convention.



"Being porous, isn't the treatment liable to premature rotting where condensation exists?"

On the contrary. Asbestos is chemically inert. It is rotproof, verminproof and undamaged by water. Condensation is diffused preventing dripping and allowing for speedy re-evaporation to the atmosphere from the warm surface of the coating.



"It seems too versatile for words. It's a Thermal and Acoustic Insulant, rotproof and verminproof, fire-resistant, prevents condensation, resists vibration . . . anything else?"

Well. It has been used extensively purely as an anticorrosion measure on metals subject to severe corrosive conditions, but we'd have to know the particular application you had in mind to give our full recommendations.



"Naturally. And if we did want Thermal and Acoustic Insulation—and Fire protection in one coating—I suppose it would cost the earth?"

Frankly—no. You see, the erection of timber grounds is not necessary. In application there is no cutting to waste, and the density and thickness is controllable to a very fine degree by highly efficient operators. It compares favourably with conventional insulation methods and materials.

Sprayed 'Limpet' Asbestos is a particularly suitable multi-purpose insulant in schools, public buildings and the like. Our considerable experience in this field will be gladly placed at your disposal.

### Newalls

NEWALLS INSULATION CO. LTD.

HEAD OFFICE: WASHINGTON, CO. DURHAM
A member of the TURNER & NEWALL ORGANISATION
Offices and Depots at LONDON, GLASGOW, MANCHESTER,
NEWCASTLE UPON TYNE, BIRMINGHAM, BELFAST,
BRISTOL & CARDIFF.



Made by HOLOPLAST LIMITED . DEPT. IIC . SALES OFFICE: 116 VICTORIA STREET . LONDON S.W.I . VICTORIA 9354/7 & 9981

## Beautiful

The clean, fresh beauty of "Standard" Sanitary
Appliances made of Vitreous China is a joy to behold.
A brilliant, practical beauty. A modern beauty
that has been achieved by years of planning, styling,
shaping and re-shaping. And below the surface
there is the beauty of a superb craftsmanship. Inside and
out, this Vitreous China ware is really beautiful.

Siamolamol



★ In many countries it is officially required that Sanitary Appliances be made of Vitreous China. Many British architects, doctors, and Public Health Authorities vould like to see similar legislation in Britain and so, not unnaturally, would the makers of "Standard" Sanitary Appliances.



### Durable ...

Whilst the beauty of these appliances can be appreciated at a glance, it takes a lifetime to discover how durable they are. For with Vitreous China comes a higher resistance to harsh treatment than with ordinary ware. Much higher. Their beauty lasts; it is difficult to mar even by accident. And because "Standard" Sanitary Ware made of Vitreous China lasts and lasts, its cost for each year of service is much lower.

### Hygienic...

Fired at a much higher temperature than ordinary ware, Vitreous China is a dense and non-absorbent material which remains steadfastly hygienic.\* And it does not depend on its glaze to make it watertight. It is non-porous and non-crazing. Germs cannot lodge and breed in it. "Standard" Sanitary Ware made of Vitreous China guarantees hygiene for the lifetime of whatever building it serves.

## Vitreous China

Beauty. Durability. Hygiene. Economy. These are the characteristics of "STANDARD" SANITARY APPLIANCES made of VITREOUS CHINA which appeal to the house owner and builder no less than to the doctor and the architect.





### for colourful, lasting decoration

Lintex is a plastic-fortified, cotton-backed wall covering that will withstand really hard wear. It resists scratching, rubbing, staining, grease, dirt and frequent washing and can be kept fresh and bright by occasional sponging with soap and water. Lintex is easy to apply and economical to maintain—ideal for interior decoration. Its wide range of attractive patterns makes it suitable for all kinds of settings, an obvious choice wherever a colourful, washable, practical wall covering is needed.



WX892





Send for the sample range of Lintex

THE WALL PAPER MANUFACTURERS LTD KING'S HOUSE KING STREET WEST MANCHESTER 3

## Rules the waves.

BLACK SHEATHING FELT is the most suitable underlining for hot asphalte, the protection of which is undisturbed by any movement of the substructure.

It rules out the "waves" on the surface of the asphalte that result from using low-grade underlays which have a tendency to wrinkle.

Black Sheathing Felt bonds perfectly with the asphalte, giving complete isolation from the substructure

- ★ Black Sheathing Felt increases thermal insulation
- \* Is pleasant to handle
- \* Will not wrinkle in laying



ASPHALTE LAID ON



## BLACK SHEATHING FELT for YOUR job



Manufactured by

D. Anderson & Son Ltd., Manchester; Engert & Rolfe Ltd., London; John Erskine Ltd., Belfast; Robt. McCalmont & Sons Ltd., Belfast; F. McNeill & Co. Ltd., London; Permanite Ltd., London; John Rogers Ltd., Belfast.

### For the true appeal & long life of all new floors-

SPECIFY

### SPOSS FLOOR SEAL

### - right from the start!



What happens, all too often, to a new floor after it's been laid? You know, and we know, that in a very short time the appeal has been marred, perhaps for good, by dirt and even grease trodden into the surface. Dressing then applied only seals in the dirt. New floors should always be treated immediately. Not only will the surface be perfectly preserved throughout its life but your own professional reputation safeguarded. Sposs Floor Seal and Dressings are formulated specifically for every kind of modern floor.

LEFT Wood-block flooring at Gamage's Stores, High Holborn, treated with Sposs Floor Seal and Dressing.
No special treatment was given to the floor before this photograph was taken. Sposs Dressing had been applied 2-3 weeks before, and normal daily maintenance had been carried out. Despite the high gloss the surface is non-slip.

SPOSS FLOOR DRESSINGS WERE USED IN THESE CONTRACTS:

ROYAL INSTITUTE OF BRITISH ARCHITECTS

GEORGE WIMPEY & CO. LTD.

LIMMER & TRINIDAD LAKE ASPHALT CO. LTD

ROWAN & BODEN LTD. GLAMORGAN C.C.

LANABY CC

LANARK C.C.

MINISTRY OF WORKS
MINISTRY OF SUPPLY

THE ROYAL NAVY

U.S. AIR FORCE

FLOOR SEAL GYMNASIUM SEAL

FLOOR DRESSING (for wood, lino, cork, etc.)

SPECIAL DRESSINGS

(for asphalt, composition and

thermo-plastic tiles)

CEMENT FINISH

### ECONOMICAL

Sposs Floor Seal provides exceptionally good coverages. 1 gallon will seal 150-200 sq. yds. When comparing the price of different Floor Seals this is a very important factor.

### PERMANENCE:

Once a floor has been sealed with Sposs it is protected throughout its life. Subsequent maintenance with Sposs Floor Dressing is all that is required—further applications of seal are quite unnecessary.

### PENETRATION:

The Seal penetrates the surface and combines with the top fibres of the floor, forming a hard, waterproof skin which protects and preserves porous surfaces.

### FINISH

Although not in itself a polish, Sposs Floor Seal will dry with a pleasing gloss. An application of Sposs Floor Dressing will combine with the Seal to produce a brilliant, non-slip and easily cleaned surface.

### SPECIAL PROPERTIES:

Sposs Floor Seal is quick-drying (4 to 6 hours, or less according to weather). It is available in Light Oak, Dark Oak, Red and Natural colours. Can be used to revive old floors with an open grain.



### SPOSS floor seal and Liquid Floor Dressings


YOU'D LIKE MORE INFORMATION?

Cut out and post this coupon now whilst the matter is fresh in your mind. Full details of SPOSS Floor Seal and Dressings will be sent to you in return.

TO SPOSS PRODUCTS LTD, 10, SOVEREIGN ST, LI	EEDS
Please send full details of SPOSS Floor Dressings	
NAME	
ADDRESS	
	; AR


TERRAZZO FINISH

# RAWLPLUG FIXING DEVICES and TOOLS... Backed by the Name that Carries the Weight





Rawldrills. Standard sizes for Rawlplugs Nos. 3 to 30 and Rawlbolts A. B. C. D. E. and G. Adaptable Rawldrills need only three holders for the 10 sizes Nos. 3 to 22. There is also a very useful Universal Tool-set with a knurled holder to take Universal Rawldrills Nos. 6 to 20.






On the occasions where a metal plug is preferred or advised, such as for wet or acid situations, there is the choice of Rawlplug Screw Anchors or White Bronze Plugs, but for these Cadmium plated screws should be used.


**Durium tipped Drills.** For faster, silent penetration of masonry and tiles Durium drills are the answer. They can be used in hand or suitable electric drills. Sizes for Rawlplugs Nos. 6 to 30; for C. D. E. and G. Rawlbolts, and a long series for drilling right through walls. Free resharpening Voucher given with every Durium drill.





Heavy Duty Fixings. RAWLBOLTS are expansion bolts which only require a hole in the masonry in the same way as a Rawlplug. By turning the bolt the metal segments are locked within the hole and the fixing will take very heavy loads with complete safety. Sizes are from 3/16" to 1" diameter.


Rawlplug Stardrills. An inexpensive one piece tool for use on jobs needing a small number of holes. Twenty sizes from 11/32° to 2½° are made, of which eight are for Rawlbolts "A" to "K", and it is only necessary to quote the reference letters of the Rawlbolts when ordering Stardrills to use with them.





Wet or Acid Situations. Rawlplug Bolt Anchors and Rawltamps are made for heavy duty bolt fixings in places where the exposure to corrosion is extremely high. The Bolt Anchor can be set deep down in thick concrete whereas the Rawltamp enables a threaded insert to be fixed in shallow concrete.

Wall Boring Tools. Specially designed for rapid boring right through walls. This triple fluted percussion tool with hexagon handle in one complete unit has been proved to make a ¾" hole right through a 9" stock brick wall in nine minutes. Lengths 18" and 24", diameters from 5/16" to 1¼".







Thin or Cavity Walls. Proprietary building materials often present fixing problems because of being either hard and thin or thick and soft. The Rawlplug Company have devised several clever devices for making firm fixings to such materials including lath and plaster ceilings, hollow pot, panel doors, etc. The upper illustration shows how one

devices will make the almost

Tubular Boring Tools. Will bore a clean hole in soft brick wall quicker than any other hand percussion tool. The serrated edges saw through masonry and the dust is collected in the channel and ejected through the elongated slot. When working in deep holes the tool should be withdrawn periodically and the dust tapped out. Size are from ‡" to 1" diameter.





impossible fixing of a metal plate to a pipe and the bottom illustration shows how the wings of a Spring Toggle spread the load over a plasterboard ceiling.

Power Tools. In addition to the hand tools listed above special Rawlplug tools are made for use in electric and pnuematic power tools. Details of these can be had on application.



Rawlplug Fixing Devices and Hole Boring Tools are sold by Ironmongers, Hardware Dealers, Builders Merchants and Stores. If you experience any difficulty in obtaining the type and size you require please send details to the following address.

8597

THE RAWLPLUG COMPANY LIMITED, CROMWELL ROAD, LONDON, S.W.7



With perfection in mind, a Bilston bath is the natural choice. Bilston design and finish have instant appeal. Bilston quality is appreciated year after year, as its beauty remains unimpaired by the passing of time. The Bilston range includes the exact colour required for any decorative scheme.

Bilston Baths for lasting beauty Atlanta . Magna .

Cresta . Marina .

Mermaid . Bermuda •

Choice of lengths includes 72", 66", 61", 60" and 54".

Atlanta flat bottom helps to prevent slipping - a point of special importance if a shower is fitted.

Shallow step is safe for young and old. The Atlanta can be fitted to give an overall height of only 16". Taps can be fitted in three different positions, to meet all possible requirements.

Corner tap mounting faci-litates installation and maintenance.

Supplied with or without overflow — with or without handgrip.

The Atlanta costs no more than an ordinary bath

BILSTON FOUNDRIES LTD . BILSTON - STAFFORDSHIRE - Illustrated literature is available on request.

High resistance to thermal transmission...



### DOUBLE CLADDING INSULATION

"Major six" DOUBLE cladding insulation provides a high resistance to thermal transmission, contributing to higher equable interior temperature and consequent economical heating. Here is dependable roofing made for quick erection and permanent service.

It's the DOUBLE cladding that does it!—a rigid asbestos-cement underlining sheet laid directly to purlins as a soffit upon which the sheet of insulation is laid before putting the "Major six" sheet in position.



Photograph above illustrates interior view of roof



CEMENTICO, LTDS AF


Easily fixed with hook bolts and washers. "Major six" Double Cladding Insulation complies with the requirements of "Thermal Insulation Industrial Buildings" Bill.

ARTILLERY HOUSE · ARTILLERY ROW · LONDON SWI

Telephone: ABBey 3081 Telegrams: "Atlstonco, Sowest"

Works at: MELDRETH, Nr. Royston Herts.

Also at: Greenhithe . Strood . Cambridge . Shorne . Rye (Sussex) . Gt. Yarmouth



## If you have a Painting Problem — bring it to **FARMILOES**

Your problem will be examined by an expert Technical Representative who will ———

- --- visit and inspect the site to be painted
- discuss the whole job with a panel of specialist experts
- arrange, if necessary, for the Research Laboratory to produce special paints to cope with abnormal conditions
- present you with detailed specifications and Colour Schemes
- maintain liaison with the actual painters until the job is completed.

This Architectural Advisory Service is free of cost or obligation of any kind.


Write or telephone THE MANAGER, Architectural Division,

T. & W. FARMILOE LTD.,

Rochester Row, Westminster, S.W.I.—Tel: Victoria 4480

T. & W. FARMILOE LTD . ROCHESTER ROW . LONDON S.W.I

### Fitting into the scheme of things . . .



When the planning reaches the heating stage remember Biddle "Vectairs".

"Vectair" Convectors are simple to install, will operate from any existing steam or hot water system, and once fitted can be forgotten. They just go on, year after year—providing a clean comfortable atmosphere to live or work in, and the only 'maintenance' they ask is an occasional wipe over with a damp cloth. They are as good to look at as they are to use and do credit to any surrounding decor wherever it may be. Of simple but sturdy construction, and made from only the finest basic materials, each "Vectair" contains the famous Biddle heating coil.

Write for full particulars to:

### F. H. BIDDLE LIMITED

SALES DIVISION OF BRITISH TRANE CO., LTD.)

16 UPPER GROSVENOR ST., LONDON, W.1

Telephones: HYDe Park 0532/9 Cables: EFBIDDLE-AUDLEY-LONDON

### VEGTAIR

CONVECTOR

"IT'S THE COIL THAT COUNTS"





### D. ANDERSON & SON LIMITED.

STRETFORD, MANCHESTER. Tel: LONgford 4444 OLD FORD, LONDON, E.3. Tel: AMHerst 2388

of the most important sporting buildings in the country.



### HOSPITAL STATE


DOHA

Qatar, Persian Gulf.



Architect : John R. Harris, F.R.I.B.A., A.A. Diploma (Hons.)

State Engineer: H. T. Hale, T.D., B.Sc.(Eng.), M.I.C.E.
Civil Engineers: Scott & Wilson, Kirkpatrick & Partners
Quantity Surveyors: Widnell & Trollope
Main Contractors: Darwish Bros., Engineering Department



Air Conditioning, Electrical, Mechanical and Sanitary Services by MATTHEW HALL & CO. LTD.

It is no longer necessary to have to organise and co-ordinate the activities of a number of different sub-contractors. The Matthew Hall Group of Companies undertakes all mechanical services economically and efficiently.

### Air Conditioning Heating

- Electricity
- Sanitation
- Sprinklers Fire Protection

### MATTHEW HALL

GROUP OF COMPANIES



LONDON, Germiston

Durban West Indies

# V Colour Aggregate

### **BRIGHTER-CHEAPER**

At last it is possible to spray brightly coloured ceramic aggregate on walls or ceilings using bitumen or plastic base. Exterior use

Dohm Decor aggregate coats concrete, wood, brickwork, etc., creating modern washable weatherproof colour schemes.

Interior use
Dohm Decor gives a bright, washable finish
for canteen walls, staircases, toilets, cloakrooms, etc.


### Colours

White, bright red, blue and yellow ceramic aggregate.

### Application

Dohm Decor camouflages wall defects and is little affected by movement.
Ordinary spraying equipment can be used.

Price
Contractors quote about 111- per sq. yd., including materials and labour—scaffolding extra.



Write for full details to: DOHM LTD., 167, Victoria St., London, S.W.1. Tel: VICtoria 1414









### Heal's Contracts throw new light on a subject


The subject in this case was the manyhued range of carpets in the new BMK London showrooms. The problem: to avoid the vagaries of natural daylight so that prospective buyers could select a carpet under the same kind of lighting the carpet would be seen in after it was bought. The raw material: two floors in a newly erected block (in its primary "shell" state).

The solution: a careful arrangement of 151 Tungsten lamps and 200 fluorescent lights complete with individual transformer housings for easy maintenance.

In addition to the wholesale showroom (shown above) and reception (below,) Heal's Contracts also designed, built and furnished the equally large retail showroom, and the new BMK offices in an older adjoining building. Particular attention was paid to simplifying the methods of display and ingenious sliding carpet racks were specially made and fitted for this purpose.



Heal's Contracts, we are sure, can be of assistance to you. Why not have your secretary arrange for our senior representative to call.



### **HEAL'S**

CONTRACTS LTD.

196 TOTTENHAM COURT ROAD, LONDON, W.I. TELEPHONE: MUSEUM 1666

Heal's Contracts Ltd. have carried out work for many well-

Heal's Contracts Ltd. have carried out work for many well-known organizations, including: The Bowater Paper Corporation Ltd. Imperial Chemical Industries Ltd. Trades Union Congress: Forn Laing and Son Ltd. Barclays Bank Ltd. Ind Coope and Alsopp Ltd. Wiggins Tlape Group. British Transfort Commission Kraft Foods Ltd. Danish Bacon Company Ltd.

Selected by The Council of Industrial Design

for display in THE DESIGN CENTRE



These three models have been specially designed exclusively for this Company by Jack Howe, F.R.I.B.A., F.S.I.A. They are available in both 9" and 12" dial size and will be appreciated for their suitability where clocks of modern design are required. All models are available for Synchronous or Master Clock operation.



### **ELECTRIC CLOCKS**

For further details write for our illustrated leaflet "Time for Business".

GENT & COMPANY LIMITED . FARADAY WORKS . LEICESTER

London Office & Showrooms: 47 Victoria St., London S.W.I.

BELFAST . BIRMINGHAM . BRISTOL . EDINBURGH . GLASGOW . NEWCASTLE

Other Products include: Time Recorders . WATCHMAN'S CLOCKS . PROGRAMME INSTRUMENTS . LUMINOUS CALL SYSTEMS TOWER CLOCKS . FIRE ALARM SYSTEMS . STAFF LOCATION SYSTEMS . BELL AND INDICATOR SYSTEMS . ETC.

### A new approach to the design and installation of Venetian Blinds







For far too long the many good points of venetian blinds have been overshadowed by unreliability and difficulties of installation. The Crittall Solomatic has been designed to solve these problems.

Its outstanding points are these:

- 1 There are no cords to dangle, tangle or wear-one single control (single strap, double strap or gear) tilts the slats as well as raising or lowering the blind.
- 2 Uneven lowering is made impossible.
- 3 A double-cross web ladder tape prevents flutter.

Every Solomatic blind is made to measure so that it belongs to the window-is not just a patchwork addition to it. Crittall are fully equipped to provide a complete planning and installation service for an entire building-new or old. Write for leaflet.


CRITTALL \_Solomatic VENETIAN BLINDS

-made to measure and made to last

THE CRITTALL MANUFACTURING COMPANY LIMITED . BRAINTREB . ESSEX . Branches and Depots throughout the country

### PLASMATIC

### INTERLOCKING DIFFUSER PANELS



## . . . for illuminated ceilings laylights and lighting fittings

Patent Application No. 37491 56. Reg. Design Nos. 882725, 882726.

Material: Extruded light stabilised Anti-static treated Polystyrene.

Colour: Translucent opal and clear. Size: 10½" wide centres × 4 ft. panels.


Weight: 10 ozs. per square foot.

Light Output Ratio: 54% to 60% opal. 80% to 90% clear.

Suitable for standard suspended ceiling construction with or without ceiling board.

Easily removable for cleaning with damp cloth.

Ask your ceiling contractor and lighting engineer for details...
TUBE LAMINATION & ENGINEERING LTD., Tel.: High Wycombe 4111/2/3/4 (4 lines)
Desborough Park Road, HIGH WYCOMBE, Buckinghamshire





### Resilient ROCKSIL

ROCK WOOL INSULATION

CAPE BUILDING PRODUCTS LIMITED Cowley Bridge Works, Uxbridge. Tel: Uxbridge 4313 Glasgow: Eagle Buildings, 217 Bothwell Street, Glasgow C.2. Tel: Central 2175 Manchester: Floor D, National Buildings, St. Mary's Parsonage, Manchester 3. Tel: Blackfriars 7757 Birmingham: 11 Waterloo Street, Birmingham 2. Tel: Midland 6565-6-7

Newcastle: 19 & 20 Exchange Buildings, Newcastle-upon-Tyne. Tel: Newcastle 20488

Also distributed in England & Wales by:

Also distributed in England & Wales by:
William Kenyon & Sons (MetaMica) Ltd., Chapel Field Works, Dukinfield, Cheshire. Tel: Ashton-under-Lyne 1614
and in Scotland by: William Kenyon & Sons Thermal Insulation (Scotland) Ltd., 140 West George Street, Glasgow C.2. Tel: Douglas 7233

TA457



For really clean air specify TRION electronic air filters


INDUSTRIAL APPLICATIONS

W. C. HOLMES & CO. LTD., (Gas Cleaning Division)

Turnbridge, Huddersfield. Telephone: Huddersfield 5280, COMMERCIAL APPLICATIONS

HARRIS ENGINEERING CO. LTD., (Electronics Division)

York Works, Browning Street, London, S.E.17. Telephone: RODney 3835



The fact that the Trion Electronic Air Filter has an efficiency of 90% on a photometric basis (99.5% on a weight basis) does not mean that it is more expensive than a mechanical filter having a much lower efficiency.

With the Trion Electronic Air Filter maintenance costs are negligible, expensive replacements are unnecessary and power consumption exceptionally low. Ten thousand cubic feet of air per minute can be electronically cleaned for the price of burning a 100 watt bulb.

Capacities of United Kingdom installations range from 250 c.f.m. to 200,000 c.f.m.

Unrelouched views of inlet and outlet of Trion unit after ten weeks continuous operation. This unit protects an electrical relay system.

€ 9383

## ELECTRIC PASSENGER & GOODS

### LIFTS





Institute of Marine Engineers 56/59, Fenchurch Street, London, E.C.3.

One 10 person Passenger Lift travelling at 250 ft. per minute.

Dual Purpose Collective Variable Voltage Control. Power operated sliding doors.


Position indicators and direction arrows at each floor.


Architects: Ronald Ward & Partners.

HAMMOND & CHAMPNESS LTD.,

HAMMOND & CHAMPNESS

GNOME HOUSE, BLACKHORSE LANE, LONDON, E.17. Telephone: LARkswood 1071 Branches in Glasgow, Birmingham, Liverpool, Plymouth, Belfast, Jersey.





At the new Wimbledon covered courts a central ventilator was needed 14 ft. in diameter. Greenwood-Airvac engineers designed and built a special fitting, shown above, photographed from inside, and, below, from the outside.

Spectacular tasks of this kind broaden the experience which helps Greenwood-Airvac build a *Standard Range* of roof ventilators to meet, efficiently and economically, the vast majority of demands for ventilation

and daylight. The cut-out illustrations below are two examples, both of which carry standard glass or 'Perspex' domes. Circular ventilators from 18 in. to 6 ft. diameter, rectangular from 2½ ft. square to 4 ft. x 6 ft.





Please write for the new illustrated leaflets on Greenwood-Airvac ventilators



Committing
Figurery
C. J. Poll and
Partners
Contractors
U. H. Gase and
Some Limited, in
Committee
Limited.

### Greenwood-Airvac

ventilation

G R E E N W O C D 'S A N D A
PATENTEES, DESIGNERS AND MANUFACTURERS OF
NATURAL AND MECHANICAL VENTILLATING EQUIFMENT
ESTABLISHED 1879



BEACON HOUSE, KINGSWAY, LONDON, W.C.2. CHANCERY 8135 (4 lines) 'Grams: 'AIRVAC', LONDON



The accurate control of colour in any tone or shade!

ROBBIALAC COLORIZER PAINTS offer the Architect a scientifically graduated selection of colours that is the world's widest colour choice. Yet all these fine colours are so simple to mix that your contractor can reproduce any colour scheme, however subtle, with absolute accuracy and repeat it again and again

in any quantity. Furthermore, Colorizer Paints impart a quality of finish that gives lasting protection to both inside and outside surfaces.

### ANY COLOUR SUPPLIED IN BULK, READY MIXED FOR IMMEDIATE USE ON SITE

\* Our Architectural Bureau will gladly advise on any colour problem, and offers full on-site co-operation to architects and their contractors.

Emulsion Paint · Super Gloss Enamel · Eggshell Enamel · Suede Finish

### Doverite's bight...

for all contemporary

Doverite is a colourful, noninflammable, plastic material for covering hand and stairway rails, door furniture, steering wheels, casement fittings, etc. It is comfortable to the touch and gives years of wear. The highly polished surface is permanent and cuts cleaning, decorating and maintenance costs. Also available in Black and White, of course.



rail fittings, handles, knobs, etc.


















Plastic covering for all hand & stairway railings, fittings, etc.

DOVER LTD., NORTHAMPTON.



# 'KEY cut my drain laying costs by 28%'

#### says Major J. H. HACKETT

Director of Hackett Builders Limited, Norwich

'A job which would have taken several weeks by traditional methods was completed in under a week with Key Pitch Fibre pipes', says Major J. H. Hackett, of Hackett (Builders) Limited. 'In this time, the entire main sewage pipe to a new estate was laid by a team of only three men. Labour costs for laying and jointing were cut from 1/2d. to 1/d. per foot run. The need for concrete bedding was completely eliminated. With performance at least the equal of best quality materials used by former methods, Key pipe gave me an overall saying of at least 28% on the job'.

Key Pitch Fibre pipes, which were supplied to Hackett (Builders) Limited by Robert R. Ruymp & Son Ltd., Norwich, through B. Finch & Co. Ltd., Essex, (Key distributors), are cutting costs on all the building sites of this company. They are also providing a far more effective answer to the problems of an area with exceptionally bad conditions of loose earth and subsidence. This modern form of drainage could bring equivalent or even greater advantages in performance, economy and speed of laying in your own building projects.

#### FULLY APPROVED

Key pipes comply with the requirements of B.S. 2760, 1956, and carry the B.S.I. 'Kite' mark.

#### NO CRACKING THROUGH SETTLEMENT

The resilience of pitch fibre pipes eliminates cracking under normal conditions of earth settlement, making bedding concrete unnecessary.

#### SIZES AND FITTINGS

2, 3, 4, 5 and 6 in. sizes. 4 and 6 in. diameters are supplied in 8 ft. lengths, other diameters in 5 ft. 6 in. lengths. Easily coupled to conventional drainage fitments.



Major J. H. Hackett handling Key Pitch Fibre pipe on one of the building sites of his company.

#### SPEEDING THE JOB - CUTTING THE COST

500 feet per hour is a modest rate for laying Key Pitch Fibre pipes and the simple jointing system ensures 'all weather' laying. With no cement to dry out, completed drains can be tested and trenches backfilled immediately. When you add laying costs to pipe costs, together with other site advantages, KEY means an overall economy compared with other drainage systems.







TAP IT



TEST IT



Get to know more about



PITCH FIBRE PIPES

A product of the KEY ENGINEERING COMPANY LIMITED Larkfield, Near Maidstone, Kent. Telephone: Maidstone 7461 and 7233



TGA KD 14



Architects: Central Architectural Department of The British Aluminium Co. Ltd. Principal Contractors: Sir Alfred McAlpine & Son Ltd.

### HAYWARDS



### "Reform" roof glazing

The illustrations show part of the

"Reform" Alumalloy roof glazing extensively

used on the new works for The British

Aluminium Company at Latchford Locks.

Write for technical literature.

HAYWARDS LTD. UNION STREET LONDON S.E.I Phone WATerloo 6035 (Private Branch Ex.)


BIRMINGHAM

CARDIFF

JERSEY DUBLIN GLASGOW LEEDS

MANCHESTER NEWCASTLE-ON-TYNE

2854/A



Part of the L.C.C. estate at Abbey Wood,

ARCHITECT: Hubert Bennett, Esq., E.B.L.B.A.

ENGINEERING SERVICES Joseph Rawlinson, c.s.k., M.Eng., M.L.C.K., M.I. Mech.R.

BUILDERS: Unit Construction Co. Ltd., 34 St. James Street, LONDON, S.W.1.

ELECTRICAL CONTRACTORS:
Holliday & sun (Electrical) Ltd.,
Batham High Read,
LONDON, S.W.12.






Electrical Accessories

SIEMENS EDISON SWAN LTD. An A.E.I. Company.

38-39 UPPER THAMES ST., LONDON, E.C.4. TELEPHONE: CENTRAL 2332 TELEGRAMS: SIESWAN CENT LONDON

TAB 1 1210 PD 18/3



## The R.M.S. Sylvania has six basins made of 'Perspex'

ALL OVER THE world 'Perspex' acrylic sheet is being used for colourful modern domestic fittings. Such items as baths, sinks and drainers as well as wash basins are being made from this outstanding material.

Recently The Cunard Steam-Ship Company Limited used it experimentally for six new wash-basins in the R.M.S. Sylvania.

'Perspex' is a tough, attractive material easy to keep clean without abrasives. At the

same time it is light, and economical to install.

'Perspex' is a handsome material which will not stain or tarnish in normal conditions of use. It is available in a wide range of transparent, translucent or opaque colours.

·PERSPEX'

'Perspex' is the registered trade mark for the acrylic sheet made by I.C.I.

IMPERIAL CHEMICAL INDUSTRIES LIMITED . LONDON . S.W.I



#### New Offices for DECCA NAVIGATOR CO LTD 9 ALBERT EMBANKMENT

Messrs. Grace & Farmer QUANTITY SURVEYORS: Messrs. Stanley Griffith & Partners.

'Another impressive building completed by Myton!'



' Yes, Myton aim to do a thorough job in the shortest time.'

Myton are playing an important role in London re-developments. The new Decca building on Albert Embankment is another major construction job which Myton have recently completed.

When you call in the Myton team you call in the wide experience and resources of the Taylor Woodrow group:

experience which blends men and machines into a smooth, efficient organisation to tackle the job, and resources which match the scale of the biggest

Give Myton the signal to go, and you are assured that work will move quickly to a successful conclusion.

### You are seeing more and more of

#### MYTON LIMITED

**Building and Civil Engineering Contractors** 

HEAD OFFICE: NEWLAND - HULL - HULL 42277

MYTON

LONDON OFFICE: 10 PARK STREET W.1 - GROSVENOR 8871 A member of the TAYLOR WOODROW GROUP

### **Trusconversations 4**

SCENE: Architect's office
TIME: Any hour between 9.30 a.m. and 5 p.m.

"Seen these conversations Truscon are putting out?"

"Yes, don't see the point myself."

"Oh! I can see the point—they try and make one each time—I've been following it."

"Oh?"

"Yes, the first was about Granada TV Studio in Manchester—and how quickly they designed and built the framework—six weeks I think."

"I remember."

"In the next one — they've made rather a name for themselves in flats — they tried to emphasise that they still do heavy work."

"Big factories and so on?"

"That's it — and then they had the two site labourers placing Truscon floor units — how light they were to handle."

"All right, but what's the point of this one?"

"You tell me!"

The Trussed Concrete Steel Company Limited, Truscon House, Lower Marsh, London SE.1: Telephone: WATerloo 6922


#### WINTHROP LABORATORIES LIMITED

FAWDON NEWCASTLE UPON TYNE

### **choose Ceramic Tiles**

The pharmaceutical industry demands the highest standard of hygiene, so Ceramic Tiles prove the only choice for wall and floor surfaces. Ceramic Tiles are the best long-term economy.





Ceramic TILES

Glazed & Floor Tile Manufacturers' Association · Federation House · Stoke-on-Trent



now

you can build and finish in one operation with

SPECTRA-GLAZE\*

SPECTRA-GLAZE units, now in production in Gt. Britain, are fully structural concrete blocks (BS2028) on to which a satin-smooth non-ceramic glaze, in a wide range of colours, has been inseparably cast. The unique method of forming the glazed face ensures a surface which is eniformly smooth, free from blemishes and dimensionally accurate. A projecting lip reduces the apparant depth of mortar joints.

SPECTRA-GLAZE combines structural strength, thermat insulation, fine finish and first-to-last economy in one component. Widely used for many years throughout the U.S. and Canada, its reliability has been proved by successful use in nearly thirty million square feet of walling in all types of building under a wide range of climatic conditions.


SPECTRA-GLAZE both in lab, and on site, has proved to be immune from most hazards associated with glazed finishes. Unaffected by normal acids and alkalis, highly resistant to abrasion, impact and thermal shock, it will not craze.

SPECTRA-GLAZE is not just another glazed finish but an already proven versatile component which combines strength, beauty and economy.

SPECTRA-GLAZE builds and finishes in one operation.


Further information and a fully detailed brochure available from the licensees: The Atlas Stone Company Ltd, Artillery House, Artillery Row, SW1.





### The 'BARKING' TRAPPED WASTE

Removed, cleaned and replaced in a matter of moments!



COMPLETE DRAINAGE-NO STAGNANT WATER

INSTANTANEOUS RUBBER SEAL

ADJUSTABLE SLIP JOINT FOR HEIGHT AND ALIGNMENT

3" WATER SEAL

SMOOTH INTERNAL SURFACE

Ends all trouble and inconvenience from stopped-up U-bend pipes. By simply loosening two hand nuts even the housewife can remove, clean and replace the unit, perfectly watertight, in a matter of moments. Requires no special tools for fitting. Well designed and superbly finished in easily cleaned chromium plating or self colour brass. Packed in individual cartons for easy storage.



U-bend instantly removed for easy cleaning



Quality Fittings

Prices and further particulars on request

BARKING BRASSWARE CO. LIMITED

WARERITE Wallboard the low cost, ready-to-fix board for walls and ceilings

Wherever vertical or ceiling surfacings must be moisture resisting, durable and easily cleaned, new colourful WARERITE Wallboard is the obvious and economical choice. Bathroom and kitchen walls, corridors, partitions, cupboard fronts and flush doors are typical applications. WARERITE Wallboard can be screwed or pinned, or fitted into extruded sections.





- Melamine-resin surfaced both sides
- Wipes clean instantly
- Resistant to steam and moisture
- Core of high density fibre board
- Easier construction at lower cost no maintenance
- 16 attractive colours and patterns
- Standard boards 8 ft. x 4 ft.

#### **WARERITE Specialist Service**

WARERITE Specialists are located in 150 cities and towns throughout the country, and supply WARERITE Wallboard from stock.


Write for literature, samples and the name of your nearest WARERITE Specialist.



with the lovelier patterns!




A product of BAKELITE LIMITED . 12-18 GROSVENOR GARDENS . LONDON SWI . Telephone: SLOane 0898



1

Elliotts. Reading

CRAFTSMEN IN WOOD & METAL



Architects: Messrs. Procklehurst, Cooper & Williamson.

Contractors: W. S. Try, Ltd.

Specialists in ECCLESIASTICAL WOODWORK · STAIRCASES · PANELLING
LIBRARY and BANK FITTINGS · SHOP and STORE FITTERS
LABORATORY FITTINGS


Makers of FOLDING and REVOLVING DOORS & TABULA INSULATED SOLID FLUSH DOORS

TDA Approved Manufacturers. Stressed Skin Main and Secondary Beams, Hardwood Stanchions and Lattice Secondary Beams for Schools and Public Buildings.

SAMUEL ELLIOTT & SONS (READING) LTD.

Telephone: Reading 71536-7-8

READING . BERKS



#### Longleys makes full use of EVO-STIK 'impact'



In the construction of the new 200,000 sq. ft. Departmental Store for Jones & Co. Ltd., of Bristol, contractors Longleys of Crawley saved time and labour by mechanically fixing battens both to vertical and ceiling surfaces and then bonding soft wood and ply wood direct to these surfaces with Evo-Stik Impact Adhesive 528.

Evo-Stik Impact Adhesive techniques have been developed for a great variety of modern building operations. If you have sheet materials of any kind to apply to any surfaces we shall be glad to advise you of ways in which accurate bonds of great strength can be obtained with a minimum of labour.



#### Fill in this coupon

'impact' Adhesives

Reg'd trade mark

EVODE LTD. (INDUSTRIAL ADHESIVES DIVISION), COMMON ROAD, STAFFORD. TEL; 2241 (5 lines) LONDON OFFICE: 82 VICTORIA STREET, S.W.1. ABBEY 4622/5 Manufactured in Eire by Evode Industries Ltd., Swords Co. Dublin,

	Please	send	me	brochure	giving	full
tec	hnical	detail	s of	Evo-Stik	adhesi	ves

NAME

ADDRESS



### 600 journals . . . read each month!

Impossible for one man?... a routine achievement for Iota.

Every issue of every technical journal published in Britain is read by the Iota panel of experts. Articles are annotated, classified and listed in the monthly 'Index of Technical Articles.'

Iota can put any article from the Index right onto a subscriber's desk. Journal back issues, or photocopies, are always available. No fuss, no bother. Iota eliminates that

growing in-tray of journals . . . makes

your professional reading much more selective.

Take out your own subscription to Iota.

It's only 8 guineas for 12 issues.

Write for specimen copy of the Index.

Don't miss a thing. . . subscribe to IOTA

IOTA SERVICES LIMITED 38 FARRINGDON STREET LONDON EC4 CITY 1353



# CONFIDENCE ...

MONTGOMERIE'S FINISHES FOR ALL DECORATIVE AND INDUSTRIAL PURPOSES

manufacturers of :-

Purovar Enamel.

Artesco Emulsion Coating.

Rustration Calcium Plumbate Anti-Corrosive Primer.

Emeskote Chemical Resisting Enamel—Air Drying Epikote Resin Based Coating.

Petrifoid 'S' Water Repellent Solution Based on 'Dri-sil' Silicone.



the basis of the artists superb performance . . . the essential when you are specifying materials or PAINT for that new important assignment.

If it's PAINT, and if it's produced by montgomerie stobo—then you can have all the confidence in the world in recommending it for quality, durability, colour fastness and 'rightness for the job'—nothing is left to chance in its manufacture, which probably accounts for the number of new projects on which it is being used to-day!


- ★ Technical Advisory Service for specifications and colour schemes.
- ★ All shades to B.S.S. 2660. 1955 Colour Classification.
  - ★ On Site Technical Service available to architect and builder.

### montgomerie, stobo , co LTD

Deeside, Saltney, Nr. Chester. Telephone Chester 23128 (3 lines) Telegrams 'Turpentine' Chester. 136/154 Stranmillis Road, Belfast, Telephone Belfast 67978. Telegrams 'Turpentine' Belfast.

52-72 Rogart Street, Glasgow, S.E. Telephone Bridgeton 1005/6/7. Telegrams 'Turpentine' Glasgow.

Also at Slough




Ьу

### **BRENT METAL WORKS**

NORTH CIRCULAR ROAD . LONDON . N.W.2 GLADSTONE 6262


### Make this test!

Luxaflex Thermofort slats always snap back perfectly straight



Bend a Luxaflex Thermofort slat which ever way you like. As soon as you let go it will snap back perfectly straight—without damage. Due to a new tempering process Luxaflex Thermofort slats stay springy, keep their

shape and go on looking like new for years.
All components of a Luxaflex venetian blind are made at the same factory.
That's why each blind is technically perfect, functionally faultless, and will give trouble-free service throughout its long life.



Test for yourself the claim that Luxaflex Thermofort slats always snap back perfectly straight. Write for the test slat, free brochure of technical data and list of Luxaflex manufacturers.

LUXAFLEX ALUMINIUM VENETIAN BLINDS



with Luxaflex Thermofort slats

We will send you a test slat free

HUNTER DOUGLAS (GREAT BRITAIN) LTD.

162 BROMPTON ROAD, LONDON, S.W.3. KNIGHTSBRIDGE 4488



Architects:

T. P. Bennett & Son, FF/A.R.I.B.A.

Contractors:

John Mowlem & Company Limited.

Designers:

Charles Hammond Ltd.

Specialist Sub-Contractor:

G. Jackson & Sons Ltd.

The solid English Oak used for the fine carved and panelled room of the Chairman of the Diamond Trading Company Limited, designed and furnished by Charles Hammond Limited, and executed by G. Jackson & Sons Limited, was supplied from the extensive stocks held at our Mill at Bury St. Edmunds where a wide selection is always available to meet architectural requirements.

The English Oak was carefully prepared in our own kilns to ensure its perfect conditioning and in other parts of the building we supplied solid Australian Blackbean and finely figured Blackbean veneer for panels.

### William Mallinson

and Sons Ltd.

TIMBER and VENEER MERCHANTS


130 HACKNEY ROAD .

LONDON . E.2

Telephone: Shoreditch 7654

Telegrams: 'Almoner' London

MANUFACTURERS OF PLYWOOD, ARMOURPLY, PANELS, COMPOSITE PARTITIONING AND INFILL PANELS




W. H. Smith exhibit at the World Fair, Brussels illustrating a typical use of Atlas display lighting.

Successful display lighting requires, above all, flexibility within the lighting system. It is this quality which is a predominant feature of Atlas

Display Lighting fittings. From four basic units and half a dozen attachments some fifty fittings can be assembled, suitable for surface or recessed mounting, with horizontal or vertical lamps, in ratings from 60 - 500 watts. The attachments include deep and shallow satin etched bowls, a white metal louvre, clear or pearl stepped lens, a glass 'festival' diffuser and a selection of Cinabex colour filters. A unique Soffit ring illustrated above clips into position hiding all fixing screws and carrying the attachments. A number of additional fittings designed for special display lighting jobs complete this range of fine quality Atlas fittings. Atlas Lighting engineers are keen to help you with your lighting problems. Their advice is free!

ATLAS LIGHTING LIMITED. A subsidiary company of Thorn Electrical Industries Limited. 255 SHAFTESBURY AVENUE, LONDON, W.C.2.



BRITISH TITAN PRODUCTS COMPANY LIMITED 10 Stratton Street London W.1






(St. Helens 4001) or Selwyn House. Cleveland Row, St. James's, S.W.1. (WHItchall 5672-6.)

SPECIFY ARMOURPLATE

PILKINGTON'S

"ARMOURPLATE" Glass Doors for interiors



TO CLOSE DISCREETLY



Door check and closer available for both doors. 'ARMOURPLATE' and 'ARMOURCAST' are registered trade marks of Pilkington Brothers Limited. Supplies are available through the usual trade channels.




SPECIFY ARMOURCAST

"ARMOURCAST" Glass Doors for interiors

### STEEL . . . the logical structural medium for this SILO BUILDING at WANDSWORTH

Due to the low bearing value of the ground, Messrs. J. Bibby & Sons Ltd. were faced with high foundation costs, and the need to keep



Steelwork by



Structural Steelwork for Factories, Bridges, Power Stations, Garages, Stores, Schools, Steel Fireproof Doors and Rolling Shutters, Steel and Glass Parti-tions, Welded Tanks and Pressure Vessels.


Bottom outlets for SILOS 8'0" × 8'0" × 10'9"

Consulting Engineers: Sir Bruce White, Wolfe Barry & Partners, I Lygon Place, Grosvenor Gardens, LONDON, S.W.1


JOHN BOOTH & SONS (BOLTON) LTD STEELWORKS BOLTON

Telephone: BOLTON 1195

London Office: 26 Victoria Street, Westminster, S.W.1 Telephone: ABBey 7162



With acknowledgements to David Esdaile & Co. Ltd.



# It's a good job—it's UNIVERSAL

### UNIVERSAL suspended ceilings

Developed through 30 years of research and practical experience, Universal's suspension systems are designed for all types of ceilings, and are of a light rigid construction allowing flexibility in design at a cost comparing favourably with other types of ceiling.

Durable and a good fire risk, the metal lath suspended ceiling also offers exceptional sound reduction qualities when used with the appropriate plasters.

Unusual and exciting ceiling design is a practical proposition and we aim to give the best possible service in planning, estimating and construction. Will you call us in at an early stage?

#### THE UNIVERSAL METAL FURRING & LATHING CO. LTD.

Head Office · 175 Merton Road · London SW19 · CHErrywood 3235-7





by



ACOrn 3444

A. DAVIES & Co. (SHOPFITTERS) LTD.
HORN LANE, LONDON W.3

### HEATED ACOUSTIC CEILINGS



The photograph illustrates part of our new offices and showrooms at 16 Berners Street, London, W.1, where our technical staff is at your service

- \* This suspended ceiling combines radiant heat with noise reduction by means of hot water heating pipe coils hidden behind acoustic panels. Both are suspended independently of each other from the existing ceiling. Heat radiating through the perforated acoustic panels provides radiant warmth without stuffiness, while excessive noise is absorbed by both the acoustic panels and the thermal acoustic pad: the latter may also economize in fuel by reducing heat loss.
- \* Extract from Publication No. 348, copies of which will gladly be sent gratis, on application to

# HOPE'S HEATING & ENGINEERING LTD

Smethwick, Birmingham & 16 Berners Street, London, W.1 Branch Offices at Leeds, Cardiff & Hull

### Wates save

# 4-months contract time on 9-storey block of flats




The completed 9-storey block

Thousands of railway travellers have commented on the speed at which the nine-storey block of flats at Royal Street, Lambeth (near Waterloo) has gone up. Few, however, realise that the 20-month contract time was cut by as much as 20 per cent and probably fewer realise how this was done. These are the reasons:

- ★ Enthusiastic pre-contract collaboration between Wates, architect Leslie G. Creed, F.R.I.B.A., A.M.T.P.I., and consulting engineers Felix J. Samuely & Partners, which reduced site work to an absolute minimum.
- ★ Modern constructional methods backed by an organisation with a wealth of experience in this highly specialised work.
- ★ Tight but not impossible targets were set, and not only achieved, but in many cases beaten.



lfter only four months' work



Mosaic mural by Malcolm Hughes

Close to Waterloo Station, the new building is set in a carefully planned landscape area. Externally two bold contrasting colours have been used—blue vertically, pink horizontally. The building is nine storeys high: and provides accommodation for 280 people with a density of 136 to the acre. It comprises 40 two-bedroom maisonettes of 770 sq. ft., 17 three-bedroom flats of 850 sq. ft., and 20 one-bedroom flats of 410 sq. ft.


Ideas become concrete when

WATES BUILD

WATES LIMITED . BUILDING AND CIVIL ENGINEERING CONTRACTORS

Head Office: 1258-1260 London Road, London, S.W.16. Telephone: POLlards 5000. London, Dublin, Birmingham, New York





filtering ... straining... or screening ...we have the media

When solids are to be separated from liquids or gases, acids, or alkalies, there may be an INTERMIT product already in existence, or large numbers can be produced to special design in collaboration with your technicians.

interpose an

INTERMIT filter, strainer, or gauze

INTERMIT LIMITED 37 Bradford Street, Birmingham 5. Phone: Midland 7961



experience and resources

WORKS: INTERMIT LIMITED, Bradford Street, Birmingham BIRFIELD INDUSTRIES LIMITED, Stratford House, London,


### Satina

### the exciting new pendants

The handsome new 'Satina' pendants designed by A.E.I. Lamp & Lighting Co. Ltd. are arrangements of one to six lights, with British made glass of the highest quality satin-etched opal.

The shades are supported by black or white circular PVC flex with brass and matt black components that harmonise with the delicate tones of the glassware.

Write today for a fully illustrated catalogue



This is one of 69 fittings in the 'Satina' range of pendants. Shades are either white or a soft translucent pink. There are twelve different shapes.



Publicity Department, 18 Bedford Square, London, W.C.1

### This is the new-style bathroom



### Braemar basins

#### set in a modern counter or dressing shelf



The Braemar has a flat rim, which means it can be dropped, simply and easily, into any cabinet, counter or worktop. Twin basins, too, are becoming increasingly popular. And more especially those of the 'drop-in' type, like the Braemar.

Smart and attractive. The Braemar streamlined shape is handsome, up to date, and together with a gleaming porcelain enamel finish makes the basin very easy to keep clean. The Braemar comes in colours either to match or contrast with the bath; match perfectly too, because the Braemar is made, like the bath, of enamelled cast iron. And a Braemar looks equally well in a bedroom or dressing room.

Hardest wearing of all. The Braemar, being cast iron, is the strongest type of basin possible, and the porcelain enamel finish can take a lifetime of hard wear.

Two sizes: 22" wide x 18" with bowl 19½" x 12" x 6½" deep. Or 20" wide x 15" with bowl 18" x 10" x 6½" deep.


Fittings: (1) Aluminium frame to make a neat joint between basin and counter-top. (2) ½" Elysian combined hot and cold fitting (mixer optional) with 1½" pop-up waste, or ½" pillar taps with plug and chain. (3) Separate overflow if required.

For full details of the Braemar Hand-basin write to the Housing Division of:

#### ALLIED IRONFOUNDERS LTD

Makers of cookers, boilers, fires and baths 28 BROOK STREET · LONDON · W.1





A large selection of wall brackets, table and floor lands, display fittings and shades

designed by John and Sylvia Rold A/A RIBA M/MSIA FIES for Industrial, commercial

and domestic use ... A lighting service geared for the production of lighting fittings

for all special schemes. Send for your copy of the new Rotaflex catalogue.

's Relafter 'Ovoid' was the 1907 Design-of-the-Year away

ROTAFLEX (GREAT BRITAIN) LTD, SHOWROOM 4 CONDUIT STREET LONDON W1



E.C.4.

STREET, LONDON.

CANNON

69

# TIME and...



The Music Room, Chatsworth House, Derbyshire.

Photograph by A. F. Kersting.

Reproduced by courtery of the Trustees of the Chatsworth Settlement

### the AGELESS BRITISH HARDWOOD FLOOR



Whether exponent of the traditional or contemporary, the Architect cannot ignore time. His works are judged through the passage of years, so too, the materials he uses.

For that part of the building which gets most wear, the floors, the choice must be Hardwood; the only material which combines durability with dignity, warmth and comfort, which mellows with age . . . and lasts through the ages.

The Chatsworth floors are typical. Accounts show that £200 was spent on "OAKE boards for ye floor of ye upper storey", in the year 1690. The floor illustrated is the original laid. No restoration has been necessary even within living memory.

Of what other flooring material can such be truly said.

Chatsworth is open to visitors throughout the Summer months.

THE HARDWOOD FLOORING MANUFACTURERS' ASSOCIATION, LONDON
15 NEW BRIDGE STREET, E.C.4. TEL.: CITY 1476



### 'UNIVERSAL' SIMPLIFICATION

Our new Universal Beam mill is now at work rolling beam sections in a wide range never before made in this country, from 36 in. by  $16\frac{1}{2}$  in. down to 8 in. by  $5\frac{1}{4}$  in. In planning this new range, the needs of the designer have been studied closely, and each section is available in different weights to suit the loads to be carried.

Designers are already reaping the benefit of simplification — for many of the beams are far stronger than any hitherto rolled in Europe. They can be used, direct from the mill, for bridge spans which have previously needed expensive fabrication.


We also roll 'H' sections for columns (ranging from 6 in. by 6 in. up to 14 in. by 16 in.) in related 'families' of different weights, so that the increased column-loading at the lower storeys of tall buildings may be met by simple sections without riveted-on flange plates.

The range of British Standard beams, channels and angles continues to be available.

Diagram showing the arrangement of the rolls, which are adjustable to control the flange and web thickness. The adjustment does not appreciably alter the surfaces shown in blue in the upper illustration.



# DORMAN LONG



# Wise flies know...

A Steelbrac suspended ceiling is practical, economical and speedy. The special light-weight framing is exclusive to the system, and the metal lathing which has 500 meshes per square foot ensures a tenacious key for the plaster. Special effects such as barrel or vaulted ceilings can be demanded without the embarrassment of prohibitive cost. The void between the ceiling and the floor above acts as a natural barrier to noise, and is the obvious place to accommodate services, since absolute latitude is obtained. We have an interesting technical booklet and will be pleased to send you a copy if you will kindly send us your name and address.



...AT THE BACK OF A GOOD SUSPENDED PLASTER
CEILING THERE'S ALWAYS STEELBRAC FRAMING



STEEL BRACKETING & LATHING LTD.

3 8 BRIGSTOCK PARADE, THORNTON HEATH, SURREY

Telephone: Thornton Heath 5601

D





Products include: Presweld steel frames, glass curtain walling, double glazed units, windows and patent glazing, ventilating equipment, etc., etc.

ALBION ROAD, WEST BROMWICH, STAFFS. Telephone: WEST BROMWICH 1811 (15 lines) BRANCHES AT LONDON, MANCHESTER, BRISTOL, NEWCASTLE-ON-TYNE AND GLASGOW



#### **Leonard for Showers**

Uniform's off and a naiad's gone
to take a shower with nothing on.

If she is wise she will take good care
that Leonard's the name the shower valves bear.


If she does not she is apt to find that the cold's not cold and the hot's unkind. Leonard irons out the bumps and keeps things in their places Complexions count not only where the face is.

More about Leonards in pamphlet No. ZC/70

## Hardness ≠Flexibility DECORATIVE = the longest life

Based on Gay's own alkyd-type media. GAYMEL enamel combines hardness of gloss with adequate flexibility and exceptional adhesion. It is these properties that enable buildings enriched with GAYMEL to retain freshness of decoration through years of exposure.

Please write for further information about this remarkable new development in paint manufacture.





Good quality oil paint is capable of long preservative life, but is soon dulled and stained by exposure.

Hard Gloss Paints, when flexibility is inadequate, may fail to expand and contract with the slight but inevitable movement of timber surfaces. 6.4Y MEL is impervious to atmospheric pollution, preserving its colour and gloss. Flexibility and adhesion hold Gaymel against normal movement of all building materials.

# GAYMEL enamel another sound paint - by GAY'S



MANUFACTURED BY R. GAY & CO. WESTMORLAND HOUSE, 127/131 REGENT STREET LONDON, W.1. Telephone; Regent 0831



Write for descriptive leaflet and prices

#### FILON properties

Acid and chemical resistance - Admits 85% of light Available in any length · Easy handling Shadow-free lighting · Standard profiles Held by standard fastenings Low transport and storage costs Needs only light supporting framework No maintenance or replacement costs after installation

#### FILON applications

(Indoor and outdoor)
Roof sheeting · Wall cladding · Partitions · Garages
Sheds · Workshops · Shower or bath enclosures · Barns
Greenhouses · Horticultural sheds
Concrete shuttering · Fencing · Glazing
Diffused ceiling and wall lighting · Shopfitting
Exhibition stand construction



for light with lightness and strength with economy

STRUCTURAL SHEETING

B.I.P. Reinforced Products Ltd., Streetly Works, Sutton Coldfield

Telephone: Streetly 2411

## S.E.C. LIGHTING WITH LUMENATED CEILINGS





#### APPEARANCE IS ONLY HALF THE STORY

- G.E.C. lighting with Lumenated ceilings combine to provide even light distribution without glare.
- G.E.C. high efficiency control gear and Osram guaranteed fluorescent tubes are the essential components for every Lumenated ceiling.
- Before planning your next installation consult the G.E.C. Illuminating Engineering Division at your nearest branch.

G. E.C.

The Reality of a Complete Lighting Service



THE GENERAL ELECTRIC CO. LTD · MAGNET HOUSE · KINGSWAY · LONDON · W.C.2



## Maxweld fabric

is manufactured by RICHARD HILL LIMITED (Established 1868)

Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206 A MEMBER OF THE FIRTH CLEVELAND GROUP



# Another notable advance in Roof-Deck development

- ACOUSTICALLY-TREATED Q-DECK

#### HIGH ACOUSTICAL EFFICIENCY PROVIDED AT MODEST COST

### • THE TREATMENT IS BUILT INTO THE SOFFIT

**Economy:** Acoustically - treated Q-deck generally represents a more economical method of providing for sound absorption in the ceiling than can be secured by most of the conventional alternatives, applied in situ to the underside of the decking.

The complete roof is quickly and easily erected—in one operation.

#### **Effective Sound - Reduction:**

The measure of sound-reduction obtainable with acoustically-treated Q-deck compares favourably with a similar specification of perforated tiles or of spray applied treatments.

The absoption co-efficients quoted are derived from proving tests carried out at the National Physical Laboratory.


#### Attractive Appearance:

Acoustically-treated Q-Deck provides an attractive ceiling: the alternative perforated and imperforate bands creating a decorative pattern.

Range: Acoustical treatment can be applied to Robertson Q-Deck types QDA2, QDC and LSD300 with which it is possible not only to obtain sound absorption, but to provide cells of untreated panels for electric wiring.

FREQUENCY	ABSORPTION CO-EFFICIENT
125 C.P.S	0.25
250 ,,	0.50
500 ,,	0.75
1000 ,,	0.70
2000 ,,	0.50





SEND FOR DETAILS

#### ROBERTSON THAIN LIMITED

ELLESMERE PORT . WIRRAL . CHESHIRE


Telephone Ellesmere Port 3622-9

Telegrams: 'Robertroof


Sales Offices

BELFAST - BIRMINGHAM - CARDIFF - EXMOUTH - GLASGOW - IPSWICH - LIVERPOON LONDON - MANCHESTER - NEWCASTLE - SHEFFIELD

Associated Companies or Agents in most countries throughout the world



## modern



AMONG those concerned with flooring problems many have come to the conclusion that "Semastic" or "Vinylex" tiles are the most practical and economical solution to covering sub-floors in industrial or commercial premises, in public buildings, and often in private homes, whether over new floors or to make old floors like new.

Tiles by Semtex provide ample opportunity for attractive designs, as the examples here show. They are quick to lay and immediately ready for use. This apart from other "user" considerations, such as the economy of longer wear; easy cleaning and maintenance; quiet, comfortable walking surfaces.

SEMTEX, with over 25 branches, provides a complete laying service throughout the United Kingdom, including technical and design advice. There are also independent approved laying facilities in the majority of the principal towns. For full information write or telephone to the address below.

Semastic Decorative and Vinylex Floor Tiles are among the range produced by

## Semtex


. THE COMPREHENSIVE FLOORING SERVICE


SEMTEX LTD. A Dunlop Company, SEMTEX HOUSE, WELSH HARP, LONDON, NW9. Tel: HENdon 6543

#### BOTH PRACTICAL AND DECORATIVE . . .

The examples above show that Semtex flooring has been accepted as the most practical and decorative solution to flooring problems, (left): Semastic Decorative Tiles at Lederle Laboratories Division, Cyanamid of Great Britain Ltd., (right): Vinylex Tiles in a reception hall in Germany.

858 56









## Plan with PILKINGTON'S tiles

Pilkington's offer a carefully selected and balanced range of plain coloured tiles in various finishes and a large variety of decorated tiles suitable for all types of buildings. Pilkington's Design Department is at your service to give you any advice or assistance you may require.








Sample packs of our different ranges of colours and a brochure illustrating the full range of screen printed tiles will be supplied on receipt of this completed coupon.

NAME

FIRM

ADDRES

PLAIN SCREEN PRINTED (delete one if both not required)





PILKINGTON'S TILES LIMITED
CLIFTON JUNCTION: NEAR MANCHESTER

1473 ®

## Born Yesterday ... already the talk of the town



THERE ARE THREE TYPES OF WALLSTRIP





Type C-Recommended for most domestic applications, providing mainly convected heat.

Type R-Institutional model of heavy construction, but shallower from wall to front than Type C, providing mainly radiant heat. Smooth surfaces, free of dust-traps, especially suitable for hospitals and other places where hygiene and cleanliness are vital.

Type RC—Again, an institutional model of heavy construction, similar to Type R but providing a combination of radiant and convected heat.

Copperad WALLSTRIP is a skirting-board: a skirting-board that heats. Which means that it places the heat where it is most needed - all along the outside walls at the normal source of loss.

It also means that windows can reach to within 12" of the floorline.

WALLSTRIP allows you the maximum freedom in aesthetic design. No ungainly, heavy equipment is involved. There is nothing to detract from its flowing lines.

For a new building - home, office, school, hall, hospital or institution - WALLSTRIP costs no more than conventional central heating. The cost of skirting-board is, of course, eliminated. Moreover, no special equipment is required; it can be installed with the ordinary tools of a heating engineer.

If you require further information about WALLSTRIP, we shall be happy to advise you.

Copperad Wallstrip

Copperad Limited Head Office & Works: COLNBROOK, BUCKS, Telephone: Colnbrook 2521 (6 lines) Telegrams: Copperad, Colnbrook

Scottish Office: 53 George Street, Edinburgh, 2 CALedonian 1562

London Office: 1 York Street, Baker Street London W.1 WELbeck 1226/7

Birmingham Office: Wolverley House 18 Digbeth, Birmingham 5 Telephone MIDland 1553

Representatives at: Glasgow, Cardiff, Belfast, Manchester, Leeds, Nottingham, Bristol

Auckland (N.Z.), Johannesburg, Lisbon, Brussels, Toronto, Melbourne

#### MARGINALIA

#### Pitkin on The Tate

The series of busy, inexpensive, gilt-covered Pitkin guides has been augmented by a new volume, dealing with the Tate Gallery. Most of the Pitkin titles deal with historic monuments, country houses, etc., and the techniques employed in describing and illustrating buildings of that kind have rubbed off on the Tate. Although, inevitably, the bulk of the text and pictures deals with individual works of art, it is salutary to see this unhistorical monument treated rather as if it were a stately home—overstuffed with family heirlooms, but under-furnished. It is a rare pleasure to see such a building illustrated as a building, the portico on the front cover, the central hall and gallery XVII on the first double spread, and an aerial view of the greatest town-planning interest, including pioneer work by the LCC Architect's Department, 1, on the back. The coverage of the exhibits is



1, air view of Tate Gallery and LCC housing.

catholic (or should one say Rothensteinian?) and generous—over lifty pieces are illustrated adequately, if not brilliantly, and the text touches on most of the main points of interest raised by the collections, as well as by individual works. Indeed, one only hesitates to recommend it warmly as a remarkable half-crown'sworth because of the unsatisfactory pseudo-rococco gilt-work framing the front cover.

#### Sundry Cicerones

London has grown so large, and a Londoner's use of it tends to become so specialized, that even its citizens find themselves in the role of tourists in their native streets. As a result the spate of London Guides continues unabated, no one can find his way about the Great Wen's secret treasures without a Cierone. Among significant recent additions is another edition—the Sixth—of Sam Lambert's London Night and Day (Architectural Press, 5s.), which remains, Lecause of its

constant revisions, a guide to how to use London, rather than a competitor of Baedeker. More nearly in the Baedeker line is F. R. Banks's new Penguin Guide to London (Penguin Books, 6s.) more generalized in its approach, more sol-mn and more exhaustive in its coverage than the Lambert London, with



2. Lord Powerscourt's house from the pamphlet on eighteenth century Dublin.

which it overlaps extensively, as it does also with Dr. Pevsner's two London volumes in the Buildings of England series. As a general guide Mr. Banks's volume seems admirable, but its architectural information is too scattered and its opinions too conventional ('imposing portico in the classical style') for it ever to realizer Pevsner.

replace Pevsner.

On the other hand, an extremely useful addition to specialist guidance in London has been provided by the Architectural Association Guide to Modern Architecture in London (3s. 6d. from the Association) which consists of a marked map and a gazetteer, up to date as far as December, 1957, covering over 180 buildings and development schemes designed since 1927. Apart from its thoroughness and its efficiency as a direction-finder, its general usefulness has been much enhanced by its tall, pocket-fitting format. This is an ideal shape for a guide that only needs to be consulted at occasional bus-stops, etc., rather than held continually in the hand, and the same format has been used in the Irish Tourist Board's guide to Eighteenth Century Dublin, 2, issued in connection with the Georgian Group's tour of the city, and obtainable from Bord Failte Eiraann, through their various offices.

#### The Penrose Annual

The unexpected death of R. B. Fishendon created a disturbance in the flow of the publication of the Penrose Annual which made many of its devotees doubt its possible survival. However, Mr. Allan Delafons, entrusted with the editorship, battled against the many difficulties which beset the preparing of these substantial volumes and won. Volume 51 had already been planned by Fishendon and came out at last in the autumn instead of at the beginning of 1957. Volume 52, with the publication date in May, was catching up, and next year, it seems, the routine will be established once more. The new volume\* moreover is as rich, as varied and as competent as its predecessors—a great compliment, if one remembers—Fishendon's triumphs.

\*The Penrose Annual, Vol. 52, 1958, edited by Allan Delafons. There are, of course, differences between the two editors, Mr. Delafons in his editorial introduction is more technical than Fishendon and less rewarding on the aesthetic side. But the selection of authors is equally interesting where the subject is technical and where it is aesthetic. For neview readers the paper which will be given first place is Mr. Floud's on Voysey's Wallpapers. Mr. Floud distinguishes two phases in Voysey's style as a designer of flat patterns, and prefers the earlier which is close on the one side to William Morris on the other to .Irt Noweem. He is less in sympathy with Voysey's later, lighter, more original, more naturalistic and more playful style, of which he shows no outstanding example. The paper, it need hardly be said, is full of unpublished details and gives one the feeling that its author had much more available had he been given more space.

The technical papers deal with the frightening changes in book and magazine production by means of new processes, for instance with the one Penguin book so far composed entirely on the film setter without metal type. New machinery seems to be mostly invented or at least developed in America. There is also much stress on the rapid spread of colour photography and colour printing in magazines, even in dailies (one newspaper in England so far accepts coloured advertisements). Most of the technical articles are technical indeed and certain passages seem to the layman to be taken straight from Paul Jennings ("at the time of writing it was available only in tungsten stock rated at Weston 8"). So the layman may be forgiven for turning with relief to Mr. Davis's paper on firms' Christmas cards, not a wholly gratifying subject, to Mr. David Thomas on Trends in English Typography from the 'thirties to the 'fifties, and to


## Mr. Schmoller on the Officina Bodoni A Stadtkrone for Marl


The customary disappointments of second prize—of which Hans Scharoun must have more experience than any other major architect alive could only have been the sharper in the case of the competition for the town centre of Marl, because it was clear that what was wanted was a Stadikrone, that fine old Expressionist concept of a city centre that should stand up like a proud symbol above the town. The idea goes back to Bruno Taut and the heyday of the Expressionists after 1918, but Scharoun's project, 5, shows that the tradition is still alive, and still capable of calling up fine work from its pioneers.

What is even more to the point, however, is that it is a tradition that has taken on new meaning and force in the last few years, as dissatisfaction with diagrammatic, Athens-Charter, city-planning continues to grow. The measure of the force it has acquired is given by the winning design, 4, which is the work of the Dutch architects Bakema and van den Broek, who have hitherto followed the Athens Charter line so piously that Bruno Zevi has accused them of Subtopia Razionalistica (Marginalia, July, 1957). The spritely group of towers with which they propose to dominate the Grune City von Marl, are still very much in the Rationalist tradition, with their mushroom structures, but a section that shows these structures also shows some closely interlocked three-dimensional planning, 3, for pedestrians and vehicles, and the whole project seems to look forward to the kind of reintegrated planning, coupled with the creation of adequate symbols of the good urban life, that the Smithsons demanded in their Custer City article in the review for November, 1957.

#### Fedala Water Tower

As ideally neat as a student's model carved from the solid, the new







section through one tower of winning design for the Stattkrone at Marl by Bakema and Van den Broek;
 air view of the model;
 Scharoun's design for the same competition.





6. Fedala water tower, showing the outer shell, as

water tower at Fedala in Morocco is yet another demonstration of the way in which mathematical subtlety and rules of practised thumb chime together in the best recent vaultwork. The outer shell, 6, is a heavily reinforced hyperbolic paraboloid, generated as usual by a shuttering based on straight timbers and founded in a massive concretering below ground. So far, this is what one might expect in a prestressed shell in which the talents of Prévost and Torroia combine to produce a form whose superficial simplicity conceals mathematics of daunting complexity. But the covering a vital necessity in such a climate, to prevent evaporation relies on time-honoured peasant vaulting techniques, and consists of two ring-yaults of pot tiles, 7, put up over simple mould-boards, without complicated shuttering.

#### CORRESPONDENCE

#### Material and Design

To the Editors.

SIRS,—May I ask you to make it clear to your readers that the introductory paragraphs to my article in the July architectural review were not, in their published form, written by me. They contain statements with which I do not agree. The article will appear in a final form in my book on architectural lettering, to be published shortly by the Architectural Press.

by the Architectural Press.

In the article referred to there also occurs a description which does not refer to the illustration appended. 5 from New Cross Road is an example of gilding and painting on glass; an example of the incised, triangular-section, glass lettering referred to is reproduced in my article of October,

The following corrections should have been made to the captions: 4 is a public-, not a boat-house sign; 12 is in Oxford Street, not in Oxford: and 27 in the Old Brompton Road.

Yours, etc., Nicolete Gray.

Greenwich.

#### Georgian Sculptors

To the Editors

Sus, —Mrs. Webb in her article 'Georgian Sculptors' (AR May) suggests that the Gibbs' drawings in the V. & A. Museum illustrated by her (figs. 6 and 8) may be alternative designs for the Craggs monument in Westminster Abbey (fig. 5). I think they are more likely to be connected with Gibbs' work for Cholmley Turner at Kirkleatham in Yorkshire, where he designed the Mausoleum attached to the parish church. (See my forthcoming article in AR.)

Both the designs (figs. 6 and 8) show a youthful figure and include books, suggesting literary tastes in their subjects; Scheemakers' monument to Marwood William Turner is of the young man (he died in 1734, aged 22, whilst making the Grand Tour) leaning on an urn, as in fig. 6, though of very different design, surrounded by volumes of the classical authors.

Both the designs are set in round headed niches of similar proportions; similar too to the actual niches in the mausoleum and unlike any possible setting in the abbey or the background to fig. 5.

The design of fig. 8 is clearly shown, in a simplified form, in both the versions of Gibbs' de ign for the mausoleum. (It is possible that it was included merely to 'furnish' the drawing, but this is a less straightforward explanation.)

Redear, Yorks. Yours, etc.,
A. C. Taylor.

#### Man in a Hot Tin Box

To the Editors

Sus. This man in his predicament is not the cause of the disease which afflicts our modern cities, he is merely the symptom. The motor car dominates the physical scene because that scene has grown too luge, and the use of the motor car has become too universal.

A motor car is merely an artifact, to plan for it leads nowhere. It is the community that must be planned for a reasonable number of people, and thus a workable number of houses, shops, offices, theatres, factories and motor cars.

Proper planning of communities can greatly reduce the need to use a car and indeed to have a car; and there is no doubt that public transport should be greatly improved and be more widely used. It must, however, be remembered that public transport also tends to fail, and sometimes disastrously, in the larger cities, not due to competition of the motor car but due to too many people living round a restricted perimeter all working in the one place in the centre.

Yours, etc.,

Edinburgh. RICHARD E. MOIRA.

#### Achthamar

To the Editors,

Sins, —I was very pleased to read the interesting article on Achthamar in your March, 1958, issue.

In spite of some misinterpretations of Armenian architecture and some superficial conclusions on the part of the authors, the article was very interesting. The photographic study was very successful; I congratulate the authors for their courage not to follow the beaten track of studying Roman or Greek architecture but revealing the creations of a small but historically important nation; and thank you for encouraging them. Armenian architecture possesses

many original features and outstanding achievements, and it is little studied by European scholars. It is the opinion of many that Seljuk architecture was influenced by Armenia, as many Seljuk mosques are nothing but Armenian churches converted. It is also obvious that many Islamic ideas come from Armenia. On the other hand, your authors seem to overlook influences in Armenian architecture from the Hittites, Urartu, Hayasa, etc. Faces on the reliefs are certainly rather Armenian, with their large eyes and prominent noses, than Mongol. For the study of Armenian art and culture, I would recommend to the authors to avail themselves of the Armenian Archaeological Museum, Academy of Science, or the Armenian State Library, Erivan, Soviet Armenian

Yours, etc., Istanbul. B. Bekar.

#### Corridor Street

To the Editors.

Sirs. I should like to correct the idea, put forward by a whole generation of architects and reinforced in the May AR (cover, Notting Hill article), that the corridor street is necessarily an obsolete and unsatisfactory form of layout. There are plenty of other means of getting good townscape of course, but this particular form has been the basis of some of the most superb urban scenes in the land. What of Oxford High, what of Chipping Campden, what of Lewes, Guildford and Winchester, what of a myriad of little towns like Marlborough, Thame and Bridport; what of Abbey Street, Faversham? True, I could just as easily cite a list of first-rate townscapes that are based on other shapes than the street: I just want to emphasize that the street has been and can still be the basis of much that is tremendously good in urban layout. To be really successful a street should normally have one or more of these characteristics: (1) it should curve. gently but perceptively out of sight. so that the buildings on one side appear in perspective; (2) it should widen, subtly or suddenly, in its most important stretch (Tenterden has a main street that narrows in the middle and opens out at either end and is successful); (3) it should have a prominent feature to close the view, like the Cross at the visual end of three of Chichester's four cardinal streets. Yours, etc.

Chichester. David W. Lloyd,

#### A Liturgical Brief

To the Editors.

Sirs,—The article by Rev. Peter Hammond in your April number was of great interest,

The approach of the liturgical movement appears to be that developed in English Congregational meeting-houses of the seventeenth and eighteenth centuries—the family of the faithful gathered around the Lord's Table.

It is alarming to notice that the

It is alarming to notice that the High Victorian stage already appears to have been reached and a number of the plans illustrated in your article are suitably identical with those of Scottish Presbyterian and English nonconformist buildings of the nineteenth century. The plan of the proposed church at Suarce is virtually that of the Kingsway House Chapel (Congragational) by Alfred Waterhouse and other examples could be quoted.

An antipodean may be forgiven if he wonders whether new Priest is but old Presbyter writ large.

Yours, etc., John Wheeler,

Brisbane, Australia.

#### Biography

Orjan Lüning. Born 1919. Graduated as architect at University of Stockholm in 1945. Worked for Sven Markelius 1945-46, then started own office. Work includes town planning in Sweden and the Bahamas, private houses in Sweden, France, Germany, Mexico, concert hall in Stockholm. Hobbies—French art, in town; on the coast, unsophisticated arts, especially those concerned with shipping.



s, Orjan Luning.

#### INTELLIGENCE


Brighton and Hove town councils have been allocated an annual Government grant to assist in the preservation of the finest examples of their Regency terraces.

#### ACKNOWLEDGMENTS

COVER. Bronislaw Schlabs, SOLENT NATIONAL WATER PARK, pages 145 152: pages 147, 148, Aerofilms, remainder, Nairn Cullen, Arphot; page 149, top left, The Times. Offices in Birmingham, pages 153 Aerofilms. 159, Galwey, Arphot. Looking Up, pages 160-170; frontis top, S. Newbery; 1, Unistrut Corporation; 3, 8, 9, 29, C. Robinson, Arphot US; 4-6, M. Silverstone; 7, 21, 22, Ezra Stoller; Steef Zoetmulder; 13, Toomey, Arphot; 15, E. Braun; 16, A. Cartoni 20, Foto Porta; 25, L'architettura; 26, 28, Lionel Freedman, Church in STOCKHOLM, pages 171 174; Atelje Sundhal, House in California, pages 174 176; Julius Shulman, East of Euclid, pages 178 180; 2, 7–9, R. I. Banks; 5, J. Donat; 6, P. Koralek, Interiors, pages 181 186; 1–5, 10–20, Nolan; 6–9, Galwey, Arphot. Thompson Fectif, pages 187–188: 1, 2, 6, 7, LCC Architect's Department; 4, 5, Galwey, Arphot. CURRENT ARCHITECTURE, pages 189-192: 1, Pantlin: 2-4, Toomey, Arphot; 5, 6, Edward Eves; 7, 8, 8, Newbery, Miscellany, pages 193-200; Exhibi-tions, 1-6, Niarchos Collection Photo-graph Knoedler; Clouded Yellow: 2, 3, 1, de Wolfe; Torrent Bed: 1-3, L. de Wolfe; Counter Attack: 1, Nairn, Arphot. Suspended Cellings, pages 201-210: 1-2. Troughton & Current Architecture, pages 189. pages 201–210: 1, 2, Troughton & Young; 5, G. I. Smyth; 6, Harris & Sheldon (Electrical); 8, J. Maltby; 10. Crompton Parkinson: 12. Falks Photographic Section.

## Ibstock Facing Bricks

. . . . add the charm of colour to every building



#### MARKEATON CREMATORIUM, DERBY

For the County Borough of Derby.

Borough Architect: THOS. W. EAST, F.R.I.B.A.

Bricks: 28" BUFF MULTI-RUSTICS.

Contractors: Messrs. FORD & WESTON Ltd.,

Osmaston, Road, Derby.


This modern building is faced with Buff Multi-Rustic facing bricks. Supplied in a number of attractive colours, Ibstock facing bricks are being specified by Architects everywhere.



FACING BRICKS

IBSTOCK BRICK & TILE COMPANY LTD., Ibstock, near Leicester London: L.M.R. Goods Depot, Wright's Lane, Kensington, W.8

Phone: Ibstock 591 (3 lines)
Phone: Western 1281 (2 lines)



## Who dreamed this up?

Sorry old chap, we did. From where you stand it may look weird, but in fact it's a particular kind of roofing: TRINASCO Built-up Felt Roofing by Limmer & Trinidad, specially designed for the lightweight buildings so much in fashion today, but completely suitable too for buildings of all kinds. Because this roofing is light in weight and extremely durable and decorative at the same time. You can adapt TRINASCO Built-up Roofing to most styles of roof construction, and it can be laid to any specification you require. And all along the line our technical staff are there to help you, and to advise you as to the system of insulation you may need. It's just part of the Limmer & Trinidad Roofing Service. If you'd like further details a descriptive leaflet is yours for the writing.

## **LIMMER & TRINIDAD**

BUILT-UP FELT ROOFING

THE LIMMER & TRINIDAD LAKE ASPHALT COMPANY LIMITED, TRINIDAD LAKE HOUSE, 232-242 VAUXHALL BRIDGE ROAD, LONDON, S.W.I

## THE ARCHITECTURAL REVIEW



The Cover reproduces, at about twice its dimensions, a photogram by Bronislaw Schlabs, from a recent o show of his work at the Architects' Club in Poznan. Made by soaking photographic paper in developer, covering it with transparent objects, and exposing it to the light from an enlarger, it represents a directly manipulative approach to the photographic process that stands close to the Bauhaus tradition in modern design, and has also taken on new significance since the advent of 'action painting.' The appearance of an image of such international currency in Eastern Europe should not, perhaps, be endowed with too much significance: nevertheless it suggests that channels of aesthetic communication are again open, where once they had seemed irrevocably closed.

- 141 Marginalia
- 144 Frontispiece
- 145 Solent by Geoffrey Robson The Solent, at present, is an arterial waterway running, as yet, through unspoiled countryside, but unless care is taken, it could become the Kingston by-pass of the English Channel. This stretch of water between the Isle of Wight and the mainland is the largest area of sheltered deeps on the South Coast, and the only undeveloped part of the same coast in two hundred miles. In his article, Mr. Robson characterizes the topography, the use, and harbours of this area which affords work and recreation to as many and as varied persons as use the inland National Park areas. Aside from the location and nature of purely shorebound developments, the problems of the Solent are almost entirely involved with yachts and yachting, but these ns in their turn also affect the appear ance of the shoreline in innumerable ways, ust be an carefully studied.
- 153 Offices at Birmingham: Architect, Ernö Goldfinger

J. M. Richards Nikolaus Pevaner H. de C. Hastings Directing Hugh Casson Executive Ian McCallum Editor Art Editor Gordon Cullen Technical

Assistant Editors production, William Mackie. research, S. Lang. literary, Reyner Bunham. Editorial Secretary Whi 0611-9

Editor

Lance Wright

### Volume 124 Number 740 September 1958

- 160 Looking Up by Michael Brawne Suspended ceiling systems have invaded architecture as a prefabricated solution to the visual problem of overhead services, but their own inherent visual qualities have been barely considered. In two articles—one in July AR, the other in p. 201 of this issue—Peter Matthews has surveyed the technical aspects of the various systems on the market, and in the present article Mr. Brawne turns attention to the aesthetic problems, in more senses than the purely visual, of the largest area in any room that is entirely within the architect's control. As he shows, when full cognizance is taken of all the effects and all the possibilities of suspended ceilings they may become so much more than the fillers-in of unconsidered overhead spaces that they revolutionize plans and elevations, and introduce new sculptural concepts of interior
- 171 Church in Stockholm: Architect, Orjan Lüning
- 174 House in California: Architect, Richard Neutra
- 177 The Exploring Eye: East of Euclid We tend to forget that Euclid was an Egyptian, born long after the completion of the Parthenon and other buildings we loosely call Euclidian. In historical fact the greet buildings of Greece were conceived in a cruder, older geometry than Euclid's, and the architecture that does benefit from his geometry was created eight-hundred years later, east of his native Alexandria, to serve the aspirations of the rising crescent of Islam.
- 181 Interiors: Nottingham University: Co-ordinating Designer, Hugh Casson Interior Designers, Ward and Austin, Hugh and Margaret Casson, H. T. Cadbury-Brown, John Wright
- 184 Interiors: Offices in Davies St., W.1. Architect, J. M. Austin Smith and
- 187 Thompson Fecit by Ida Darlington One of England's most enterprising forger-architects was Peter Thompson, who, in 1852, successfully passed off a number of drawings at the Archaeological Association as being the work of a parliamentarian captain in the Civil War. Other drawings from his hand appeared with such signatures as Sutton Nichols, and even W. Hollar, and alt/Lough all were exposed, this caused only a temporary check in Thompson's devious career. As Miss Darlington shows, he was also involved in periodical publishing, pro-

duced a design for the new Houses of Parlia-ment, had views on working-class housing, and actually built a series of temporary churches in London's outer suburbs.

189 Current Architecture

Miscellany

- 195 Exhibitions
- 196 Townscape
- 198 Outrage
- 198 Functional Tradition
- 199 Counter Attack

Mcill.

- 201 Suspended Ceilings Part II by Peter Matthews In the second of two articles designed to provide the technical backing to Michael Brawne's on p. 160, Mr. Matthews describes the various suspended ceiling systems that provide for the delivery of services—heat, light, ventilation—passing through the plane of the ceiling.
- 212 The Industry
- 213 Contractors


Authors: Geoffrey Robson was born in Scarborough in 1918, studied at the AA school from 1935-40, and became a partner with Richard Sheppard in 1949, He is an intrepid motorist maintaining a collection of Lancias, and a yachtaram sailing an 8-ton yawl built in Hove in 1913, with moorings in Beaulieu river. Among other things, responsible for design of School of Navigation at Warsash to be started in 1939, a prominent landmark in the east Solent; numerous schools for Essex, Worcestershire, Berkshire, Southampton, London and Waisall. At present working on science and technical college buildings at Reddich, Loughborough and the University of Durham. He is married with two children. Hu Durlington was educated at Green School, Isleworth, and graduated in history at Reading University. She worked on the Survey of London until 1953, wrote four of the volumes, and has been responsible for research work for commemorative plaques in London. She is now head liberain and archivist to the London County Council.

SUBSCRIPTION RATE: The annual post free subscription rate, payable in advance, is 23 3s. 0d. sterling, in U.S.A. and Canada \$10.50, in Italy Lire 6940, elsewhere abroad 23 10s. 0d. Italian subscription agents: A. Salto, Via Sunto Spirito 14, Milano; Librerie Dedalo, Via Barberini 75-77, Roma. An index is issued halfyearly and is published as a supplement to the REVIEW.

ARCHITECTURAL REVIEW

9-13 Queen Anne's Gate, Westminster, SW1 . Whitehall 0611

SHILLINGS



As Mr. Robson points out in the article which begins below, the Solent is a place for yachting, and much of its future as a national water-park depends on the way its shore-based facilities for yachting are handled. Though these can be very various, Gordon Cullen's drawing opposite shows the existing basic type, which needs revitalization rather than reform—the busy, easygoing multi-purpose harbour such as Lymington, with its forests of masts and rigging and its buildings squatting comfortably and naturally between the green shore and the water. The map on page 152 shows the location of the Solent.

Geoffrey Robson

and the second second second second and the second second

## SOLENT

#### A NATIONAL WATER-PARK BEFORE IT'S TOO LATE

The Solent is the stretch of water between the Isle of Wight and the Hampshire mainland, bounded on the west by the narrows between Hurst Castle and the forts to the west of Yarmouth, and on the east by the forts protecting the entrance to Portsmouth and Southampton Water. It is not merely the only large expanse of sheltered deep water on the south coast of England, but its shores are the only 'undeveloped' piece of coastline between Margate and Swanage. They have remained 'undeveloped' so far as the result of a combination of circumstances. On the mainland between Calshot and the Hurst narrows the shores are muddy and shallow and are not immediately tempting to the bather, nor easily approachable by boat. Extensive marshes and the deep inlets of Lymington and Beaulieu rivers have discouraged road building and development of the coast, and the big landowners who control the Solent shores and the land on either bank of the Beaulieu river have managed to restrict building and prevent access to the shores, to a certain extent because of the absence of temptation and acute financial need. There is no doubt, however, that without the benevolent influence of private landowners -which cannot be guaranteed to last indefinitely-the northern shores of the Solent might now be as hideous as Hayling Island, and Beaulieu river might be much like the Thames near Maidenhead.

On the Island shore the deep inlets of the Newtown and Medina rivers have forced the main roads away from the coasts, and from Yarmouth in the west to Ryde in the east there is little building on the coast, except at Gurnard Bay and Cowes, and farmland and large estates such as Osborne come down to the low cliffs. The shores of the Isle of Wight already developed for mass amusement are confined to the western end—Colwell and Totland Bays and the south-eastern shores from Sandown to Ventnor, where cliffs,

sandy beaches, and the brisk channel sea provide the conventional requirements for a family holiday.

The shores of Southampton Water are already so far gone towards industrialization that it is difficult to suggest any remedy; on the west, Ower and Ashlett creeks are now useless to yachts as a result of the Fawley refinery, though Ashlett is now the headquarters of the Esso sailing club. On the eastern side, the Hamble river, which probably holds the greatest concentration of moorings, yachtyards, and boat builders in Britain, is now almost unbearable as the result of the stench and noise from Fawley, and the possibility of another large refinery at Hook, on the rather unattractive shores southeast of the Hamble, may drive yachtsmen to other, already overcrowded harbours. The question of policy involved in siting a second oil refinery in this area does not concern us, nor the difficulties of dredging berths for large tankers at long piers in shoal water on a comparatively unsheltered shore; to the sophisticated eye another refinery, such as the one at Fawley, might improve this rather dismal shore as seen from a mile or so on the water. We must assume, however, that anyone who enjoys this more than the sight of wooded shores or marshes can enjoy himself on the upper Thames estuary, or on countless other industrialized rivers, for although there are no practicable harbours between the Hamble and Portsmouth, and the chimneys and cranes of Gosport lie in the background, there is no doubt that a refinery at Hook on the scale of Fawley would effectively ruin the present predominantly rural character of the Solent shores.

This is the picture which presents itself today. The real threat—as it exists over the whole country—is the tendency to spread development thinly over the whole area; the same tendency which results in ribbon development, and tempts the house builder always to add one more house to the 'unspoilt countryside'; and is in its way more destructive even than the unconsidered siting of a large industrial plant.

As an awful example of the ruination of a large area by a single building we have only to sail thirty miles west to Poole Harbour. The view from the old quay at sunset, over Brownsea Island and the Purbeck Hills is one of the most splendid in the south of England. From the water itself the sun lights up Hamworthy power station which, though in itself no worse and no better than scores of monumental pieces of nonsense, strikes a note of pure horror in this particular landscape. The cranes, elevators and chimneys of Poole itself, though squalid and Heath Robinson, are acceptable as part of the little com-mercial port, but from almost any part of this great harbour the power house now seems to dominate the landscape. In the far greater expanse of the Solent another oil refinery on the Gosport peninsula might not be so disastrous, but any large-scale building on the mainland or island shores, in the comparatively narrow waters of the Solent proper, would have a similar effect. The few existing houses seen against a background of woods provide an interesting punctuation to the shore, but any slackening of the present private control would lead to road building, and in rapid sequence tree felling, wirescape, beach kiosks, and a line of chromium plate and cellulose from Needsoar Point to

It may be thought that I imply that

the purpose of the shore is to provide a pastoral backcloth for the activities of the wealthy yachtsmen, and incidentally to preserve the privacy of the few fortunate people who own houses on the sea. Without some form of control, combined with practical assistance to the present landowners, these fortunate people will eventually share the fate of thousands of others and find themselves engulfed in a sea of new houses in which none will obtain any real pleasure or privacy. The wealthy yachtsman is almost as rare as the Daily-Worker-cartoon motorist, top-hatted and Rolls Royced, and yachting is almost a national sport, enjoyed probably by far more people than the ramblers and climbers for whom the wilder areas of the national parks are preserved. It is one of the many curiosities of the times that people who travel everywhere by car and bus still refer to motorists as 'them,' and that ownership of a 'yacht'-which today may mean anything from a ten-foot dinghy to a fifty-year-old five-tonner, the one built at home for the cost of a clubman's bicycle, and the other bought and maintained by its owner for far less than the cost of a second-hand 'weekend' car-implies membership of a wealthy and privileged class. It must be realized that a very large number of people enjoy themselves on the water in a remarkable variety of ways, and that the Solent being

the only large stretch of sheltered water on the south coast within a reasonable distance of London should be not merely preserved but that some positive action should be taken to enhance its different attributes.

To continue the analogy existing national parks, which are all considered from the viewpoint of the landsman, it is important that an area like the Solent should be preserved and developed for people who are willing and able to exert themselves to gain their weekend and holiday pleasures; the public for whom a national park is preserved are those who want to walk-cycle-or sailnot those who are satisfied to see the view from the inside of a car in a strategically placed car park. The hikers, ramblers, and campers may be equated to the day dinghy sailors, who may run their boat ashore at night and sleep under an awning, the people with small cruisers who want to explore the creeks and secluded harbours, fish, or watch bird life in Newtown or Beaulieu. Apart from these, there are the people to whom yachting means racing, from dinghy racing in the rivers to short passage races in cruising boats, and one must not forget the charabane tourist—the cruisers and pleasure steamers.

To a certain extent all these people use

To a certain extent all these people use all the Solent and its harbours, but certain places are more attractive to one type than

## The Solent: a chart of spoortunity and danger.



## The Solent: variation of character.

this is Posle Harbour, a microsom of the Solent; opposite and examples taken from the whole area.




right: Posle Yacht Club left: Cover Yachtlub Power Station: Porla Lymington, left. the Horizow.

## The Solent: a National Park.







1 Beautice River



Buckley Hard &

1 Porte Yacht Club

Hamble River T

1 From Exbury





The Architectural Review, September 1958 continued from p. 146

to another. The family with the old cruising boat are happy in a quiet creek, where they might have to row half a mile and walk another mile if they wanted to find a shop or a drink. The danger is that the quiet creek may be invaded from the land by caravanners or weekend bungalows, or from the sea by yachtsmen who are unable to find moorings in more sociable waters, and who will create the demand for shops, water, petrol, landing stages, roads, car parks, and so on. A great many people are prepared to walk twenty miles or to put up with considerable physical dis-comfort to sleep in places—on moors or in muddy creeks—the attraction of which will not survive being made accessible and convenient. At least half the pleasure of sailing is that of getting to an anchorage after maybe hours of being wet, cold, and possibly frightened, but whilst one man looks forward to an evening in the bar of a yacht club, another wants the silence of a marshy creek.

Such places exist round the Solent and the purpose of control must be to develop and enlarge the more lively and urban harbours to improve their facilities and greatly increase the number of mooring, and at the same time strictly to preserve the undeveloped harbours for those who are prepared to sacrifice comfort and convenience for the sake of quiet and

completely rural surroundings.

If we ignore the eastern shores, and Hamble river, which could hardly be more highly developed, the principal town harbours are Lymington, Yarmouth and, of course, Cowes. Yachting, which is now a very different thing from the brassbound social activity of Edwardian times exists amongst the ruins of scores of decayed commercial harbours, once busy with small coasting ketches and schooners, very much as in London a dozen families live like mice in the great rooms of one Victorian middle-class house. Lymington was an important port in the Middle Ages, and was used by large coasting vessels until the end of the nineteenth century. As the result of damming the waters of the river, and building a railway bridge to the Isle of Wight ferry station in the late nineteenth century, the natural scouring effect of the river has been destroyed, and it is now used with difficulty by yachts and the shallow ferries, navigable only by courtesy of British Railways who dredge a narrow channel.

Yarmouth is largely artificial and could only be extended at considerable cost, whilst Cowes, which is a good natural small-ship harbour, is already crowded; though in spite of the fact that it is more closely associated with yachting in the grand manner than any town in the world, it is in many ways rather squalid, and the humble sailor who has to row his own dinghy ashore, has difficulty in finding a landing stage or a place to fill his water cans, if he is a stranger to the town. The development of a welcoming waterfront and good public landing stages would obviously be beyond the scope of any national park authority, and I understand that Cowes itself has seen the desirability of some improvement.

The only other harbour which might

be developed as a 'sociable' anchorage, with all facilities for the smaller cruisers and dinghy sailors, is Keyhaven. This curious creek, running in behind the gravel spit of Hurst Castle which guards the narrows at the western end of the Solent, must once have had a strange and fascinating atmosphere, protected from the westerly gales only by low bulwarks of shingle. The one boatyard which serves the harbour is too small to deal with the number of boats at Keyhaven, and most major yard jobs go to Lymington or one of the larger harbours.

Much as most yachtsmen dislike the idea of planning, in a vague and rather sentimental way, there is no doubt at all that a competent authority, representing all the interests—urban, rural and industrial, the yachtsman, "fisherman, and birdwatcher, and the businesses which minister to them, could not only preserve what is left of the undeveloped coastline and the quiet creeks and harbours, but could do so without hardship to anybody by concentrating and developing mooring, landing, and boatyard facilities in one or two harbours, so as to eliminate the temptation for anyone to commercialize

the others.

The policy which we should expect the

Controlling Authority to pursue would include the following main points.

(i) Strict control—if not prohibition—of building on both sides of the Solent—from Yarmouth to Cowes, and if possible the coasts from Cowes to Ryde, and from Keyhaven to Hillhead on the mainland.

(ii) The establishment of a public shore walk along the shores over the same length of coast. Owing to the deep inlets of Lymington and Beaulieu on the mainland, and Newtown, Cowes and Wooton on the Island, it is not likely that these walks would flood the shores with family parties with karricots and gramophones.

parties with karricots and gramophones.
(iii) At two points, inaccessible from the land by public road, the equivalent of youth hostels should be set up, to cater only for day dinghy sailors; this could deal with the problems of young (or for that matter old) people who can neither afford a cruising boat nor hotel accommodation but who need a home base. This should provide cheap storage for dinghies and facilities for working on them winter and summer, and should be open only to people who own and sail them. The traditional yacht club tends to be a social centre for the neighbourhood, in which the bar is the most active room, and many of the members join either for the sake of organized dinghy racing or because it is a pleasantly situated social club. It still has its place, but it is unfortunate that it tends to perpetuate the idea of yachting as a rich man's sport, however difficult to maintain the illusion may be.

(iv) To assist the various local authorities and landowners responsible for the upkeep of the various harbours, by advising on the development of each centre with a full knowledge of the overall situation, and by grants or short-term loans to enable local authorities to improve their harbours for the yachtsman. Although to a certain extent this is a national responsibility, as is the preserva-

tion of Snowdonia or the Lake District, there is every reason to expect the yachting harbours to be self-supporting if they are properly managed, the difficulties generally being caused by inertia or lack of capital.

(v) To control—not prohibit—the growth of suitable industries in the designated areas, both on the Island and the mainland. The most difficult task for yachtyards, chandlers, and the other businesses catering for the yachtsman, is to maintain a reasonable volume of work all the year round. The yachtsman still expects his boat to be fitted out and expects his boat to be litted out and as all the other boats (or preferably rather earlier) and to have odd repairs carried out during the scason, without much thought about what the boatyard is doing in between times. The harbour authorities in between times. The harbour authoritics draw fees for moorings which cover the cost of maintaining (in some cases quite inadequately) the banks, buoying and perhaps lighting of the river, but in several cases the only convenient landing places and other facilities are provided quite independently by a yacht club. It is almost impossible for a yachtyard to remain solvent, unless it combines its parmal maintenance work with boat normal maintenance work with boat building contracts which will keep it going during the season and the slack winter months. Only yards which combine com-mercial or Admiralty work with yacht maintenance can hope to keep a regular flow of work and by and large the yachtsman must either pay an economic price for the work which is done to enable him to enjoy his sailing, or facilities should be provided by the local authorities who obtain a very large return, directly or indirectly (not merely in mooring dues but in trade brought to the towns) from the summer yachtsman, to enable them to lay up boats and if they wish to work on them out of the season.

To suggest in more detail the policy which should be adopted in the various existing creeks and harbours, we should start with Keyhaven and work eastward

along the mainland shore.

Keyhaven: With a limited amount of dredging Keyhaven could accommodate a very large number of small and medium sized cruising boats and the construction of a 'training wall' at the entranee might improve the scouring of the channel. As it is the one harbour in the Solent which could be developed extensively without any great loss to the lover of solitude, the local authority might be advised and assisted in the provision of moorings, landing stages, slipways and all the minor facilities—water, petrol, etc., and possibly the establishment of a boatyard which could be leased for private management. It would also be an excellent position for the establishment of a 'youth hostel' sailing club, which might be zun by the local authority with the guidance of the Park Authority.

Park Authority.

Lymington: Lymington is a delightful town with an interesting community, containing a fair amount of light industry, but owing a lot to yachting for its prosperity. It has lost a great deal through sheer inertia and shortsightedness, and of course the complete cessation of yacht-

ing in two wars; thirty years ago there were moorings capable of taking large yachts close inshore above the yacht club, where the river is now completely silted up. It is too much to hope for the removal of the railway bridge which cuts off a large section of the river, but dredging the river at least as far as the bridge could not only increase the space available for moorings by nearly 100 per cent, but would increase the scour on the ebb and help to keep a deep channel in the lower reaches. The habit of dredging only the lower reaches of a river encourages silting elsewhere and consequently redoubles the need for dredging lower down. Although it is not such a simple problem as in the tideless Mediterranean, with the moderate rise and fall in this part of the Solent (at Lymington it is only 8 feet at spring tides, and at neaps the rise and fall is sometimes hardly visible) some form of mooring fore and aft to a quay and mooring buoys could be adopted, and the whole frontage to the public ground north of the yacht club laid out as a harbour frontage. In addition to this, the lakes to the south of the yacht club, at least one of which could take quite large vessels at high water in the thirties, could be dredged and cleared of the encroaching mud. By the con-struction of a lock a non-tidal Marina could be formed, capable of holding as many yachts as the river itself does at present. There is little doubt that the capital cost would yield a handsome return, and a scheme like this could be self-supporting. Whilst the individualist yachtsman is prepared to put up with great discomfort and hardship for the sake of solitude, the man who enjoys mooring in a crowded river for the sake of company is prepared to pay for his plea-sure, and can reasonably expect somewhere convenient to tie up, fill up with water, dispose of his rubbish and get ashore for a drink. The development of Lymington and Keyhaven would reduce the pressure on Beaulieu river, which at least in its lower reaches should be left untouched. It is at present preserved by a benevolent aristocracy, and the results -whether the motives are selfish or altruistic—are excellent. The river is certainly the most beautiful navigable river east of the Dart, and apart from adding a few more pile moorings and providing reasonable car parking space off the river front at Gins Farm—for mooring owners-it should be preserved

On the Island shore, Wooton is one of

the pleasanter little harbours which is unfortunately becoming rather squalid as the result of uncontrolled dumping of old hulls on the banks, for use as houseboats. We do not suggest that this should be prohibited, but if it is accepted better provision should be made for mooring, access, refuse disposal, etc., and here again by more intelligent control of the upper waters and occasional dredging, moorings could be considerably increased without spoiling the river in any way. Wooton is controlled by the Queen's Harbour Master at Portsmouth, whose main aim is presumably to keep a clear channel for the Portsmouth ferry which berths near the entrance, but a private association with Wooton Creek Association controls moorings and navigation in the creek itself. The Association, through their own Harbour Master, Mr. Young, do an excellent job under difficult circumstances, but obviously require more financial support. It is not possible indefinitely to make do with the wreckage of old landing stages and to hold up crumbling banks which have had no real maintenance since the days when these creeks and harbours were used commercially.

Cowes itself could hardly come within the sphere of influence of a National Parks Authority, but the impression given is that it is still thinking in terms of the so-called great-days of yachting; given a very small expenditure on landing stages and water taps, many more small yachts would use the upper reaches of the Medina river in spite of the shoal water. Although it is considerably shorter than the Beaulieu river very few yachts penetrate as far as Newport, which in the old days was regularly used by sailing barges and small coastal ketches. Given a few more spare moorings, it would be possible for such a harbour to be rather more welcoming to the easual visitor and to offer some more incentive to him to come ashore and spend money in the town.

Farther west, Newtown is the only completely undeveloped creek in the Solent (if one disregards Pylewell, which is really only a swashway into Lymington). We should hope that really firm action would be taken to preserve it as it is, and that the provision of extra moorings elsewhere would reduce the likelihood of yachtsmen coming to Newtown for permanent moorings. As a relie of an ancient harbour (Newtown itself, now only a few cottages, was in the early Middle Ages the 'capital' of the Isle of Wight) it is of great interest, and surrounded as it is by

farmland, accessible only by a rough track, it is the perfect natural harbour. During Cowes week owing to the shortage of moorings elsewhere, it is as full as a cinema car park; the air is full of hearty voices cursing the next boat for anchoring too close, and the effect seems almost sacrilegious, like using a cathedral as a garage. Provided that the Association which preserves the harbour can be backed by authority, its character can be retained, and we do not think it is only selfishness on the part of the yachtsman which would condemn the slowly spreading caravan settlement at the head of the creek. The land round the lower stretches of the harbour is fortunately so difficult of access that it is unlikely to be 'developed' in this way, and by an absolute prohibition on providing petrol or even water supplies to the landing stage (however desirable that may seem at times) the harbour will remain a refuge for the comparatively small number of people who are prepared to row and walk for their supplies and who can get on very well without a club bar for a night or so.


Yarmouth within its limits is very well developed and managed, and it would be difficult to propose any great improve-ments. The general aim, therefore, should be to develop (more by intelligent cooperation between the various authorities and landowners than by any drastic control from above) the facilities of the various creeks and harbours so that their present characteristics become more marked, and in a way more specialized, so that a particular harbour will appeal more strongly to a particular type— Lymington, Yarmouth, Cowes and possibly Keyhaven to the man who enjoys company and (as far as is compatible with yachting) comfort and convenience; Newtown and the lower reaches of Beaulieu river to those who enjoy solitude and the company of herons and oystercatchers; and Wooton creek and the upper reaches of Beaulieu to the family cruising man, who enjoys something in between the two extremes. The present state is not so far from the ideal, and a certain amount of unobtrusive planning can perfect it, but without this the Solent shores and harbours will almost imperceptibly slip into the long chain of suburban development which extends for nearly 200 miles along the coast. Unlike the existing national parks, the Solent is in effect an arterial road running through unspoilt country; if we are not prepared actively to preserve this it can become another Kingston-By-Pass.



### offices at bermercham

ERNO GOLDFINGER

ARCHITECT



l, south front of the factory offices at Shirley. The parked cars stand on land which will later be a garden.

A STATE OF THE PARTY OF THE







#### OFFICES AT BIRMINGHAM


2. the external spiral staircase on the east gable is of precast concrete. 3. general view of the south front, with the offices carried on columns above the open ground floor. 4.5. the architect's working drawings, showing sections and parts of the elevations.














D feet











OFFICES AT BIRMINGHAM 10, the internal staircase. 11, the west elevation showing the pattern formed on the concrete by the shuttering. the pattern formed on the concrete by the shuttering.

12. the main entrance, enclosed by plate glass screens, with an armourplate door. The floor is of green marble.

13. the reception desk in the main entrance hall.



12 13

This office block at Shirley adjoins the main factory, but was designed as a separate prestige building with landscaping, including an ornamental pool. The offices are all grouped on the two upper floors carried on concrete columns and only connected with the ground floor by the staircase and lift. The ground-floor entrance and reception hall has a green marble floor and a wall of wax-polished Zebrano panelling, and is enclosed by plate-glass screens with an armourplate main door. The ground floor also accommodates kitchen and cloakrooms.

The first floor has a conference room, secretary's room and offices; on the second floor are the managing director's offices, board room and directors' suite, with a kitchen and small conference room. On the third floor is a recreation room opening on to the roof terrace, and the lift-motor room, tank room and document store form a small square block above roof level.



The building has been designed on a 2 ft. 9 in. basic grid and the construction is in situ reinforced concrete with piled foundations and prestressed suspended floors, All structural concrete is exposed, and on the east and west gable wall the aggregate is exposed and patterned by the shuttering. There is an external spiral staircase of reinforced concrete. The floors in the first-floor offices are of thermoplastic tiles, on the second floor they are cork tiles and in the recreation room black quarry tiles.

Heating is by means of calorifiers supplied by the factory boiler-house, heating convectors and some radiators on the ground floor, and a calorifier also provides hot water. Vertical services are housed in ducts in the columns. All windows on the south and north are designed with photobolic screens\* to give greater daylight penetration.

Top lights set back behind a white-painted ledge. See 'Offices in Albemarle Street,'
AR February, 1958, page 119.







The flat saucer dome of the Breakfast Room in Sir John Soane's Museum is an early, but significant, break with the tradition of the ceiling as a monolithic closure — light wells between the vault and the wall imply another cover at a higher level, as with the ceiling of Philip Johnson's Port Chester synagogue, below. The structural status of Soane's ceiling is arguable, but Johnson's is emphatically a suspended ceiling of the sort discussed in Michael Brawne's article, opposite.





## LOOKING UP

#### SUSPENDED CEILINGS AS AN ELEMENT IN INTERIOR DESIGN

When it became necessary to house the convolutions of pipes and ducts which form the heating, cooling, ventilating, lighting, communication and fire protection systems inevitable in even so simple a space as that enclosing a dozen young women typing and telephoning, it soon became obvious that the ceiling was the only place for them. The inevitable result was visual chaos. It was found, however, that the confusion could easily be obliterated by a suspended membrane which, conveniently, was also able to reduce the general noise level. The suspended ceiling, as we know it, thus became a new and accepted building element; the easy answer to a series of complex and related problems. Until its advent, the surface overhead had often been dramatic and decorative: mosaic and fresco, pompeian plaster and lincrusta. There is, of course, no reason why the provision of services and visual pleasure should be mutually exclusive, although rather too many buildings testify to the contrary. It would seem that too frequently the care given to the ceiling has not gone beyond making sure that the different parts from the catalogue fit together. The purpose of this article (and, indeed, of the two articles on 'Suspended Ceilings' in the Skill section which should be read in conjunction with it\*) is therefore to draw attention to a neglected surface. The ceiling is, after all, an important part of the visual field; in the past it has in fact been accepted as giving the architect one of the most challenging opportunities. Today others certainly think this. A glance at the rich variety of products made for ceilings displayed in the Skill articles on Suspended Ceilings shows that this section of the building attracts a great deal of commercial attention, much of it well conceived. There is, evidently, money in the ceiling. Yet even the best products fail to give that lasting satisfaction which is felt when a building form achieves the level of architecture; nor, it would appear, when the

<sup>\*</sup> The first of these appeared in the July AR, page 59; the second is to be found on page 201 of this issue.

matter is looked at carefully, is the functional performance of these ceilings as high as one might expect. These two aspects, though distinct, go hand in hand; and perhaps the ceiling will not perform visually or functionally as it should, until it is considered as an important and form-giving element of each design.


The multi-storey office block poses the problems of the suspended ceiling in its commonest form. The expensive and therefore overcrowded floorspaces obstructed by office paraphernalia, the outer walls pierced by windows, the inner walls non-existent or forever moving as staff groups and re-groups, only the ceiling remains to provide a standard of environmental comfort which may have to be of a relatively high order. Visual tasks may be exacting requiring both high levels of illumination and lack of contrast between task, surround and light source; the noise produced may be considerable and will need reduction for reasons of comfort and communication; winter heating will be essential but will only be needed for about eight hours a day; summer cooling may be necessary especially as intense light sources and electric business machines add to the heat and even such sedentary exertions as typing soon become uncomfortable. Apart from this, ventilation must be adequate to cope with tobacco and humanity. These are the relatively simple criteria of an office space. Laboratories, shops, restaurants and so on each create their own specialized conditions.

The choice of ceiling material, shape and construction is dependent on the methods used to provide this environmental control and itself considerably influences them. It should not therefore be undertaken haphazardly. 12 in. by 12 in. perforated fibre tiles on a 'patented' suspension system are seldom the only, and rarely a sufficient answer.

The great danger inherent in an architecture assembled from factory-made components is that

each set of elements, whether it be the curtain wall, the suspended ceiling or the movable partition, can so easily be considered in isolation. Yet the effect of these elements on each other and the building as a whole should not be underrated. Their relation is not only one of simple dimensional co-ordination, it is more fundamental than that.

Suspended ceilings, for example, are normally considered as obvious sources of artificial light. But it ought not to be forgotten that any ceiling surface will also influence the natural light conditions of an area receiv-



1, the additive architecture of the 'Unistrut' Experimental Building at the Michigan University: additive space can, through the repetition of similar materials within a strictly coordinated structure, create the unity aimed at in curvilinear spaces as 21.


ing daylight. The reflective factor of luminous ceilings with plastic eggerates, to take a common form, may be extremely low. Such a room will thus appear unnecessarily dark unless the lights are turned on. Similarly a ceiling composed of vertical fins or coffered recesses with luminous inserts will create large areas of shadow. Evidently certain forms of luminous ceiling demand that, once installed, they are used continually. This in turn poses the question that if illumination is to be provided entirely by artificial light, what reliance should in fact be placed on daylight? Even if for psychological reasons some kind of outlook is thought advisable, this may well take a quite different form from the transparency necessary for efficient daylighting. Thus the seemingly simple choice of a particular suspended ceiling has serious repercussions on the treatment of the elevation.

If, moreover, the gap between a louvred ceiling and the underside of the structural slab is a continuous open space (i.e. to house lamps and heating ducts) or itself acts as a plenum, partitions will fail to act as sound barriers. The main function of rigid partitions having thus been lost, it seems questionable whether they need be retained. If office space is not to be subdivided and if there is no need to rely on daylight for illumination, the traditional shallow arrangement on either side of a corridor will no longer be necessary. Much deeper undivided areas become the logical answer. These will in turn demand artificial ventilation which will itself modify the design of the suspended ceiling. The luminous ceiling, therefore, not only suggests certain elevational criteria, but also radically amends the plan form and service installation of the building.

Certain recent offices in the United States and elsewhere have accepted these conclusions. Except for shops, complete reliance on a luminous ceiling is, as yet, infrequent in this country. The suspended ceiling is thought of primarily as a sound absorbent area; but here again, choice is not merely a matter of deciding between dots, stripes and a travertine finish.


Sound absorption to be effective can only be determined when the use of the space is known. A suspended ceiling over the workshop floor of a factory may be far from helpful if its absorption coefficient is low for the particular frequencies at which the machine noise is loudest. The value of the absorption coefficient at 128 cycles, a value which will almost certainly be critical, can vary between .09 and .53 for a perforated cane fibre tile depending on its thickness and mounting. The too frequent reference to coefficients at 512 cycles may be a useful shorthand but it may also be very misleading.

Precise function is just as important a determinant in an office building—the private office, the conference room and the clerical space each demand separate treatment. In the private office there will probably be



the additive ceiling at its most basic— 2, Skidmore, Owings and Merrill's Connecticut General Life Insurance Company where ducts, lights and services are concealed by a deep grid.

3, Finn Juhl's Trusteeship Council Chamber at the UN where the service elements form a coloured three-dimensional pattern which becomes a dominant and lively feature of the room. Both examples make a virtue of





The depth needed to house the equipment and create a new spatial effect the pergola brought indoors.
6. Studio Valle's Bank at Udine has translucent honeycomb diffusers added to the bottom chord of a space frame and these act as luminous ceiling both 4, during the

day, and 5, at night, yet still reveal the intricacies of structure.
7. Saarinen's G.M. Technical Center, Michigan, has an elegant 'universal' service ceiling, developed with the Wakefield Lighting Co.
8, the entrance hall at 383 Madison Avenue,



#### looking up





NY, gives more rapid and less subtle variations by changing the colour of the light behind different areas of the ceiling.

9, Skidmore, Owings and Merrill's Manufacturers' Trust Bank, NY, successfully

combines a high level of general illumina-tion with directional lighting for Bertoia's

gilt screen.
10, timber ceiling by Hiroshe Ohe in the Miki Building, Tokyo and,

11, by Breuer in the Bijenkorf, Rotterdam, where the lighting within the deep fixed grid is related to sales areas.
12, a suspended ceiling at G.M. Technical Center shows the application of the pressed





#### looking up














15, Vernon Russell's cafeteria at the Lockheed Factory in California, an attempt to give sculptural feeling to the ceiling with simple elements, in 15, merely asbestos sheets, web joists, sprinkler heads and lights.

16, conference hall by Aldo della Rocca in Rome, where the limits of space are con-fused by glare and the irregularity of the ceiling formed by the random juxtaposition of different elements.



17, Ford Motor Car Central Office Building. Dearborn, where more complex patterns are achieved by the regular intertwining of identical units. 18, the entrance hall of the Tishman

Building, Fifth Avenue, NY, by Carson and Lundin, has a ceiling of cloud-like metal fins by Noguchi which are a highly successful excursion of a sculptor into industrial design.

19, the lobby of the Alcoa Building, Pittsburgh, by Harrison and Abramowitz; the suspended aluminium mesh is also an early attempt at the dapple effect now so often used by Edward Stone.



The suspended ceiling, although technically always an added element, need not be left out in the early consideration of the room.

'20, Knoll Showroom, Milan, with its folded planes over an equally divided room.

21, World House Gallery, New York, by

Kiesler and Bartos. 22. Bank at Tulsa, Oklahoma, by Carson,

22. Bank at Passa, Okaaoma, oy Carson, and Lundin. 23. Philip Johnson's Guest House, New Canaan, Conn. 24. Tea Bar, Lower Regent Street, by the

Design Research Unit. 21 and 23 demonstrate that wall and sus-pended ceiling can achieve a sculptural unity which becomes the regulating element of the

continued from page 162]


little need for absorbing any of the sound generated within the room. Design must concentrate on excluding noise from neighbouring areas. Such sound reduction can only be achieved by mass and the blocking of all connecting air spaces. Partitions must either be taken up to the underside of the structural slab and fit tightly or the suspended ceiling must be composed of relatively heavy sound reducing elements. The difference between the average noise level in a large office and that acceptable in a private room may be 20 to 25 decibels. Sound absorption of this order is unlikely to be achieved by a rigid vinyl diffuser or in. thick cane fibre, but could, for example, be realized by suspending sheets of 32 oz. glass with their edges sealed. In the conference room sound absorption will most likely be provided by a carpeted floor and wall linings and the ceiling may have to be of a reflective material; it may also be advisable for this surface to be facetted so as to diffuse sound.

The most complex problem occurs in the general office space. Here two criteria ought really to be satisfied: the general noise level, and particularly noises at some distance, should be reduced; but at the same time the level of speech must not be lowered to the extent that it is overlaid by the background noise. Unfortunately the flat ceiling of absorbent material tends to work against these conditions, since the degree of absorption is proportional to the angle of incidence of the sound wave. In other words, the ceiling will be most efficient in relation to noise directly underneath it and least efficient in relation to distant noises hitting it obliquely—a situation, the reverse of the ideal. This problem can be overcome by turning the absorbent material through 90° and suspending it as a series of fins. Saarinen's General Motors Technical Center, 7, and Skidmore, Owings and Merrill's Connecticut General Insurance Building, 2, have adopted this solution with results which seem both visually and functionally highly successful. The suspended fins can also act as light baffles and, in the case of Connecticut General, actually provide sufficient visual cut-off to conceal service runs. In view of the simplicity and usefulness of this arrangement it seems surprising that it has not yet been used in this country.

So far the suspended ceiling has only been discussed in terms of certain notions about light and sound. It has often, however, to perform tasks in connection with heating and ventilation either separately or simultaneously with the first two. The ceiling developed in conjunction with the Wakefield Lighting Company for General Motors Technical Center incorporates luminous panels, sound absorbent baffles, airconditioning outlets, fire sprinklers and partition fixings and is probably the best co-ordinated building element available 'off-the-peg.' The apparently divergent demands of these separate functions need not, it

would seem, conflict.

Some suspended ceilings, like Aalto's delightful inverted trays at the Social Security Building in Helsinki, 25, concentrate on fulfilling only one function, in this case radiant heating. Others like the standard suspended ceiling of perforated metal tiles combine heating and ventilation with some sound absorption





25, restaurant at the Social Security Building, Helsinki by Aalto.


though, of course, sound isolation becomes impossible since the whole of the hollow space between ceiling and slab is used to convey hot air. The merits of using the overhead plane as a heating element are debatable since the desirable heating gradient assumes greatest warmth at floor level. The reverse naturally applies if summer cooling is considered and the ceiling is, therefore, an excellent location for air diffusers or radiant cooling panels. The functional complexity of such multi-purpose ceilings need in no way be a justification for second-rate solutions; it can, on the contrary, if treated with wit, create the sort of visual richness which Finn Juhl achieved in the Trusteeship Council Chamber at the U.N., 3.

The problems of the suspended ceiling are impossible to treat in isolation, for not only is the ceiling itself frequently an intricate combination of several functions, but there is also a continual reference back to the basic assumptions governing the building: to plan form, to structural choice and economy in relation to the depth given up to the ceiling, to cladding, to space sub-division, to maintenance and fire protection. On some of these aspects the architect is able to get specialist advice, though the number of such consultants in this country independent of particular business organizations is relatively small. The meshing of the separate and possibly conflicting advice given by these consultants is still the architect's responsibility. In the last resort it should, perhaps, always remain so. But there does seem a place for a group practice covering the whole range of specialist fields which could advise an architect at the earliest possible stage of design on the implications of the alternative choices. It is this sort of fundamental advice which it is so hard to get at the moment.

The most encouraging recent development in the use of suspended ceilings has not been the refinement of technique—radical technical changes await the commercial introduction of such devices as electroluminescence—but the marked extension of its visual vocabulary. This extension has been brought about by the belated awareness that a suspended ceiling is not







26, entrance hall, Yale Art Gallery, by Louis Kahn. 27, bank at Udine by Studio Valle, during construction. 28, auditorium at the Fine Arts Center of the University of Arkansas by Edward Stone.

an imitation plaster surface with a smooth trowelled finish, but more often an assembly of a large number of separate pieces and that these pieces have an expressive quality in their own right which can easily be exploited. (To get such an assembly absolutely flat and aligned has always been rather difficult, particularly if the light sources are very near the ceiling when they turn the slightest imperfection into a noticeable shadow.) The additive nature of the suspended ceiling has now been adequately demonstrated by such examples as Breuer's Bijenkorf, 11, Juhl's Trusteeship Council Chamber or Valle's Bank at Udine, 6. The forms which a ceiling designed on such assumptions can take have hardly been exploited yet. Louis Kahn's concrete tetrahedra at the Yale Art Gallery, 26, though not in any way a suspended ceiling, show a possible line of development. The prefabricated suspended

ceiling—as distinct from the suspended ceiling of plaster or sprayed asbestos—is, like the curtain wall, essentially additive architecture.

There are many approaches to the possiblities and problems of this kind of additive design. The most obvious assembly consists of taking acoustic panels, lights and their supporting grid and letting each stand separately. Breuer's ceiling in Rotterdam or Farmer and Dark's ceiling at Marchwood, belong to this category. At the other end of the scale there is Studio Valle's brilliant device of combining an opal acrylic honevcomb into a ceiling plane and then adding this entire plane to the underside of a complex truss so that structure and ceiling combine to form a shimmering surface overhead. This shimmering effect, as of light coming through moving leaves on a spring day, achieving the apparent paradox of restful excitement, is also the intention of the dapple ceilings with which Edward Stone has recently been experimenting. The courtyard of the U.S. Embassy at Delhi will be covered by necklaces of aluminium discs diffusing the light onto the water garden below. Dapple ceilings do not, however, depend on Indian sunlight. Stone has hung a similar ceiling over an auditorium at the Fine Arts Center of the University of Arkansas and hidden electric lights and ducts behind it, 28.

Together with the appreciation of the additive quality of many factory made ceilings has come the awareness that the suspended ceiling can, whatever its construction, be a form-giving component within the organization of a space. This second discovery may, in the end, prove more important than the first. Phillip Johnson's attenuated and Soanesque vaults in the brick guest house which faces his glass enclosure at New Canaan, Connecticut, 23, were perhaps the first to make this point. Johnson has now used a similarly

taut ceiling in his synagogue at Port Chester, N.Y., where its obviously suspended canopylike nature becomes even clearer. Both these ceilings are, despite their acknowledged superimposed character, controlling elements within each space. The same may be said of the ceilings in the chapels at Brandeis, 29, the Knoll Showrooms in Milan, 20, and Kiesler's World House Gallery in New York, 21, where suspended ceiling and suspended wall merge into a continuous flow.



to a continuous flow.

These faceted or

29, Protestant chapel at Brandeis University by Harrison and Abramowitz.

curvilinear forms are evidently part of a new sculptural awareness of space which we are currently experiencing. A new visual feeling often precedes the technical innovation which will in fact make it possible, and it may be, that these moulded ceilings are the fumbling prototypes of forms which will become commonplace in what might perhaps best be termed the 'resin' age.



1. the bell tower, from the churchyard.



#### CHURCH IN STOCKHOLM

This church, about six miles west of the centre of Stockholm, stands on a triangular site with an hotel and bank, and is financed by the rents of the business premises. The buildings are grouped round a church-yard, but only the church and its offshoots have access to it or windows overlooking it. The church seats a congregation of 250 and a choir of 30, and can be extended to include the adjoining parish hall, which accommodates a further 120. The sanctuary, which is dominated by a sgraffito figure of the Good Shepherd, has been designed for the special ceremonies and processions connected with baptism. The candidates enter the church up a flight of stairs from the basement, where they have changed into the white robes worn during the ceremony and attended a preparatory service in a small

circular chapel. The baptismal tank in the centre of the sanctuary is fenced in with large white candles and at the left-hand end is a wooden screen, behind which the candidates leave the church. The exterior is finished in a marble-grained plaster. Internally the walls and roof are plastered, the floor is polished red brick, doors and panelling are of Oregon pine. The benches are of solid Swedish oak with foamed plastic seats. There is no paint in the church, but colour is provided by the red and blue glass of the large triangular window in the sanctuary, which lights the sgraffito mural. The high windows at the back of the church have scattered triangles of yellow glass to give a warmer light during the long winter. The free-standing bell tower is of prestressed concrete beams with an aluminium cross.



2. general view from the south, with shops on the left and the lighted window of the church on the right. In the background, behind the bell tower, is the hotel block.

3. the entrance to the hotel and shops.

4. the bell tower from the west.










5, the churchyard, showing the long stained-glass window which was designed by the architect. 6, the interior, with the sgraffito figure of the Good Shepherd dominating the sanctuary.

#### CHURCH IN STOCKHOLM







1, looking west along the terrace, with the pool below. 2. the basins in the bathroom are set in a marble slab backed by a wall of mirror.



#### HOUSE IN CALIFORNIA

fireplace and have sliding doors and windows opening on to the balcony terrace over the pool. The dining area and kitchen are at a slightly higher level, overlooking the hillside. The bedrooms are at the western end of the house, with two servants' rooms on the lower level, adjoining the pool porch, which also gives access to the changing-rooms and storage space.



### HOUSE IN CALIFORNIA

3, view from the breakfast room, showing the fireplace which is a dominant feature of the plan. The large transparent bubble in the roof gives a view of the treetops.

4, another view of the fireplace, looking towards the terrace and showing one end of the Texas Shellstone slab.



#### the exploring eye

We forget that Euclid was an Egyptian. We tend to think of a single Greek geometry that embraces everything from Paestum to Ptolemy's world map, as static as a statue, without evolution. But Euclid was not born till a century after the Periclean culture that produced Plato and the Parthenon had run aground in a dead end summed up by Professor Ritchie's tart 'intellectual clarity was hardly enough."

Born in Alexandria, Euclid was a member of is renewed every year for the pilgrimage. that Hellenistic culture we are pleased to regard but no square stone in Europe could ever as decadent because not Athenian, and yet it be this shape; even if it were not a perfect stood right in the line of intellectual progress a cornice and a less ambiguos pedistal. from the ancient world to the modern. Yet the The concept 'a square stone' transmits a Roman world found as little use for Euclid's east of Euclids's birthplace in Alexandria. 'Elements' as it did for the amusing toys (such as the steam turbine and the hydraulic engine) of his fellow Alexandrian, Hero.



1. The Black Stone of the Kaa'ba in Mecca, hung in the embroided cloth which It is-by common repute—a square stone, cube it would almost certainly have acquired different visual image in the lands to the

Euclid's ideas went East, to fertilize the nascent culture of Islam, to meet 'arabic' numerals coming up from India, to fall into the hands of mathematicians as subtle as al-Khwarizmi. Finally, the 'Elements' found their way west again through the great chain of mediaeval Muslim universities, and by the Renaissance had improbably taken up position alongside Vitruvius, as the inspiration of a revived ancient culture that neither Greece nor Rome ever knew.

But the classical architecture that we like to think of as Euclidian derives in historical fact from an earlier and cruder concept of geometry, innocent of Euclid until Renaissance humanists got to work on it. The true architecture of Euclid was created to the east of his native Alexandria, and later carried as far as Spain by a culture that was far from Periclean. We, with our Parthenon-style prejudices have been happy to agree with Choisy's snap judgment that the appearance of Muslim architecture is 'capricious,'

We have been less vigorous in pursuing the implications of his second opinion that only a simple law could explain its complexity. Yet such an explanation was produced almost a century ago by Owen Jones, who showed that the 'fantasy' vaults of squinches and pendentives such as appear inside this fold-out, were based, in plan, on a system of simple Euclidian elements-squares, regular triangles-each corbelled out at its base from the one behind. The obviously impossible half-arches that appear to support the edges of the panels do so no more than do the more obviously rational ribs of Gothic vaults; it is an entirely corbelled system, with the bricks laid in flat courses, the arches are pasted on with mortar.





Western geometry at its most forceful, the portal vault of the eighteenth-century Madrasseh Madar-i-Shah, Isfahan. These stalactite or pendentive vaults are found throughout Islam, but reach a particular frenzy and a particular sobriety in the great niches of Isfahan. Even Perpendicular Gothic, Western rationalism on the verge of madness, never achieves the sense-defying

quality of these half-domes that seem, to Western eyes, to cry out for another half to complete and buttress them before they collapse.

3 and 4, the secret of these improbable vaults is that they are not vaults, are not formed of voussoir-shaped stones. They are formed of course upon course of corbelling bricks, organized in squinches apparently for the sake of simplicity in laying out the work (though 2 shows where

that simplicity could end) and guarded against toppling by the great 'proscenium arches' behind which they are built. These are details of the aiwans of the Masjid-i-Jami in Isfahan, built in the fourteenth century.

5 and 6, the extrados of these aiwans laid out plate-over-plate, like the carapace of crustacean, seem to belong to another architecture. Here, a Western eye might believe itself to behold a T






2,3,4














#### the exploring eye

We forget that Euclid was an Egyptian. We tend to think of a single Greek geometry that embraces everything from Paestum to Ptolemy's world map, as static as a statue, without evolution. But Euclid was not born till a century after the Periclean culture that produced Plato and the Parthenon had run aground in a dead end summed up by Professor Ritchie's tart 'intellectual clarity was hardly enough.'

Born in Alexandria, Euclid was a member of is renewed every year for the pilgrimage that Hellenistic culture we are pleased to regard but no square stone in Europe could ever as decadent because not Athenian, and yet it be this shape; even if it were not a perfect stood right in the line of intellectual progress a cornice and a less ambiguos pedistal. from the ancient world to the modern. Yet the The concept 'a square stone transmits a Roman world found as little use for Euclid's east of Euclids's birthplace in Alexandria. 'Elements' as it did for the amusing toys (such as the steam turbine and the

hydraulic engine) of his fellow Alexandrian, Hero.



Black Stone of the Kaa'ba in Mecca, hung in the embroided cloth which It is by common repute a square stone, cube it would almost certainly have acquired different visual image in the lands to the

Euclid's ideas went East, to fertilize the nascent culture of Islam, to meet 'arabic' numerals coming up from India, to fall into the hands of mathematicians as subtle as al-Khwarizmi. Finally, the 'Elements' found their way west again through the great chain of mediaeval Muslim universities, and by the Renaissance had improbably taken up position alongside Vitruvius, as the inspiration of a revived ancient culture that neither Greece nor Rome ever knew.


But the classical architecture that we like to think of as Euclidian derives in historical fact from an earlier and cruder concept of geometry, innocent of Euclid until Renaissance humanists got to work on it. The true architecture of Euclid was created to the east of his native Alexandria, and later carried as far as Spain by a culture that was far from Periclean. We, with our Parthenon-style prejudices have been happy to agree with Choisy's snap judgment that the appearance of Muslim architecture is 'capricious.'

We have been less vigorous in pursuing the implications of his second opinion that only a simple law could explain its complexity. Yet such an explanation was produced almost a century ago by Owen Jones, who showed that the 'fantasy' vaults of squinches and pendentives such as appear inside this fold-out, were based, in plan, on a system of simple Euclidian elements-squares, regular triangles-each corbelled out at its base from the one behind. The obviously impossible half-arches that appear to support the edges of the panels do so no more than do the more obviously rational ribs of Gothic vaults; it is an entirely corbelled system, with the bricks laid in flat courses, the arches are pasted on with mortar.

# a monthly review of interior design

Nottingham University. Co-ordinating interior designer: Sir Hugh Casson. Associate designers: Ward and Austin, Lady Casson. H. T. Cadbury-Brown, John Wright.

Ball pendant chandelier in the ballroom (see page 183).





#### the exploring

We forget that Euclid was an Egyptian. We tend to think of a single Greek geometry that embraces everything from Paestum to Ptolemy's world map, as static as a statue, without evolution. But Euclid was not born till a century after the Periclean culture that produced Plato and the Parthenon had run aground in a dead end summed up by Professor Ritchie's tart 'intellectual clarity was hardly enough.'

Born in Alexandria, Euclid was a member of is renewed every year for the pilgrimage. that Hellenistic culture we are pleased to regard but no square stone in Europe could ever as decadent because not Athenian, and yet it be this shape; even if it were not a perfect stood right in the line of intellectual progress a cornice and a less ambiguos pedistal. from the ancient world to the modern. Yet the The concept 'a square stone' transmits a Roman world found as little use for Euclid's east of Euclide's birthplace in Alexandria.



1. The Black Stone of the Kaa'ba in Mecca, hung in the embroided cloth which It is-by common repute-a square stone, cube it would almost certainly have acquired different visual image in the lands to the

'Elements' as it did for the amusing toys (such as the steam turbine and the hydraulic engine) of his fellow Alexandrian, Hero.

Euclid's ideas went East, to fertilize the nascent culture of Islam, to meet 'arabic' numerals coming up from India, to fall into the hands of mathematicians as subtle as al-Khwarizmi. Finally, the 'Elements' found their way west again through the great chain of mediaeval Muslim universities, and by the Renaissance had improbably taken up position alongside Vitruvius, as the inspiration of a revived ancient culture that neither Greece nor Rome ever knew.

But the classical architecture that we like to think of as Euclidian derives in historical fact from an earlier and cruder concept of geometry, innocent of Euclid until Renaissance humanists got to work on it. The true architecture of Euclid was created to the east of his native Alexandria, and later carried as far as Spain by a culture that was far from Periclean. We, with our Parthenon-style prejudices have been happy to agree with Choisy's snap judgment that the appearance of Muslim architecture is 'capricious.'

We have been less vigorous in pursuing the implications of his second opinion that only a simple law could explain its complexity. Yet such an explanation was produced almost a century ago by Owen Jones, who showed that the 'fantasy' vaults of squinches and pendentives such as appear inside this fold-out, were based, in plan, on a system of simple Euclidian elements-squares, regular triangles-each corbelled out at its base from the one behind. The obviously impossible half-arches that appear to support the edges of the panels do so no more than do the more obviously rational ribs of Gothic vaults; it is an entirely corbelled system, with the bricks laid in flat courses, the arches are pasted on with mortar.

#### **Nottingham University**

The new Portland Building for Nottingham University was designed by Cecil Howitt and Partners. It provides Union offices and recreational and welfare facilities for approximately 2,500 people including staff and students. It is primarily intended for the use of non-resident students.

The interior design of the major rooms was done by various architects with Sir Hugh Casson as Co-ordinating Interior Designer. These rooms include the Portland Lecture Hall and Students' 'browsing' library by Ward and Austin. a series of Common Rooms by Sir Hugh and Margaret Casson, the Department of Fine Art by H. T. Cadbury-Brown, and the Ballroom and Restaurant by John Wright.


2, view of the gallery in the art library designed by H. T. Cadbury-Brown which is reached by a black metal spiral staircase. The gallery handrail is of 3 in o.d. silver anodized aluminium tube. Dark brown hessian lines the walls and is carried up and over a white suspended acoustic ceiling. The Library shelving is black metal. On the right near the entrance is a spiral cluster of white pendant lights.

3. the library table which was specially designed by the architect




and is of ebonized timber with a black tooled leather top. Three inverted saucer-shaped pendant lights hang over the table; they are black metal





26 KITCHEN 27 PRIVATE DINING ROOMS 28 BALLROOM



DI NEIPO WHITTHE PLOOM

I JOINT COMMON ROOM

2 MEN'S DISCONDENSE

3 MAT LIBRARR 8

ART GALLERY

M LECTURE ROOM

19 MIN'S LIDRARR 9

7 JOINT COMMON ROOM

19 WOMEN'S CLOAKS

19 STIDEN'S BROWSING ROOM

20 JUNIOR COMMON ROOM

21 LIBRARY


22 SENIOR COMMON ROOM

23 LADRES QUIET ROOM


24 MOMEN'S COMMON ROOM


24 MOMEN'S COMMON ROOM

24 MOMEN'S COMMON ROOM



- COMMON ROOM
  WOMEN STUDENTS CLOAKS
  COFFEE ROOM
  MEN STUDENTS CLOAKS
  PORTLAND LECTURE HALL
  CAREERS & APPOINTMENTS BOARD
  AND GENERAL OFFICE





with opaque glass baffles. White plastic chairs by Aidron Duckworth have purple seat cushions. The floor is cork tile and is partially covered with a plain yellow carpet.

4. in the restaurant, designed by John Wright, the suspended ceiling of natural cane lattice on timber lit from above, from which ball pendants hang from rods over the alcoves. The whole of the window wall is covered by curtains of a white, red and green French fabric.

5. close up of one of the chrysaline ball pendants.

6, one of the alcoves in the restaurant; they are formed by leather covered banquette seating with cane filled screens above.

view of the restaurant from an ante-room linking it with the ballroom.

8. the ballroom designed by John Wright can be divided in two by plain light blue curtains. This view shows the main area with three 26-light chandeliers with ball pendants designed by the architect. Full length curtains of alternate panels of bright pink and yellow cover the windows and the areas of wall between them. The walls are dark blue, the upholstery is black and brown and black



carpet define the sitting areas around the perimeter of the room. The floor is maple strip.

 another section of the ballroom showing a suspended ceiling of white continuous metal boxes containing painted timber lit from above. The walls are donkey brown and at either







#### Nottingham University



end there is a free-standing panel of wallpaper designed by John Aldridge in brown, blue and white.

10. the plastic 'egg-crate' louvre ceiling in the main art gallery, lit from above with additional roving spotlights which can be fitted anywhere on the grid. To the right are fluorescent tubes suspended from the ceiling to throw light on to the walls.



11, the small art gallery, the walls are covered with natural hessian, and the floor is of 6 in. by 36 in. cork tile strips. The white plastic chair designed by Aidron Duckworth has purple seat cushions.





12. corner of the senior common room. designed by Hugh and Margaret Casson. The curtains are of yellow corded silk and the upholstery is in cinnamon and blue tweeds and black leather.

13. a corner of one of the joint junior common rooms. The black leather settee and imported cane chair are set off against a wallpaper in dark green, black and grey designed by Walter Hoyle.

14. In the Portland Lecture Hall designed by Ward and Austin, one of the wall lights; they are of perforated black metal and are used mainly to give low general light when the epidiascope is used.

15. a view of the lecture hall showing the general lighting effect.



## Offices at Davies St. W.1

architect: J. M. Austin Smith and Partners partner-in-charge: Geoffrey Salmon assistant: Ian Morton-Wright

This is a reconstruction of an existing motor-car repair shop to provide a suite of offices including a reception room. a large general office for 27 clerks and secretaries, five directors' offices, and a small boardroom. A limited budget of approximately £8,000 was allowed. 16, general office seen from recep-

tion room (see also 20).

17. typist desk in the general office. All office furniture is designed by the architect and is built up from metal frames of 1½ in. by ¾ in. mild steel flats with lino covered chip-board tops and structured edging of pine wax polish.





18. telephonists' desk in the reception room.

19. ceiling in the board room. It consists of 'egg-crates' made up from 3 in. thick chip-board which is self-supporting over the room. The fabric is brown, beige and grey madura.

20. the general office. The floor



consists of a special jointless screed over which is laid lino tiles. The walls are lined with plaster board scrimmed and lined with heavy lining paper and painted white, dark blue and yellow and the panels between the glazed screens in the partition are of sapele mahogany.





## design veriew



wall clock: A straightforward design for a high quality wall clock is still a rarity. Until recently designers have frequently been forced to have special designs made at great expense or have had to resort to the ships' chandlers. Only industrial clocks or the cheaper mass produced models which cannot afford the decorative disguises of compasses, astral charts or frying pans have achieved a readable simplicity.

The model illustrated, 1, has a marine flavour and is produced by Baume & Co. Ltd. and designed by Margaret Casson.

The face is dark olive green or white with Roman numerals and hands. The case is lacquered satin brass and it can be fitted with syn-chronous, impulse, 8-day, or battery wound movement. The prices range from approximately £18 for the synchronous to £25 10s. 0d. for the battery wound movement. The battery wound movement is a Swiss import, which accounts for the high price. The spring of the clockwork mechanism is kept wound by a flat, torch-type battery which lasts approximately 9-12 months, and is simple to replace. A clock with this type of movement has the advantages of an electric clock but with added mobility and no electric leads. The clock is 8 in. in diameter and

projects 4 in. from the wall. Larger

sizes can be supplied to special order.

The design combines elegance suitable for a domestic interior and the essential boldness and clarity for a pub or an office.

The British Horological Institute is planning an exhibition for next month at the Goldsmiths' Hall which is to include the current products of British watch and clock manufacturers together with ex-amples of our old master clockmakers. It is hoped that some new designs will emerge by them of the standard of Big Ben's contemporaries of 100 years ago.

fabrics: A new firm was started at the end of last year under the name of Hull Traders Ltd. to promote and co-ordinate the work of seven young designers. The name refers to one of the Directors, not the

The exhibition includes furniture. fabrics, wallpapers, rugs and tiles. and some of the smaller elements of

interior design.

Work from this firm will form a large part of the furnishing and textile section of an exhibition of British goods opening this month at Lord and Taylors in New York, which was inspired by an earlier visit to Hull Traders' showroom.

Amongst the fabrics are some beautifully drawn silk screened prints by John Drummond on classical themes. They are on 50 in. cotton satin and the prices range from 35s. to 50s. per yard. These are a refresh-

ing change from the recent rash of mediocre fabric designs which debase modern painting techniques. Such large and splendid scale is rare some of the repeats are as much as 44 in.—and should be seen by architects searching for designs for large areas in public buildings. The colours are mostly sombre mixtures of black, white and brown, but special colours can be printed to order.

can be printed to order.

The three fabrics illustrated are, 2,


'The Big Lady' at 50s. per yard, 3,

'Sabines' at 35s. per yard and 4,


'Baiae' at 40s. per yard. The fine
gauze-like texture of the lawn would
look particularly well for his curlook particularly well for big curtains if skilfully lit. This range might well be useful to local authorities and their architects for schools. Hull Traders strongly recommend silicone treatment when the fabric is to be used in public buildings. It costs Is. per yard extra.







## THOMPSON FECIT



On March 24, 1852, a Mr. Gould exhibited to a meeting of the Archaeological Association a series of pen and ink drawings of the fortifications round London erected fortifications round London erected by the parliamentarians at the beginning of the Civil War. They were said to have been drawn by a Captain John Eyre of Bakewell, Derbyshire, and of Cromwell's regi-ment, and to be, together with a letter and some memoranda, the property of Mr. Peter Thompson of Oxford Street, who intended to rublish them. The members of the publish them. The members of the association found the drawings 'exceedingly interesting and Mr.
Thompson received a number of orders for engravings of them at 42 12s. 6d. the set, one of which was for the Guildhall Library.

Among those who were most

Among those who were most interested in this discovery was William Salt who was collecting material for his library. By a convenient coincidence Peter Thompson was able to produce a number of other drawings of seventeenth century London and of places in the midlands, a portrait of 'Master Salte of Yoxall,' a portrait of 'Master Salte of Yoxall,' and many notes on monumental inscriptions and heraldry relating to Staffordshire. These were acquired by Mr. Salt at the cost of several hundred pounds and they are still in the William Salt library. As Mr. S. A. H. Burne, a senior trustee of the library, remarked in a recent article on the drawings, 'the story that Eyre, while campaigning with the Parliamentary army, filled in his lessure moments by this archaeologi-Parliamentary army, filled in his leisure moments by this archaeological activity, was not an unlikely one; Symonds and others have shown that it was the fashion of the day for soldiers to take pencil and notebook with them. But Eyre was almost too industrious.' Among his papers were two letters on military papers were two letters on military topics, one dated 'from ye towne of Walsall' on April 18, 1642, four months before the king raised his standard at Nottingham! The story goes that at a small literary party several of the guests began to twit Salt on his gullibility. He expressed his belief in the authenticity of the drawings and offered to submit them to the judgment of a panel of experts, who, alas, pronounced them

be ingenious but obvious fakes. Salt's acceptance of them must have been largely due to wishful thinking for no one with any real knowledge of London during the Civil War could have accepted the 'fortification' drawings at their face value. The forts erected in 1642-3 consisted of trenches and earthworks hastily dug by the citizens of London to meet a sudden emergency. The description of them given by William Lithgow, a Scotsman who made a survey of them, in 1643, bears no resemblance to the elaborate erections with enormous brick and stone ramparts portrayed in the drawings. The fort at Wapping, 1, for example, was 'a seven angled fort erected of turffe and watles and carthenworke' with and waties and earthenworke' with nine port-holes and as many cannon and 'neare the top, round shout pallosaded with sharp wooden stakes fixt in the bulwarkes.' The plan of the forts is certainly based on that drawn by Vertue in 1738 and printed in Maitland's History of London, 1758, while the houses and streets in the drawings have for the most part been taken from Wencedaux Hollor's been taken from Wenceslaus Hollar's 'Long View of London.' Thompson was a print- and book-seller and would therefore have had access to such material; he had some skill as a draughtsman and the evidence of style and writing leave no doubt that the fortifications and the other so-called seventeenth century drawings which he offered for sale were his own

Thompson was emboldened by his initial successes and before his bolt was shot he produced a number of other drawings bearing the legend, 'W. Hollar fecit.' There are several of these in the collections at the Hackney and Bethnal Green reference libraries, 2 and 3, where they still some-times give trouble to unwary search-ers. The print room at the Victoria and Albert Museum contains an ink and Albert Museum contains an ink drawing on very yellow paper of a castellated building purporting to be the 'Greate house and mannor' at Kennington in 1643. A note on the mount casts doubt on its authenticity and it is almost certainly Thompson's work. The Guildhall Library also has work. The Guildhall Library also has a Thompson drawing. This is signed 'Sutten Nichols' and purports to be of St. Paul's Cathedral in 1685, 4; it shows the dome half completed and surrounded by scaffolding. A large volume containing 'Peter Thompson' drawings and engravings was acquired by the print room at the British Museum some years ago.

Thompson's most during attempt in this genre was described in a letter addressed to Notes and Queries in June 1853 and signed P.T. He said 'I have very recently become

'I have very recently become possessed of some curious drawings by Hollar; those relating to Shakesby Hollar, those relating to Shakes-peare very interesting, evidently done for one Captain John Eyre, who could himself handle the pencil well.' The drawings included interior and exterior views of the house 'in ye whiche Master Shakespeare lodged

in ye while he writed and played at ye Globe in Clink Street, Southwark.' They may possibly have been inspired by the Payne Collier forgeries in the manuscripts at Dulwich College. Thompson offered to engrave the drawings if 60 people undertook to subscribe a guinea a piece for a set but his offer came too late for his prospective clientele had already discovered that the drawings were faked and he had to return to more legitimate ways of getting a living.


Peter Thompson was born in Norfolk about 1800. The census return for 1851 gives his calling as 'colonial architect,' a designation which will be explained presently. From the same source we learn that he had a wife, Sarah, and three children, Peter, aged 20, Elizabeth, aged 16, and Charles Edward, aged 7, born respectively in Westminster, Norwich and Limehouse, and a servant girl. He first appears in a London directory in 1828 as 'carpenter and builder opposite Cleveland Street, New Road, Regents Park.' Two years later he is shown as a bookseller in Osnaburgh Place and this address remained his head-quarters for the next thirty years, though he boasted a number of temporary or 'accommodation' addresses during that time.

Thompson scems from the first to have had ambitions beyond those of the ordinary working craftsman. In 1835 he submitted a set of designs, 5, for the new Houses of Parliament in






#### Ida Darlington: THOMPSON FECIT



4, signed 'Section Nichole', this drawing supposedly of St. Paul's Cathedral in 1685 with dome half finished and surrounded with no finished and surrounded with no finished was also done by Thomason.

the competition to be judged by the Committee of Taste. He published his designs in the following year, dedicating them to His Majesty William the Fourth, the hereditary peerage of Great Britain and to the members of the Herse of Committee of the Herse of Committee of the Herse embers of the House of Comm He remarked in the preface that so many architects of distinguished reputation had put in designs that 'a candidate who ranks himself no higher than a Carpenter and Builder could feel no mortification if his entry should be among the many which should 'be declined.' This was as well, for his two storey building was singularly uninspired and his draw-ings were not even among the 87 sets of unsuccessful designs exhibited at the National Gallery in June, 1886.

'erect a temporary wooden structure for church purposes', 6, while the permanent building was being constructed, he found himself up against the new regulations which were being enforced by the Metropolitan Buildings Office, set up under the Metropolitan Buildings Act of 1844. The new church was intended for the Rev. Edward Thompson, perhaps a Rev. Edward Thompson, perhaps a relative of the builder, and he was relative of the builder, and he was anxious to have his temporary church as soon as possible in order to collect a congregation and funds for his new parish. Thompson sent in a water colour drawing of his proposed temporary building, but the registrar thought it a gimerack affair and turned it down, a refusal in which he was supported on appeal by the



in a competition in 1835 for the New Houses of Parlie

In the 1840's Thompson hit on what proved for a time quite a profitable idea, the erection of temporary buildings which were in part prefabricated and could therefore be put up in a few days. One of the first of these was a temporary church at Kentish Town to accommodate the congregation of St. John the Baptist while their church was being enlarged. In the words of the Haptist while their church was being enlarged. In the words of Frederick Miller (St. Pancras Past and Present, 1874) Mr. Peter Thompson, who had advertised wooden churches prepared for exportation to the colonies for the use of emigrants, exected for them an extremely next. erected for them an extremely neat and simple church on brick foundations for 500 adults and 300 children. Kentish Town was outside the area covered by the 1774 London Building Act but when, in February 1845, Thompson, acting as agent for Thomas Little, the architect of All Saints, Finchley Road, wanted to

Little and Thompson and on April 16 approval of the proposed building was given on condition that the piers were made at least 18 inches thick and that the walls between them were of brick and were bonded in every sixth course with iron hoops. Flushed with success Thompson applied in the June following to be allowed to build a temporary church 'in strict accordance with the one I am now building at. John's Wood,' at Maida Vale, for use during the 18 months it was estimated that Thomas Cundy would take to creat the retrongent church. estimated that Thomas Cundy would take to crect the permanent church. In this case the registrar made the additional conditions that the roof was to be of slate and the lobbies paved with fire-proof material. Other temporary churches followed, in Camden Town (1846), Agar Town and South Lambeth (1847) and belowed. Without the conditions of the condition of the conditions and South Lambeth (1847) and Palmer's Village, Westminster and Chalcot Road, St. Pancras (1848). With the church at Chalcot Road Thompson again found himself in trouble with the Metropolitan Buildings Office. The surveyor reported that the piers rested on the surface of the ground which was of wet clay; the wooden floor was raised above the ground on brick posts without caps and the bearing timbers were old and weakened by mortices and notches made in connection with their former services. Moreover the gap under the floor had not been the gap under the floor had not been boarded in and it was feared that ill disposed in and it was reared that in disposed persons might get under-neath and knock down the supports. Some further props were put in but the building was still reported to be insecure even 'in summer time.' In

Commissioners of Works. Various modifications were suggested Little and Thompson and

managed

Thompson

strengthen it sufficiently to obtain the necessary certificate and it was opened for public worship, but the trouble he had with it seems to have deterred him from attempting any more temporary churches. Thompson's ventures in prefabricated structures were not confined to churches. In 1845 he addressed a letter to Edwin Chadwick, who was much interested in methods of getting better housing for the working class, enclosing a water colour drawing of a building closely re-sembling that originally submitted for the temporary church of All for the temporary church of All Saints, Finchley Road. Thompson suggested that this building, which could be erected very cheaply, could be made into six distinct dwellings for poor families, each dwelling containing an entrance lobby and three rooms. Apparently these or similar houses were put into pro-duction, for the Trade Directory for this year shows Peter Thompson as of 'Commercial Road Limehouse, Thompson builder of portable houses for ex-portation'—hence the designation 'colonial architect' in the 1851 'colonial architect' in the 1851 census. Thompson was probably at his most affluent at this time. He was using notepaper headed with an engraving of a large factory building by the waterside and labelled 'Thompson's Manufactory.' If this manufactory was anything more than a figment of Thompson's imagination he cannot have owned

it for long for by 1847 he was back in Osnaburgh Place.

In 1851 Thomp-son carried out the conversion of two old houses, No. 30 Soho Square and No. 1 Frith Street, into a Hospital for Women, though he had some difficulty

in getting his drawings passed by the Metropolitan Buildings Office. After the flasco of the 'Eyre' and 'Hollar' drawings he seems to have laid low for a while, but he was not yet barren of ideas. In 1863 he started a shortlived periodical, The oil and colourman and in the next few years he wrote a number of letters to the papers on number of letters to the papers on philanthropic projects, for most of which he worked out a detailed if over-optimistic budget. For example, in October, 1864, The East London Observer published his proposal for a company to set up self-supporting dual purpose Christian apostolic churches in crowded East End districts for services on Sundays and lectures and reading rooms on weekdistricts for services on Sundays and lectures and reading rooms on week-days to keep people off the streets; capital was to be raised by the sale of 60,000 shares at £6 a share.


Thompson in 1867 issued a series of pamphlets on the housing of the working classes, 7. He advertised

plans, elevations and sections of cottages at 10s. a set and the same for villa residences at two guineas. He became enthusiastic about the use of concrete, which, being fireproof and vermin proof, could be used to build 'healthy moral homes' in the 'fever producing spots' of the metropolis and elsewhere. He himself low-water and he probably spoke from personal experience when he wrote of the difficulties of people earning less than 10s. a week for whom Peabody's Buildings were too whom Peabody's Buildings were too expensive. One of his schemes was for blocks of dwellings built round a quadrangle to be called the 'Palace for our Industrious Workers.' This was to 'provide house room for say 12,000 souls' at 9d. to 1s. 6d. a room. All the fittings, doors, windows and All the fittings, doors, windows and frames were to be of galvanized iron

which would be fire proof and require no paint. 'In the centre of the quadrangle of each block, there should be a coffee and soup and should vegetable room, with a well-lighted and warmed reading room; also a and warmed reading room; also a smoking room. With, to the women's department, a large well-lighted and warm general room for meals and work; also a wash house and drying room and laundry, with a few bett warmen and eather of these. bath rooms and other offices. . . . A retired soldier with an assistant to A retired soldier with an assistant to attend to the kitchen department in providing coffee, tea, soup, etc., at a moderate price—these adjuncts would be self supporting.' Arches should also be provided at street level to house the donkeys of 'that large class called costermongers.'

large class called costermongers.'
In 1869 Peter Thompson, now three score years and ten, was living with his son at Harrow and selling off his stock of engraved views and portraits. He wrote again to Edwin Chadwick offering him a set of his housing pamphlets for a shilling. He quoted Dr. Lancaster's saying that 'in London starvation commences at 2s. 7½d.' a week but stated that for six months he had been living on a dietary of bread, milk and tea costing only 2s. 2d. a week with the only ill consequence a 'titillation' of the skin at night which 'upon an excitible temperament' produced 'an occasional quiverment' produced 'an occasional quiver-ing of the heart.' He obviously hoped to 'touch' Chadwick with a hard luck story but it is probable that his condition was not really so desperate as he made out and that his toovivid imagination was again running away with him. He died in 1874 at the home of his younger son in Leicester Road, Barnet.


Thompson's life span almost co-incided with that of Charles Dickens, Whether they ever met it is impossible to say, but had they done so it is certain that Thompson's character—his ambitions, far outstripping his capacity, and his Pecksniffian combination of moral



7, houses for the working classes by Thompson sentiment with an unscrupulous eye to the main chance—would have made an immediate appeal to the imagination of the novelist.

The writer gratefully acknowledges the help given her in the collection of material for this article by Dr. Still, of the William Salt I.B.-rary, and Mr. Howgego, of the Guildhall I.B.-rary. The records of the Metropolitan Buildings office from which much information has been gleaned are in the London County Record office, County Hall, S.E.1.






1, general view of the factory from the north east.

#### FACTORY AT BERKHAMSTED

ARCHITECTS: ARCHITECTS CO-PARTNERSHIP



This factory, for the manufacture of fine chemicals by the solvent extraction process, stands on the Grand Union Canal to the west of Berkhamsted. The grinding and extraction processes involve a considerable fire risk and are housed in a separate building, with an adjoining boiler house. This building is on three floors, with a precast reinforced concrete frame and in situ reinforced floors. The cladding is aluminium patent glazing on the north side and troughed asbestos sheeting on the other three; the roof is hollow asbestos decking covered with bituminous felt.

The refining area is in the same building as the offices and laboratory, and is constructed of London stock cavity brickwork with timber framed window units supporting a hollow timber roof deck, which is covered with bituminous felt. Heating is provided by convectors supplied with steam from the boiler house.



2, the south and east facades from Montagu Square.

#### THEOLOGICAL COLLEGE IN LONDON

ARCHITECTS: YORKE, ROSENBERG AND MARDALL


This theological college in Montagu Place, W.1, provides residential accommodation, teaching rooms, a library, offices and a squash court, on a very restricted site. The line and scale of the Georgian houses in the square has been preserved and the building follows the original building line, with a standard column spacing of 9 ft. The ground and basement are clad with Portland stone, with brick facing above, the windows on the first, second and third floors being linked with a stone surround. At fourth-floor level there is a long horizontal terrace with a brick 'beam' above, on cantilevered supports. The north elevation has exposed columns with large windows and brick apron panels. The library, offices, dining room and kitchens occupy the basement and ground floors; the first and second floors have classrooms and the synagogue, and the bed-sitting rooms and warden's

3, one of the students' bed-sitting rooms on the third floor.



#### Theological College in London

and caretaker's flats are on the third and fourth floors. The frame is of reinforced concrete with 11-in, cavity brick external walls. The window frames are galvanized steel set in timber sub-frames. The external doors are fully-glazed solid hardwood; the floors are hollow pot reinforced concrete finished with cork tiles, polyvinyl sheet or hardwood blocks. The principal staircase is finished in terrazzo. In the synagogue the Ark is faced with chestnut and Israeli olive wood veneers, with a suspended ceiling of ash veneered ply.





4, the north elevation, facing the mews, expresses the structure clearly, in contrast to the elevations facing the square, which have retained the existing Georgian scale.



5, view from the south east, showing the large dining room window, with the studio balcony above.

#### HOUSE AT COVENTRY

ARCHITECT: DUNCAN KAYE

The house is in a corner of a quiet estate near the centre of Coventry, and surrounded by silver birches and wild plums which were already there. All accommodation is on the ground floor, except for a combined studio and spare room at first-floor level, which leads into a workshop, lit by a dormer window, in the roof space. The main bedroom and bathroom form a separate suite, and a shower

in the cloakroom enables it to be used as a second bathroom. The house has an oil-fired warm-air under-floor heating system. The floors are of mansonia wood blocks, the staircase and fittings of sapele and the ceilings gaboon plywood. The painted walls are grey, with cedar boarding above door level in the sitting room. The house is built of deep red bricks, with teak frames to the large windows.




6, looking from the dining room under the stairs to the sitting room.

#### House at Coventry



#### FLATS AT LAMBETH


ARCHITECT: L. G. CREED



key.

3. Bed sitting-room

m. 4. kitchen. 5. bathroom.



8. abstract mosaic mural by Malcolm Hughes, opposite the lifts on the ground floor.



7, south elevation, showing recessed private balconies.

This building in Royal Street, Lambeth, provides accommodation for 280 people displaced by the rebuilding of St. Thomas's Hospital. The structure is r.e. on a mass concrete foundation, and the columns at ground floor level are set at 29 ft. 6 in. centres to give a feeling of lightness and provide views across the site. The balcony fronts, end walls and roof parapet are of precast bush-hammered granite concrete; all the window panels are of prefabricated softwood. The floors are finished with thermoplastic tiles. Heating is by convector stoves which also supply hot water in winter; there is an immersion heater for summer use. Contrasting colours have been used externally, blue on the soflits of the staircase and pink horizontally along the whole length of the block to emphasize the recessed balconies.

#### BOOKS

#### GLOAG'S GENERAL HISTORY

GUIDE TO WESTERN ARCHITECTURE. By John Gloag. Allen and Unwin. 63s.

This pleasantly written guide, sweeping comfortably through the centuries from the origins of Greek architecture to the origins of reinforced concrete, should be a smooth introduction for an enquiring teen-ager or enquiring grown-ups. Its ten chapters are strewn with drawings by Hilton Wright, and with reproductions of engravings; there are also plates, which for the most part avoid the hackneyed view.

The first chapter introduces the reader to such basic components of buildings as walls and windows, getting him used to the idea of structure and what happens to it, from the Roman wall of London to a disused railway viaduct between Hammersmith and Shepherd's Bush. The chapter on Romanesque architecture makes a nice change from older histories, which dwelt almost entirely on French examples; Mr. Gloag is generous with English, German, and Spanish examples.

Line drawings are very helpful in revealing the relation between interior and exterior arrangements in a Georgian terrace, or the skeleton of the Crystal Palace, or reconstructing a Pompeiian villa; but less helpful in showing up the peculiarities of the piers beneath St. Paul's dome. One sometimes feels with drawings—especially those with character as drawings—that the artist's reaction to the building will creep in. But then, even photographs can lie. On the whole, this book is greatly enlivened by its drawings.

It is good to read an author who encourages people to use their eyes. Perhaps, if they do, they will find a little harsh his own judgments on buildings of the nineteenth century, the Law Courts, for example (a century ago Street himself, in his Brick and Marble Architecture in Italy, was rejecting the Renaissance just as harshly).

#### MEYER ON DECORATION

HANDBOOK OF ORNAMENT. Franz Sales Meyer. Dover Publications Inc., New York, \$2.

Meyer's very special and peculiar Handbook has been unobtainable in England for a long time, but every good old-fashioned art-school library has a copy, worn to shreds. Meyer first published it in 1888 from earlier drawings that had been published as loose sheets; this new edition is a photographic one, and reproduces it exactly: 'a grammar of art industrial and architectural designing in all its branches for practical as well as theoretical use.'

The work is in three divisions: The Elements of Decoration, Ornament Applied to Features, and Decorated Objects. Each division is richly

divided and subdivided, so that the finial and the finial-knob are carefully separated, and we cannot confuse the mug and the tankard.

The Elements of Decoration shows first how the traditional two-dimensional geometrical ornaments are constructed, and everything that any student or designer would normally want to know about them is briefly here. It is in the second section of Division I, the Flora of Ornament, that the curious quality of the book begins to show. The method of instruction is to present first the natural plant and then the 'artificial forms,' the designs that have been based on the plant; one expects, of course, that the 'natural' drawings will have been done very precisely from life, but no. Hop and bryony, for instance, were drawn from pressed leaves, and various quite ordinary flowers 'from casts from nature by J. G. Bofinger of Stuttgart.'

This method of presenting perfectly accessible things at second hand continues throughout the book and gives it a very aloof atmosphere; it is fascinating to see a mediaeval cradle not merely through Meyer's eyes, but also, first, through the eyes of Viollet-le-Duc.

There are pleasures for readers of wide interests; we learn that strapwork may come as tablet, border, or margin; there are pages of alphabets, constructions, and monograms, and some astounding heraldry—five pages of 'helmet trappings' alone. There are hundreds of drawings of every kind of furniture, as usual incredibly subdivided, but it is remarkable that Meyer mentions many things not commonly regarded in the 'eighties as being worth a word at all, such as revolving office chairs, and camp stools. And students of furniture may like to consider abandoning 'monopodium' in favour of Meyer's less expressive but melodious 'trapezophoron.'

Do not miss 'the most usual fundamental forms of vessels and their names'; you are unlikely ever to see a 'recumbent' or a 'cake-shaped' vessel again.

It is a splendid \$2 worth. Barbara Jenes

#### PIAZZAS AND PORTICOES

THE EARLY ARCHITECTURE OF GEORGIA. By Frederick Doveton Nichols, with a Pictorial Survey by Frances Benjamin Johnston. North Carolina University Press. London: Oxford University Press, 120s.

In an exhibition of photography called 'Image of America,' held last year at the Library of Congress in Washington, there was a photograph entitled 'Tintype Booth at the County Fair: May 1903.' There, on the grass of a Southern courthouse square, stood the flag-draped tent—no one would dare to use the flag thus today—of the Elete (sic) Tintype Gallery, Frances Benjamin Johnston, Manager; there, to the left, stood the silk-hatted barker with his megaphone, and there, at a table before the tent, surrounded by quite a crowd of ladies and gentlemen invited

(one hoped) to be in the picture, sat the Manager herself. Miss Johnston, who died in 1952, was to make her mark in more photographic fields than one—she was the first woman press photographer in the White House—but for those who think of her as the best of all photographers of the early architecture of the South the setting gave the scene a special poignancy.

It is Miss Johnston's photographs that will attract most people to this handsome volume, which makes a pair to Thomas T. Waterman's The Early Architecture of North Carolina (likewise illustrated with her photographs), which came from the same publishers in 1941. But Mr. Nichols's text is a worthy accompaniment to them, as the Society of Architectural Historians recognized by its award to him of the 1957 Alice Davis Hitchcock Medallion for the best book on an American architectural subject, or on any architectural subject by an American author, published during the year.

One of his most valuable chapters is that on town-planning in Georgia during the hundred-and-twenty or so years with which he is concerned. As everyone knows, Georgia was founded as a refuge for debtors by General Oglethorpe in 1788, when Savannah was laid out on lines which-pace Mr. Nichols-surely owe a good deal to the Holme-Penn plan of Philadelphia, made sixty-one years before. (The tale that it was somehow derived from something in The Villas of the Ancients of Oglethorpe's debtor friend Robert Castell is put where it belongs by Mr. Nichols, who shows, however, that there is some reason to believe that an uncle of Jean-Jacques Rousseau, the military engineer Gabriel Bernard, was mixed up in the business.) The plan of Savannah, which still gives the city a difference that becomes perceptible to the south-bound traveller today as soon as he begins the descent of the huge toll-bridge over the Savannah River, is quite well known. The planning of the later towns of Georgia has been little studied, and Mr. Nichols will deserve well of the author of that unwritten but much needed history of American town planning, both for the information he has assembled and for the drawings and maps he has reproduced.

Few buildings have survived from the colonial period in Georgia. Indeed, the most remarkable of the colonial buildings about which Mr. Nichols can tell us much was destroyed by fire as long ago as 1773. This was George Whitefield's Orphan-house at Bethesda, known from engravings (repreduced) made when it was in course of construction in 1742. With its four 'piazzas'-to use the contemporary name for the feature still current in the South, though in England since our course of empire took its way eastward we have preferred to follow the Portuguese in calling it a verandah-and with its airy plan, it showed a degree of adaptation to climatic conditions uncommon

in the English colonies in North America; as Mr. Nichols points out, it is reminiscent of certain later buildings in Louisiana.

Neo-classicism arrived in Georgia in 1817. with William Jay. Born in Bath, Jay had been a pupil of the surveyor D. R. Roper, who designed the Lambeth Shot Tower. He spent seven years only in Savannah, but the first five of them were busy ones. He was a skilful house planner with a fondness for contrasted room-forms in the Adam tradition; his exteriors—as for instance those of the destroyed Scarborough house and of the Telfair house can remind one of Ledoux. After Jay's return to England the important man was Charles B. Cluskey, who worked in and around Savannah from about 1830 until the mid 'forties, when he moved to Washington. Both these architects, as Mr. Nichols observes, 'used the Greek Revival for inspiration rather than a copybook.' Others, especially those up-country, did not. By 1840 colossal columns. usually Doric, were being deployed along the fronts, and often the backs and sides too, of the houses of pretty well everyone who could afford them. It is a take-it-or-leave-it affair. this Ante-Bellum phase of the Greek Revival. But those who cannot take it, even in Miss Johnston's photographs, must admit that few towns have tried so hard to live up to a borrowed name, architecturally, as did Athens, Georgia.

#### PLAN AND REALIZATION

DIE ERSTE NEUE STADT IN DER DDR (The First New Town in the German Democratic Republic) by Kurt W. Leucht, VEB Verlag Technik, Berlin 1957.

Cut off as it was from the heavy industry of the Ruhr District, Eastern Germany had to create its own heavy industry as quickly as possible. The first Five-Year Plan (1950-55) had therefore to establish a new industrial centre—an iron and steel combine—together with the new town, of Stalinstadt which this publication describes.

Being dependent on raw material mainly from the USSR and Poland, transport conditions were of paramount importance in choosing a site; which moreover had to be flat to accommodate the immense industrial works. A site where the central German canal system meets the river Oder had the advantage of linking up the transport facilities from

AND THE PARTY OF T

School in one of the housing neighbourhoods of the new town of Stalindark, K. Germany.

the Rhine in the west to the Baltic in the north and Poland in the south; and here the new combine and town was located.

The town is relatively small. It is to have about 30,000 inhabitants, half of whom had been housed by the end of the first Five-Year Plan, mainly in four-storey flats, with a number of three, six and seven storey flats. Shopping, cultural and administrative facilities are lavish, and great care has been taken to provide for all conceivable requirements of the population, from exhibitions and hospitals to youth hostels and water-sport facilities in the Park of Culture.

Altogether it is the thoroughness and precision in the briefing of the architect and the town-planner which is the most impressive part of the undertaking; the interpretation in architectural terms both in the conception of the town as a whole, and in its parts, e.g. islands, streets, squares and individual buildings, shows no signs or manifestations of a new society. The total discrepancy between skill in scientific diagnosis and utter poverty of creative idea, 1, is most distressing. Is it too much to hope for a more constructive expression in the newer enterprises which are taking shape in the East?

Arthur Kern

#### HALF CENTURY OF HAVOC

LORD GRIMTHORPE 1816-1906. By Peter Forriday. John Murray. 21e,

Perhaps the best explanation of Lord Grimthorpe is that he was supernatural, a devil sent in exasperation to tease and prick the complacent nineteenth century. For fifty years he played a Dionysian three-cornered game: the conventionally moral organization (clerical, architectural, horological) in one corner, the truly moral-mostly it seems, members of the SPAB-in another, and Grimthorpe himself in the third, completely amoral, swiping at good and evil impartially. He designed Big Ben, he buttered his legs at dinner, he wrote as clearly and sensibly about architecture as anyone in the nineteenth century and his own house was plain and sensible too; but in his appointed work he was merciless. His capacity for bludgeoning invective was fantastic, and he excelled in sudden sideways shifts of position in the last clause of the last sentence that left the recipient helpless, disarmed, suddenly speaking another language altogether: 'And after abusing the West front (of St. Albans) as mine, as soon as my later clerk of works was dead, they turned round and discovered that it was too good to have been designed by me, but must have been designed by him, without even a pretence of evidence that he ever designed anything at all, except a dreadful brick house in the Italian style for himself to die in, as it unfortunately turned out.'

Lord Grimthorpe was obviously a natural for a biographer: he has been very lucky in finding this one. Since the war, in this field, we have had pedantry, pomposity and potboiling: what this book offers instead is wit.

a kind of humane sympathetic cynicism which is possibly the best of all biographical attitudes, and a miraculous ability to treat history as a branch of present-day life and not as a dead self-sufficient end in itself. Here is an example from the preliminary intrigues before the making of the clock for the Houses of Parliament:

'How far away already was the originating Barry to Vulliamy, "Will you make a clock?" Vulliamy to Barry, "Yes!" It was no longer a clock, it was the clock. It was no longer happy families. It was all distasteful to the profession. What would have become of the old ways, the old profits and the old jobbery?"

This is the perfect foil to Lord Grimthorpe's verbal cudgelling, and the combination sets up a rhythm that catapults the reader through the book. This must be almost the only architectural biography that you can't put down.

Perhaps architecture today needs another visit from Lord Grimthorpe, a point which Peter Ferriday has inserted into the book like the speck of irritant inside the oyster; reading through the book you realize that it is today's society which is being indicted as much as that of the 1870's: some leopards have changed their spots and some haven't.


[18] Waira

#### Shorter Notices

LE CORBUSIER: OEUVRE COMPLÈTE (VOL. VI) 1952-57. Gireberger, Zurich, 48f.

The fifth volume of Le Corbusier's complete works showed him attaining, at last, the recognition and employment he deserved; the sixth shows him a master full of years and works, with a practice scattered over a quarter of the globe. If he has a 'late style' in the accepted sense of the word, then this volume records it, but the reader is almost certain to be struck by Le Corbusier's continuing variability, rather than by the emergence of any constant factors in these late works. Most of them are in India, either at Chandigarh—the Courts of Justice, the Secretariat, the projects for the Governor's Palace and Parliament House-or at Ahmedabad-the Museum, the Millowners' Building, the Villa Shodhan, and the Sarabhai House-and they exhibit four radically different approaches to architecture in the tropics. The Courts of Justice is a row of compartments under an independent sunshade structure; the Secretariat resembles an unité (like Nantes, also in this volume), and the Millowners' Building belongs to the same persussion of brise-soleils and so forth: the Museum follows the traditional Muslim recipe of blank exterior walls and a central court: while the Sarabhai House resembles the Jaoul houses (again, illustrated in this volume) in its use of long tunnel-vaults with closed sides and open ends. In spite of all these exotic buildings in exotic sites, however, there can be no doubt that the strangest and most intriguing building is that with which Volume VI begins, the Chapel at Ronchamp, vividly demonstrated in a series of superb photographs, that make the physical form of the building, its spatiality and its illumination, as clear and comprehensible as photographs ever could, and still leave the psychological motives behind its creation and its shape as secret as they ever were—and probably ever will be. Q.s.c.

<sup>\*</sup> This is very sinister and devilish. Had architecture was for other people; there was no treed to make it on himself.



Haywards wallpaper "Festa" No. 571. Drawing by Dennis Bailey.


## A SERVICE FOR ARCHITECTS

The primary purpose of our ABCHITECTS' DEPARTMENT is to give advice on the use of wallpaper but we welcome inquiries relating to the interior scheme of decoration as a whole. Our products may be seen at the Showrooms in London and Manchester, and if required we can provide a complete specification incorporating wallpaper, paints, furnishing fabrics and floor coverings. The Architects' Showroom in London is reserved exclusively for the use of Architects, Interior Designers and their clients.



THE ARCUITECTS' DEPARTMENT THE WALL PAPER MANUFACTURERS LIMITED 125 HIGH HOLDORN LONDON WCI OR KING'S HOUSE KING STREET WISL MANCHISTER 3

## Thermal Insulation need not be an extra



THERMAL INSULATION
LOAD BEARING
HIGH SPEED OF LAYING
LIGHT WEIGHT
WORKABILITY
OFFECT FIXING
FIRE RESISTANCE
REDUCES THE RISK
OF CONDENSATION

With THERMALITE-YTONG building blocks, it is possible to design load bearing external walls with a high thermal resistance, and at a cost comparable with traditional brickwork or concrete construction.

The lightweight blocks nominal size 18" x 9" are made in various thicknesses to suit specific needs, have exceptional working properties, and allow for speedy laying, being easily cut and shaped with bricklayers tools or handsaw.

How infinitely more economical it is to build with thermal insulation instead of needing an additional operation with the consequent increased costs.

## THERMALITE-YTONG

Load bearing insulating building blocks

For further details and technical data apply to:

THERMALITE LIMITED, Hams Hall, Lea Marston, Sutton Coldfield, Warwickshire. Tel. COLESHILL 2081

NIARCHOS COLLECTION

There are many fine pictures in the

Niarchos collection but there was something extremely disturbing about the atmosphere of the exhibition at the Tate Gallery. Unfortunately, I will not be able to say what was wrong without giving the impression that I was looking for trouble, and I rather envy the virtuosity of those critics who managed to give the exhibition a cool treatment without finding fault with anything.

Actually, I approached it with far less prejudice than many of the critics: I am not in the least disturbed, for instance, by the fact that Niarchos has become one of the most important private collectors of nineteenth-century French masters by the simple expedient of taking over someone else's pictures. He is a man who has grown used to making big deals, and from that point of view his collection is now a proper reflection of his financial standing.

He started to buy pictures in 1949, and made a modest enough beginning, for in the first twelve months he acquired only a watercolour called 'A Voice from the Cliffs,' 1, by the nineteenth-century American painter Winslow Homer—a very good



picture in an unfashionable idiom—and a small oil by Renoir. Since making his bulk purchase of the Edward G. Robinson pictures, which accounts for forty of the seventy-two works shown at the Tate, he has continually added important paintings, often at hair-raising prices. Some of these acquisitions have destroyed the homogeneity of Robinson's refined and tasteful collection in a manner that many people find brutal and insensitive, but others have marvellously enriched the Robinson group on its own ground.

In his less flamboyant way, Robinson has been as much concerned with the 'gilt-edged' as Niarchos. He was essentially a collector of nineteenth-century masters of the French School, and although he bought pictures by famous twentieth-century artists they were almost always

works that were conceived in a nineteenthcentury spirit. His approach to the moderns was timid in the extreme: his Matisse was painted before the turn of the century, his Picasso, which was not on view at the Tate, was painted not later than 1901, and he was content to let his two elegant but excessively mannered Modiglianis represent the 'modern movement.' It was perhaps his nineteenth-century approach to modern painting that landed him with a very bad painting of the nude by Segonzac, and although it seems to have been his only serious mistake, it has so to speak perpetuated itself, since it is the one really unsatisfactory picture in the Niarchos collection.

The Robinson pictures are rather like the children of divorced parents who treat their new step-father with coolness and suspicion, and it is fascinating to see what Niarchos is doing to break down their resistance. He flatters them at one moment and bullies them at another, and I think that the largeness of his gestures is winning them over. I was not helped to arrive at this conclusion by the presentation at the Tate. On the contrary, it was the totally unimaginative hanging that cast a shadow over the collection and gave it the look of being a mere aggregation of precious merchandise.

It is, of course, absolutely barbarous of the Tate to expect the Arts Council to hang good pictures in the gloomy anteroom to the galleries grudgingly assigned to temporary exhibitions. The Niarchos pictures could not have been decently arranged in less than three good-sized galleries, but were allotted only two, with the miserable ante-room thrown in for bad measure. Nevertheless the inadequacy of the wall space did not account for the worst features of the hanging.

It was fatal to the presentation of this particular group of pictures to try to abide by the conventional view that the work of different periods and schools should be kept apart. There were not enough works outside the main Impressionist and Post-Impressionist group to fill a gallery, so they couldn't be properly isolated, but the 'next best thing' that presented itself to the hanging committee was the worst





possible solution: the pictures by El Greco, Goya and Rubens were pushed into the end gallery along with an overflow from the main gallery. This desultory and meaningless way of hanging pictures made the end gallery look like a lumber room and gave one the unpleasant impression that the old masters in the collection were being treated as indiscriminate purchases.

I am harping on the dilatoriness of the hanging because the collection is of a



kind that offers particularly good material for lively and illuminating juxtapositions.

El Greco's 'Pieta' could have been flanked by some of the Rouaults, for these two painters share an intense religiosity which is as evident in Rouault's large and impressive picture of darkly blazing flowers as in El Greco's grey Christ. Goya's insouciant use of black in his portrait of Donna Joaquina Candado would have contrasted effectively with 'The Black Clock.' 2. in which Cézanne treats black as an almost insuperable problem. The Rubens self portrait would probably have been the most difficult picture to place sympathetically, since at first sight it looks like a hundred other Flemish portraits of the period, but it might not have looked altogether amiss beside Cézanne's self portrait; they share at least a sharp yet not too unforgiving self-scrutiny: other-





wise, it would have been an understandable kindness to find Rubens a position near the Renoir nude, 3, which most resembles his own great images of the Junoesque.

The neatness of the Winslow Homer was treated as an embarrassment, and the picture was hung behind the girl who was in charge of the catalogues, but if it had been tried out against the neatness of Scurat's coast scene I doubt if it would have been put out of countenance. In any case the Scurat, surrounded as it was by more freely painted pictures, didn't look at all happy.

Manet's watercolour of Olympia, instead of being hung beside Cezanne's 'Aqueduct and Lock,' where its wonderful transparencies would have found appropriate company, was allowed to make a whole line of Renoirs look dull in colour. Oddly enough, the one Renoir in the collection that could have resisted interference from the Manet—the sumptuous 'Mosque at Algiers,' 4, acquired by Niarchos at the Biddle sale—languished in the ante-room.

The five works by Degas—four of them are pastels of dancers—were also in the ante-room. The entrancingly ungraceful 'Dancer Leaving her Dressing Room,' 5, deserved to be in the main gallery. The other pastels are a little disappointing and offer no sort of challenge to Lautree's oil sketch for the poster of 'Jane Avril Dancing,' 6, which was to my mind one of the chief glories of the exhibition.

The collection is likely to go on expanding, and if the quality doesn't fall it will not much matter how many schools and periods get into the mixture: on the basis of 'only the best is good enough,' it will always have its own kind of homogeneity.

Robert Melville

1, model of Michael Laird's scheme for an hitel and festival center on the edge of Princes Street gardens.

### TOWNSCAPE


HIGH BUILDINGS IN EDINBURGH

Edinburgh is a city of many splendoured things to delight the antiquary —but it also has building of such mediocrity and outrage in some places that recent propositions for high building in these very places are the more interesting.

Until lately, the city has been comparatively free from the ramifications of developers or at any rate those who are anxious to cram the maximum lettable floor space on the most central city sitesbut these enterprises may not always be hard to reconcile with the encouragement of worthwhile building interests. Implicit in these circumstances is the decision (or lack of this) of the planning Committee. who, according to a recent press report from the Town Planning officer '. . . have adopted no particular standard; it is rather based on the general appearance of the building. One thing the city is against is the creation of "canyons" or towering buildings on either side of the street such as in New York.' In this brief survey, we have taken account of schemes for high building projects (both factual, and those for demonstration purposes only), together with local press information, in an endeavour to establish a proper report on this precarious situation. There are three main instances of reference to this question which are illustrated here:

(A) Project for Hotel and Festival Centre by Michael Laird in 1957, 1, 2. In this case the site is on the south-west fringe of Princes Street gardens and allows exceptional possibilities for high building. The scheme





With Conduit WEATHERMASTER, Carrier offer the most comprehensive air conditioning system yet available. Summer cooling, winter heating, constant supplies of clean air and temperatures controlled in individual rooms free from traffic noise — just a few of the many outstanding features of this revolutionary, space-saving, air conditioning system for multi-roomed buildings. Please ask for full particulars.



### Conduit WEATHERMASTER

AIR CONDITIONING SYSTEM

CARRIER ENGINEERING COMPANY LTD + 24 BUCKINGHAM GATE, WESTMINSTER, S.W.1 + Telephone: VICtoria 6848

The Pioneers of Air Conditioning



# OVER 18 MILLION FEET have pounded this floor

Over 18
million feet
have walked and
shuffled across
this Linoleum
floor in the course
of 24 years.

At this busy and popular

restaurant in
Ludgate Hill, Linoleum
provides added evidence
that it has beauty
which cannot be stamped
out in spite of years

of hard wear.

Easy to clean

and maintain, quiet

to the tread and hygienic,

Linoleum is available in a

wide range of patterns and

colours which facilitate

decorative enterprise.

For beauty that cannot be stamped out

LINOLEUM



"THELMA" stands for The Linoleum Manufacturers' Association, 127 Victoria Street, London, S.W.I.

For further indirection write in the Association or to any of the following members: Barry Ostlere & Shepherd Ltd., Kirkcaldy - Dundee Linoleum Co. Ltd., Dundee Linoleum Manufacturing Co. Ltd., 6 Old Balley, London, E.C.4 - Michael Naira & Co. Ltd., Kirkcaldy - North British Linoleum Co. Ltd., Dundee - Scottish Co-operative Wholesale Society Ltd., Falkland, Fife - Jas. Williamson & Son Ltd., Lancaster



2, the heel from Princes Street jurdens

is of high plot ratio and provides for underground car parking over the whole basement area. The following quotation from an article by 'The Scotsman' leader writer, A. J. Arthur, is relevant: 'It would be necessary to forget the passionate prejudice against high building in Central Edinburgh. The cry, ''It would compete with the Castle!' is usually enough to put the veto on anything over 60 feet within a mile or two, Michael Laird has defended his hotel block against this charge, in a way I find very convincing. The one object, he says, is a semi-translucent tower, the other a dark, opaque massif....'

(B) Rentable office building in Drumsheugh Gardens. Although the building is only eight floors high (including the recessed top floor) it must count as a high building in its relations, if any, by scale and size to the form of its immediate neighbourhood, 3. The developers (Western Estates & Properties Co.) cannot be held responsible for the pale yellow artificial stone finish which the City authorities have insisted upon—and was in fact selected by them, 4. Apparently, it is quite usual practice in Edinburgh for the Planning Committee to demand a selection of

material samples from the applicant from which they, the Planning Committee, may finally choose.

(C) Projects for high buildings in George Street. Recently the Lord Provost has declared that George Street may well become the commercial centre of the city, but only now is there a plan for its development, the question having been referred to a panel of consultants for resolution in October 1957. In the interim period ideas were forthcoming from private architects



2, the Drumshough Gardens site today



1 proposed office block in Drumsheugh Gardens



5, development of George Street suggested by the author showing high building set back from two-storey shops on the pavement


and in studying these proposals we should have regard for the fact that a commercial development programme here will demand a plot ratio of, say, 5:1, some provision for pedestrian shopping, and increased ear parking facilities. The proposals may briefly be summarized in chronological order:—

(a) New shop and rentable office accommodation on a gap site of about 70 feet frontage for Modern Property Developments Limited by Michael Laird (assistant architect: Douglas Laird). An application for guidance over this building remained with the Town Planning Authority from September 1957 (when it was stated that the permissible plot ratio would probably be at about 5:1), until May 1958, when the findings of the panel of consultants took effect so that permission was refused.

(b) Proposal by Alan Reiach for a framework in George Street within which buildings of up to 120 feet in height may be accommodated. Although independently prepared, this proposal takes account almost exactly of the project outlined in preceding paragraph, and Alan Reiach has made it clear in an article in 'The Scotsman' that he considers this, the crown of the hill, a proper place for high building in Central Edinburgh.

(c) The situation has been spiced by publication this June of the conclusions about George Street from the Panel of private consultants to whom the question was remitted. Their recommendations have been for no building above the existing terrace height on the street frontage or about 75 feet on a second higher building line set back on the site. This report restricts George Street redevelopment to a plot ratio of about 31:1, but suggests that if a greater concentration of buildings became essential they could be spread into an area near the East End and perhaps around St. James' Square. 'The panel suggested that façades of all streets should be constructed of natural sandstone, and faces of the lanes and all high buildings should be of artificial stone to match the natural stone.' It remains to be seen how this resolution can be reconciled with contemporary building science and architectural quality.

The whole problem is bound up with questions of traffic circulation and this aspect is rapidly coming to a head regard-less of these proposals for redevelopment. The City's proposal for a new traffic roundabout in Randolph Crescent has met with strong objections from several



6. the George Street tunnel and its relation to the new buildings.

responsible sources. This proposal would not only divert more through traffic by the unsuitable road pattern of the New Town terraces but would seriously affect the character of the Town itself. There can be no doubt that long-distance heavy traffic should be diverted a long way from the town centre and that some more radical proposal is necessary for dealing with the central traffic problem. It has been suggested that a tunnel below George Street, which would surface at perhaps Randolph Place at the West End and near St. James' Square to the east, 6, would be an invaluable asset. This tunnel could also have access to the cleared island sites in the lanes behind George Street where multi-level car parks (also serving Princes Street) could be built.

This last idea surely bears investigation together with the additional finances which might be available to help its construction through redevelopments to higher rateable values on either side. In London and in Glasgow the applicant does know more accurately at the outset where he stands, at least in relation to plot ratios, but there is as yet no code for Edinburgh. Obviously the next question Edinburgh must ask itself is, 'do the same opportunities exist?' It would be odd indeed if Patrick Geddes' own city regarded Town Planning simply as a restrictive practice.

In any event these matters of moment will have to be resolved somehow, sometime, in Edinburgh, Will this capital city acknowledge the extraordinary opportunity which attends these problems? If this is realized with foresight and imagination then a new townscape will be created which should rival the bold courage of the existing 'Old' and 'New' towns and which, as the Town Council must appreciate, incidentally represents an investment offering greater and more rapid return than any over-cautious half-measure. Certainly the proper answer will not lie in the imposition of any inflexible plan and neither in some incomprehensible ideology which cannot be defined to the architects concerned. It will be interesting indeed to see what arises. M.L.

### OUTRAGE

The despoiling of shrines—though an active national sport in which Britain, we feel sure, would wish to yield to no one—is not, alas, wholly confined to this country.

You will remember, for instance, the



1. Van Goah's 'Yellow House

radiant 'Yellow House' sweating in Arlesienne heat through Van Gogh's incandescent canvas, 1. The place is a domestic dream, a corner of perfection, seen through a haze of southern light and surrounded by a naïve architectural good-neighbourliness. You earry it in your mind as something set aside from the world that will always remain so and will always await your visit when you've time. You were wise never never to go-the place would be difficult to find in any ease, and the house is no longer there. For the Arlesienne French, by means no more deliberate than complete indifference, have succeeded in obliterating any memory of Van Gogh and the Yellow House today. Worse, by going their own shabby twentieth-century way, they have also succeeded in so polluting the site as to make it unrecognizable. If you are morbid enough to seek the place out you will find no wall-plaque to



2, the scene as it is now

help you—instead an infestation of rubbishy decay cheek by jowl with a petty proletarian commercialism. The house had an ideal setting, a corner site shaded by trees, and backed by a dignified four-storey block that has also suffered insult. The wooden-shack café, 2, with its corrugated roof, messily obscures two floors of the sunny side. The front bears the familiar stigmata of French telephone fittings, together with the rusted relies of a decayed garage. The back, 3, is just a rubbish tip, litter-bin, car park, dirt store. And the



3, the dumping ground behind the house

house behind, packed to the roof with no doubt happy families, flies from most windows an abundance of drooping washing. It is beyond us here to attempt to interpret the French provincial mind, their denial of Van Gogh in general and the site of his house in particular. Apart from the café, which should never have been allowed, the whole place could be cleaned up in a few days at very little cost. Suffice it to say that the effect of the Yellow House site is one of quite ordinary modern desolation in front of a building which, through its magical associations, would still merit quite extraordinary care.

### FUNCTIONAL TRADITION

THE TORRENT BED

As part-compensation for the previous outrage, here is an example, also from the South of Frances, howing how an apparently hopeless state of affairs was turned to good account.

The problem was how to treat the bed

# METAL WINDOWS and

CURTAIN WALLING





**POWER STATIONS & FACTORIES** 



SCHOOLS & COLLEGES



MINISTRY & GOVERNMENT BUILDINGS



HEAD OFFICE: CENTURY HOUSE, WESTMINSTER BRIDGE ROAD,
LONDON, S.E.I. Telephone: WATERLOO 6314
LONDON • PERIVALE • BIRMINGHAM • GLASGOW



**PUBLIC BUILDINGS** 



**CHURCHES & SYNAGOGUES** 



OVERSEAS PROJECTS

Illustrated are some recent projects by our Metal Window and Curtain Walling Division

HERCULES HOUSE

Architect, R. N. Wakelin, F.R.I.B.A., of O. Campbell-Jones & Sons, F.R.I.B.A., Contractors, Richard Costain Ltd.

ALEXANDRA PALACE :

UPPER CLAPTON CONGREGATIONAL CHURCH : Architects, Spalding, Myers & Attenbrow, F. A.R.I.B.A. Contractors, C. R. Price Ltd.

KUWAIT WORKSHOPS WATER DISTILLATION PLANT: Architects, Farmer & Dark, FF.R.I.B.A.; Contractors, Richard Costain Ltd.

LONDON AIRPORT:
Architect, Fdk. Gibberd, C.B.E., FR.I.B.A.;
Contractors, Taylor Woodrow Construction Ltd.


GATWICK AIRPORT:
Architects, Yorke, Rosenberg & Mardall, FF R I B A.
Contractors, Turriff Construction Corporation Ltd.

Contractors, Turriff Construction Corporation:
MARCHWOOD GENERATING STATION:
Partners, Sir Wm Halcrow & Partners,

Consultant Engineers, Sir Wm Halo MMICE: Architects, Farmer & Dark, FFRIBA Contractors, Stayerton Builders, Ltd.

LANGDON CRESCENT SCHOOL: Borough Architect. fors, W. & C. Fren


H.M. EMBASSY, CAIRO, CHANCERY OFFICES:



And whatever the plan may be, we can design, construct and install the equipment to your specification.

Over 80 years of experience in the manufacture of catering and kitchen equipment is at the service of the architect plus the widest range of adaptable units for every catering requirement-from selfservice counters to dishwashing equipment, from canteen boilers to automatic self-service tea and coffee machines.

Our experienced technicians will gladly advise and co-operate in the planning of efficient catering installations on any scale.



We shall be pleased to send you our fully illustrated literature on request

### W. M. STILL & SONS LTD

Manufacturing Engineers for over 80 years

Registered Office: 29 31 Greville Street, London, E.C.1. Telephone: HOLborn 3744



Manchester: 14 Cathedral Street, Corn Exchange Buildings, Manchester. Telephone: Blackfriars 5778

Glasgow: 136 Renfield Street, Glasgow, C.2. Telephone: Douglas 0444

Bristol: 31 Lawrence Hill, Bristol, 5 Telephone: Bristol 58440





1, dried up river bed at Menton. 2, noque aire's solution of the same problem

of a small stream, which may be a raging torrent when it is raining or the snows are melting in the hills but for the greater part of the year is a mere trickle between the stones. Such dried up river beds are among the most characteristic features of southern France, and, indeed, of most of the Mediterranean littoral, and with their weeds and the rubbish that gets left in them they are also—at least in urban surroundings, where a measure of orderliness is proper—among the least attrac-



3 another view in Roomeraire

tive; the first photograph, taken at Menton, shows the kind of thing, and it will probably be agreed that less promising townscape material would be hard to find. The remaining photographs show how the town of Roquevaire has solved the problem of its river by paving its bed and sinking a central channel just wide and deep enough to contain its normal summer flow. Functionally, the treatment is justified by its making what water there is readily available and ensuring that it keeps on the move instead of collecting in stagnant, mosquito-breeding puddles; aesthetically, the clean lines and smooth yet welltextured surfaces are all that could be desired.

The dried up torrent bed is not a problem that troubles us much in Britain. Nevertheless, we have plenty of other problems whose solution demands the same spirit and the same sensibility as the citizens of Roquevaire have shown in this.

Andrew Hammer

### COUNTER-ATTACK

The image of Dounreay, planted by artists' impressions and carefully posed photographs, must be clear in everyone's mind: sphere and chimney standing out stark and symbolic on the rocky north coast of Caithness. What the northern traveller finally sees when he travels west out of Thurso (133 miles from Inverness, 680 miles from London) is something looking exactly like a well-mannered fish-curing factory on the Thames Estuary, with a lot of mess around it and an



1. Dounreay as it is.

unexpectedly large ball in the middle of it. It is sound, clean, respectable, modern, worthy, decent, and utterly and irretrievably dull.


Dullness can be a virtue—Gower Street is dull, and thank goodness. But if there were any job which cried out for an imaginative solution it was Dounreay: exciting site, exciting function, exciting basic shapes and plenty of justifiable symbolism ready to hand without needing to be desperately dragged in. The main buildings when first published seemed likely to do justice to the programme; they have somehow been submerged by careless design of all the ancillary buildings and then by all the accumulated litter that the various authorities concerned could slap down without caring a damn whether it was Caithness or Camberwell: wires, poles, officious notices, bad fences, arid roadmaking, an electricity substation. The two illustrations show the difference between what could have been and what is: the image, drawn by Gordon Cullen in 1956, 2, and the reality photographed in 1958, 1.

And what else could have been done? In the existing framework, probably very little: whatever imaginative idea was proposed, there would have been some little man at a big desk to stop it. But the effects of the little men would disappear if the will were there; so suppose that the project was in charge of an atomic scientist who lived outside the laboratory as well as in it, someone of the calibre of Bronowski, and suppose that the job was done by a small tough-minded architectural team who were all obsessed by the site and the job. Then there might have been something expressing the idea of Dounreay, to appeal to the human spirit as well as to the calculating machines. The sphere might have been glossy white,\* the chimneys and sheds jet black, instead of the whole lot being an indeterminate grey (the black hangars left over from the wartime aerodrome are the most real buildings on the site). The offices and ancillaries could have become a pattern of connected covered. ways out of the weather -a winter in Caithness is not the same as the gentle Berkshire weather of Aldermaston or Harwell, as the transplanted technicians will find out-using every possible means to serew themselves into the ground, as the local vernacular housing does, so that the sphere and the sheds could have risen up sheer above a set of cowering whalebacked buildings; all the

 Obviously I know nothing at all about the particular requirements, and these suggestions may thus be nonsensical.
 But they are meant to show the tupe of solution that was received. extras outside the perimeter could have been handled coherently and intelligently instead of being plonked down by the yard as though the site were another housing estate.

What it would all add up to would be expressive function rather than just functionalism: a situation where the needs of the atomic plant are not only satisfied physically but are expressed, through the physical requirements, to be a satisfactory image for the spirit as well. That is the idea behind the simplest features of the functional tradition; the handrail that expresses the idea of clinging-on as well as being able to take the right statistical load; the bollard which expresses the idea of stopping as well as having the necessary physical dimensions: on a larger scale the town which expresses the idea of living together as well as conforming to the by-law standard. For lack of this quality many of our older architects, whose names were so bright in the 'thirties, are producing dozens of buildings like Dounreay: and the younger architects are reacting in despair with a vocabulary of pointless bloody-mindedness. Simultaneously there are the big jobs done by the big offices that are under-designed, and the tiny private houses and office blocks done by newly qualified architects which are over-designed, loaded with monstrous doses of architectural symbolism: it is not a healthy situation.

There is an ironical twist to all this. Dounreay is a long way away, and fewer and fewer architects and critics actually bother to go and see buildings. So the artist's perspectives and posed photographs will probably win after all—an entirely false image of Dounreay may well inspire less mediocre countries, in their atomic power programmes, to create the sort of thing that Dounreay should have been. That, after all, is how many of the best classical buildings in Northern Europe were designed. But to keep the record straight, there ought to be a small uncouth voice in the background blowing the gaff; and that seems to be the present vocation of Ian Naira.



2. Ibounreay as it could have been



There is a Weatherfoil System for any type of building.

# EVERY WEATHERFOIL SYSTEM -a Model Installation

Designed exclusively for your project...planned to suit your programme... priced to your budget...engineered to produce a discreet, effective installation.

WEATHERFOIL HEATING SYSTEMS LIMITED

19 Berkeley Street, London, W.1. Telephone: GROsvenor 5146 · 185 Bath Road, Slough, Buckinghamshire

### ACKNOWLEDGMENTS:

L.C.C. Brandon Estate, Southwark. Hubert Bennett, F.R.L.B.A., Architect to the Council.

British Railways, Great Eastern House, Cambridge, H. H. Powell, B. Arch., F.R.I. B.A., Regional Architect (Eastern Region) British Railways.

Monsanto Chemicals Limited. Oil additives engine test laboratories, Newport.

St. Aidan's Church, Speke, Liverpool, Architect: Bernard A. Miller, B. Arch., F.R.I.B.A.

Office Building. Architect; Richard Sheppard & Partners.

Broadgate House, Coventry, Warwickshire,

# DRI-SIL silicone masonry treatments

- \* Keep buildings dry
- \* Prevent damp and deterioration caused by weathering
- \* Keep buildings clean
- \* Prevent staining and streaking
- \* Do not block the pores of building materials, thus do not inhibit "breathing"
- Maintain thermal insulation of buildings by preventing the absorption of moisture by the walls
- \* Are effective for many years, thus reducing maintenance costs
- \* Are easy to apply by brush or spray

### For new buildings For old buildings



OFFICES OF DOCK LABOUR BOARD by courtesy of Frederick Gibberd



ALL SAINTS' CHURCH, HASTINGS
by coursesy of the Rector and consultant Architect

% Water absorption after

Proof of the effectiveness of these treatments is shown in this table

in in substances that he can

		24 hours immersion	
		Initial test	Retested after 3 years' natural weathering
Sandstone	untreated	7-0	6-2
	DRI-SIL treated	0-1	0.2
Cement Block	untreated	6.0	5.9
	DRI-SIL treated	0-4	0-7
Common Brick	untreated	20-0	20-1
	DRI-SIL treated	0-1	0-3

All over the country DRI-SIL treatments have been used on many buildings, large and small, old and new. Use a DRI-SIL silicone to guarantee the quality

### These firms supply water-repellent masonry treatments based on DRI-SIL silicones

Allweather Paints Ltd, London, WC2
Atlas Preservative Co Ltd, Erith
Isaac Bentley & Co Ltd, Manchester
Lewis Berger (Gt. Britain) Ltd, London, E9
Bitulac Ltd, Newcastle-upon-Tyne
5. Bowley & Son Ltd, London, SW11
British Paints Ltd, Newcastle-upon-Tyne
Byrom Paint & Varnish Co Ltd,
Stockport

Chemical Building Products Ltd (Dept DS1) Hemel Hempstead Clutha Paint & Oil Co Ltd, Glasgow Samuel Courtney Ltd, Belfast John S. Craig & Co Ltd, Glasgow W. David & Son Ltd, London, NI Detel Products Ltd, South Ruislip Stuart B. Dickens Ltd, London, SET W. C. Evans & Co (Eccles) Ltd, Manchester

Evode Ltd, Stafford
T. & W. Farmiloe Ltd, London, SWI
Farrow & Ball Ltd, Verwood, Dorset
Floorlife & Chemicals Ltd, Manchester
Joseph Freeman Sons & Co Ltd,
London, SW18

Grangersol Ltd, Watford

John Hall & Sons (Bristol & London) Ltd,

Bristol

Hangers Paints Ltd, Hull
E. Hardman & Son Co Ltd, Hull
Harvey Langford Ltd, London, WI
W. W. Hill Son & Wallace Ltd, Salford
Hydrol Ltd, London, W3
Indestructible Paint Co Ltd, London, WI
Irish Cold Bitumen Ltd, Belfast
Leyland Paint & Varnish Co Ltd, Leyland
George Lillington & Co Ltd, Mitcham
John Line & Sons Ltd, London, WI
Donald Macpherson Ltd, Manchester
John Mathews & Co Ltd, Liverpool
Mineralite Ltd, Croydon

Montgomerie Stobo & Co (Chester) Ltd. Saltney

Nubold Development Ltd, Crawley Permoglaze Ltd, Birmingham Purimachos Ltd, Bristol 2 Reynolds Paint & Varnish Ltd, Liverpool Ribble Paints & Varnishes Ltd, Blackburn

Ripolin Ltd, Southall Sealocrete Products Ltd, London, NW10 Silicaseal Ltd, Newcastle-upon-Tyne William Sim & Sons (Paints) Ltd, Ediphyrch

Stephenson & Co., Blackpool
Thornley & Knight Ltd, Birmingham
Turner, King & Shephard Ltd, London, E15
Walpamur Co. Ltd, Darwen
Wareing Bros. & Co. Ltd, Bolton
F. A. Winterburn Ltd, Leeds

Architects and Paint Manufacturers are invited to write for full information and details of extensive tests of DRI-SIL carried out in this country and in the USA. DRI-SIL is a registered trade mark of Milland Silicones Ltd.

### MIDLAND SILICONES

Associated with Albright & Wilson Ltd
and Dow Corning Corporation

first in British Silicones

19 UPPER BROOK STREET · LONDON · W1
Telephone: Grosvenor 4551
TBW/M0122

# SKULL

### SUSPENDED CEILINGS PART II

bu Peter Matthews

The suspended ceiling has come to us as a screen to hide the paraphernalia of the services. It was only therefore a matter of time before the services became incorporated in the ceiling surface. In this second article the author, Peter Matthews, considers products on the market which have been designed to provide heating or lighting through the ceiling. This article (and its predecessor in the July issue of the AR) should be read in conjunction with Looking Up on page 161 of this issue.

In the first of these two articles we considered the straightforward suspended ceilings which attempt no more than to conceal the services and, in some cases, to provide special sound deadening. In this second article we complete our survey by listing and commenting on the anlisting and commenting on the an-cillary equipment which has been designed specifically for building into suspended ceilings and to provide heating and lighting. These fall into five categories. First there are the modular recessed lighting fittings. As these are legion, it is unfortunately not practice of listing each separate product: instead, as we explain product; instead, as we explain below, we group them into their main classes, discussing the charac-teristics of each and giving an average price figure for each standard size. After the recessed lighting fittings a mention is made of visible fittings a mention is made of visible suspended trunking systems, though these need not be used in suspended ceilings. Next comes the fully illu-minated suspended ceiling, in which the actual translucent surface has become the ceiling: these, as they are relatively few, can be taken product by product. The same is true of heated ceilings, which are of two types. Of these we take first the electrically-heated ceilings, in which the heating element is actually in-corporated in the ceiling; and leave till last the water-heated suspended ceilings in which the actual heat source is remote.

Lastly there are two words of warning. The first concerns prices. These are approximate only, and are not based on identical assumptions. The use of uncorrelated prices in this way is open to objection; but it is not practicable to give fully com-parable prices and it is our opinion that it is of more use to an architect to have some indication of cost (with the assumptions given whenever possible) than to have none at all. He must in any case get his final prices from actual estimates.

The second warning is one which must always be made with this type of article: namely that we have been able to include only those products which we have been able to find at the time of going to press, and that the list may well be incomplete.

### Modular recessed lights

Manufacturers of lighting equipment have designed recessed fittings to fit exactly into the 2 ft. module which seems to have emerged as a standard ceiling panel dimension, and although most of them claim to have eo-operated with certain specific ceiling manufacturers, the fittings are really standard specials and can usually be adapted to suit other systems.

It is therefore very difficult to compare costs except by quotations for a specific job, but the prices for the stand rd sizes might be expected to fall close to the following (prices

2 ft. 0 in. × 2 ft. 0 in. -£12 2 ft. 0 in. × 4 ft. 0 in. -£17 plastic

2 ft. 0 in. × 6 ft. 0 in. - £24 louvres Prices for dished plastic diffusers would be similar but subject to 261

per cent purchase tax. The same fittings containing clear glass would be appreciably cheaper,

2 ft. 0 in. ×2 ft. 0 in.—£10

2 ft. 0 in. × 2 ft. 0 in. — £13 2 ft. 0 in. × 6 ft. 0 in. — £13 1 ft. 0 in. × 6 ft. 0 in. — £19 2 ft. 0 in. × 6 ft. 0 in. — £19 to purchase tax if the glass actually diffused the light.

When planning a suspended ceiling it is important to allow for the minimum depth required for the electrical installation, which can be as much as 10 in. for certain tungsten fittings, but may be as little as 6 in. in the case of fluorescent fittings. Some 'elbow room' is nevertheless welcomed by all concerned.

If the ceiling is intended to give fire protection to the structure above, it might well be advisable to consider some other type of illumination, for although there is no existing law governing this matter, 0.5 per cent of the fotal area is considered a maximum without additional fire-proofing in the USA, which would not give a particularly high level of illumination. Alternatively extra fire-proofing could, of course, be provided, but might prove rather costly.

One of the drawbacks of this type of light fitting is the fact that it it might well be advisable to consider

of light fitting is the fact that it tends to leave the bulk of the surrounding ceiling in darkness, resulting in glare even if the level of illumination is quite adequate where it is required. This can be slightly offset by the use of light coloured finishes on the surface below, which will reflect upwards to a certain extent. Some of the dished diffusers project below the ceiling surface, 1, and although the light source is still above ceiling level, about 2 per cent ceiling illumination might be ob-



1, Troughton and Young's dished acrylic plastic diffuser.

tained. Light fittings which actually floodlighted the ceiling might over-come this difficulty only to emphasize inaccuracy in the ceiling itself, but in shops it would be simple to arrange for some lights, secreted in fitments, to play up on to the ceiling.

Where flat glass is used for diffusing, some firms leave a gap of about 1 in, between the glass frame and the frame of the fitting so that there is a transitional strip of soft light between



2. Troughton and Young's fitting with Spot-lyte

the ceiling surface and the light

source, 2.

Apart from cost, the criteria which may influence the choice of fittings are as follows.

dimensions are tight, then

depth of fitting may be important.
Some fittings are normally suspended independently from the parent-structure, which calls for very from the ecurate positioning if any work is to be done before the ceiling is installed. Others are supported on the sus-pended ceiling structure, but since a


instead of sinking the lights within the surface of the ceiling you use the trunking system which contains the

trunking system which contains the wiring to support the ceiling.

The SGB Flexible Grid is one example which is used to support the panel infilling in a complete modular system, although it may be used on its own to carry individual light fittings. Perhaps the most adaptable trunking is Inver-trunking produced by the AEI Group, 4, the continuous slot in the bottom being filled with a clip-in cover strip between fittings. By opening up the module of almost any of the ceilings described in part I of this article some 2½ in., a strip of this trunking may be introduced to take the place of the standard sus-pension and permit the flexible pension and permit the flexible arrangement of surface fittings along its length.

The transition between fitting and trunking still manages to look rather improvised and could stand further

There are, of course, a host of flush tungsten fittings, mostly circular, which may be incorporated in the ceilings already discussed, but they are far too numerous to examine



Group, Left with Burgens ceiling, right with Conduit Tee balt.

6 ft. 0 in. imes 2 ft. 0 in. recessed fitting and gear can weigh as much as 85 lb. this arrangement might not always be possible.

As 2 ft. 0 in. fluorescent tubes with sockets will not fit into a 2 ft. 0 in. grid, some fittings are designed so that the reflector box is tailored to the module and the tubes project through the sides to end plates which are not enclosed. This may lead to the deposit of dirt from above and reduce the lighting

### Visible recessed trunking

The visible recessed trunking sy tem when used with a suspended ceiling represents the opposite ap-proach from that of recessed lighting:

### Fully illuminated ceilings

The veteran illuminated ceiling in this country is the 'egg-crate' louvre and it remains one of the most trouble-free in that it does not collect dust and dead insects. Bearing in mind the once popular ceiling pen-dant bowls which still abound in suburbia and so frequently are overdue for a scouring, it would seem that to extend this principle to the entire ceiling is not without its drawbacks.

Crompton Parkinson face up to this problem with Modulume and claim that in a clean commercial interior, dry dusting should be carried out at intervals of about two months, with complete washing or damp

### SKILL

cloth wiping every nine to twelve months. No doubt this is quite representative and assumes favourable conditions. Lumenated Ceilings Ltd. offer special maintenance contracts and cleaning facilities for owners of large installations.

Modulume pan diffusers are the only ones available in strong colours, which would, of course, be used

sparingly.

Corrugated plastic continuous strip diffusers are usually fed into channel support sections at one end, and therefore present special difficulties when the time comes for cleaning the upper surface. There is quite a wide variety of design amongst the open louvre types and perhaps one of the more interesting textures is provided by Paragrid with 'bi-planar' louvres which appear to be very ingeniously designed for accurate alignment and, like so many of the more sophisticated suspended ceilings. was not designed on this side of the Atlantic.

In most cases the void above an illuminated ceiling should be de-corated for maximum light reflection, but the exception to this is the SGB Flexible Grid which may be left partly unfilled, in which case the parent structure and services would be 'painted out' in a dark colour. This is not strictly fully illuminated and in any case the lighting has shallow integral reflectors.

Whilst the louvre type ceilings are, of course, acoustically neutral. the void above may be lined with sound-absorbent material. The modular illuminated ceilings (apart from Ionlite) depart from the 2 ft. and, less commonly, 1 ft. modules which are prevalent among the opaque and sound-absorbent ceilings discussed in the first article and adopt dimensions which are appropriate to the spanning capacity of the material or may be conveniently integrated

with the available light fittings.
Sylvalume and Lumenator Module Sylvalume and Lumenator Module ceilings both use a V profile for the visible portion of the grid so that some light plays on the surfaces and softens the joint. The Lumenated ceiling, Sylvalume and Modulume can be fitted with perforated metal sound-absorbent fins which are filled with Fibreglass quilt and clip on to the bottom of the supporting grids. At present no figures are available on their acoustic performance, but they would appear to be more for visual effect than for sound control.

The plastics which are incorporated in these fittings consist of Acrylic sheeting, Fibreglass, Polystyrene, sheeting. Fibre PVC and Vinyl.

Vinyl is non-inflammable and due to its low heat distortion temperature will fall out of its supporting grid and possibly help to smother the flames, leaving the sprinklers free to operate

Acrylic plastic, however, has better colour and light stability, and together with Polystyrene gives better light transmission, but both burn.

Translucent Fibreglass is only accepted by the LCC for rooflights in comparatively thick sections as a result of combustibility tests, whilst PVC does not burn readily and in some forms may be self-extinguishing.

All these materials tend to produce characteristic toxic gases when ex-posed to flame and the prospect of being trapped under a blanket of flaming plastic is not a pleasant one. Finally it might be interesting to

note that some architects have affected a considerable saving by mounting a diffuser unit from a fully illuminated ceiling system in

timber surround and casing made by the contractor.

### OPEN LOUVRE SYSTEMS Atlas Lighting Ltd.

Infill: Aluminium 'egg-erate' louvres. Size: Standard panel 33 in. by 33 in., cell size 3 in. by 3 in. by 3 in.

Joint: There is a double fin where
panels abut and the corners of panels
are chamfered to make way for the

suspension which terminates with a visible circular clip stud.

Weight: Approximately 1 lb./sq. ft. Light source: There is a 45° cut-off and the depth of the void above the louvres should be a maximum of 33 in. and a minimum of 18 in. Finish: Normally white.
Approximate cost: Supply only,

including suspension, 20s. sq. ft.

Infill: Clear polystyrene interlocking strips reeded on one side, which may be assembled to form an 'egg-crate louvred panel.

Size: With practice a panel 321 in. square may be assembled in 30 minutes. The cell size is 2 in. by 2 in. by 2 in.

Joint: The panels are supported on 11 in, by 11 in, by 1 in, aluminium T sections (supplied by contractor) or aluminium angles at the peri-

Weight: No information supplied. Light source: There is a 45° cut-off and the depth of the void above the louvres can vary from 18 in. to

Approximate cost: Supply components and hangers (but not including aluminium intermediate supports where required) 13s. 6d./

Infill: Opal plastic diamond pattern 'egg-crate' louvres.

Size: 10% in. by 9 in. panels with cells 1% in. by 1% in. by 1 in. deep. Joint: Panels are supported on translucent white polystyrene T sections which may be cemented to one side

of panels at no extra cost.

1 in. by 1 in. T will span up \( 1 in. to 4 ft. 6 in. 2 in. by 1 in. T will span up centre span Weight: No information supplied. Light source: No information sup-


plied Approximate cost: Supply Louverex panels, 11s. 4d./sq. ft. 1 in. T bar 2s. 4d./ft. run. 2 in. T bar 3s. 6d./ft. run.

### Elco Plastics Ltd.

Elcoplas lighting lowere

Infill: Anti-static treated, light sta-bilized plastic diamond or square

Size: Heavy pattern (1564) 5½ in. by 5½ in. by 1 in. (1½ in. square cells). Light pattern (1884) 10½ in. by 9 in. by 1 in. (11 in. square cells). Also in units 15 in. by 12 in. by 11 in.



light pattern (2025) (2 in. square cells). They are completely self-supporting in panels up to 6 ft. by

Joint: Interlocking corners assure alignment. Extruded plastic Ts are available (6 ft. to 8 ft. long) to support edge

Weight: Rather less than 12 oz.

Light source: Angle of light cut-off

Finish: Onal colour.

Approximate cost: Heavy pattern, 2s. per unit 5½ in. by 5½ in. Light pattern, 4s. 8d. per unit 10% in. by

The panels may be cut with a hacksaw to fit any shape.

### Harris & Sheldon (Electrical) Ltd.

Paragrid tile (developed in Canada by J. A. Wilson Lighting & Display Ltd.) Infill: Anti-static treated, injectionmoulded polystyrene.


Size: 1 ft. 4 in. by 1 ft. 4 in. with bi-planar 'egg-crate' construction

Joint: The tiles span 1 ft. 4 in. between 'U-trax' suspended channels and key together for perfect alignment. Tiles lift out for access to fittings

Weight: 9 oz. sq. ft. complete with suspension. Light source: 40° angle of light cut-

Finish: White pearl.


Approximate cost: 10s. sq. ft. includ-



panels are fixed to simple clips suspended on the hanger rods, and may be demounted for washing or merely hinged down on either side give access to services and fittings. Weight: 14 oz./sq. ft. complete with

suspension. Light source: Fluorescent tubes should be mounted on the parent structure at centres not less than twice the distance between the louvre tiles and the tubes. angle of light cut-off is 45°.

Finish: Available in white, pale pink, blue or green. The coloured louvres



Metal Sections' Diffulite. Below, sections through AA, left, and BB, right.

do not affect the colour of the light


on the working plane. Approximate cost: 14s. sq. ft. in-cluding suspension (supply only). Light fittings not included.

### Metal Sections Ltd.

Diffulite

Infill: Plastic-coated aluminium strip 2 in. by .010 in., stapled together to form undulating louvre units, 8.

Size: In 4 in. increments up to 7 ft. by 2 in. by 2 in. increments up to 2 ft. 6 in. (i.e. maximum size 7 ft. by 2 ft. 6 in.)



6. Paragrid biplanar tile and 7. Handrite Luve-Tile.

ing suspension (supply only). Light fittings not included.

Handslite Luve-Tile (developed in Canada by J. A. Wilson Lighting & Display Ltd.) Infill: Moulded styrene plastic, anti-

static treated, 7.
Size: 1 ft. by 1 ft. 'egg-crate' unit

Size: I ft. by I ft. 'egg-crate' unit 2½ in. deep.

Joint: The basic units are clipped together to form panels 2 ft. by 2 ft., 2 ft. by 3 ft. or 3 ft. by 3 ft. The

Joint: The bottom flanges of the galvanized pressed steel supporting Ts are visible as a grid which may also support some form of fibreboard ceiling. The Ts are painted to the customer's requirements and are available in a very wide variety of sizes to suit various hanger spacings. Weight: Diffulite panels only, 4 oz.,

Light source: With fluorescent tubes at 2 ft. 6 in. centres the distance

[continued on page 203


# TUBALUX MODULE FITTINGS

TUBALUX MODULE FITTINGS are designed for incorporation with 2 ft. x 2 ft. or 2 ft. x 1 ft. module ceiling panels. The standard fitting incorporates adjustable bolts at each corner for use in ceiling panels manufactured by:—Frenger Ceilings Ltd.; Burgess Products Co. Ltd.; Horace Cullum Ltd.; and with their co-operation we can arrange for the weight of the fitting to be taken by the suspended ceiling. Alternative methods of suspension can be provided for other types of suspended ceiling based on this module.

Module fittings are made from sheet steel which is


bonderized and finished in white stoved enamel. Instant start or switch start control gear is mounted in two removable channels along opposite sides of the interior and supplied ready wired to a fused terminal block easily accessible for connection to mains supply. Interchangeable diffusers in obscured 'Spotlyte' glass with removable hinged frame, polystyrene louvres, or dished opal 'Perspex', are available.

The diffusers allow easy access for maintenance and cleaning.



### OPENING 2FT.x2FT.

T254 Glass Diffuser T264 Polystyrene Louvres T274 Dished Opal 'Perspex' Diffuser Lamps. Four 20W, 2 ft.






GLASS DIFFUSER



### OPENING 2 FT. x 4 FT.


T454 Glass Diffuser T474 Dished Opal 'Perspex' Diffuser T464 Polystyrene Louvres Lamps. Four 40W. 4 ft.





### OPENING 2 FT. x 6 FT.

T554 Giass Diffuser T574 Dished Opal 'Ferspex' Diffuser T564 Polystyrene Louvres Lamps. Four 80W. 5 ft.



### TROUGHTON & YOUNG

Prices may be obtained on application.

TROUGHTON & YOUNG (Lighting) LTD. 7
143 KNIGHTSBRIDGE, LONDON, S.W.1. 'Phone and at 46 Rodney Street, Liverpool I.

The Lighting Centre
'Phone KENsington 3444
pool 1



# SUSPENDED CEILINGS in **MODERN MATERIALS by** RAFTSELE LIMITED INSULATION drawing office for The Iron & Steel Co. Ltd., constructed from Corrugate Translucent Vinyl Sheeting with surrounds of Unit Acoustic Tiles fixed by the McTcO "C" Hook Met Fixing System.

Draftsele Limited and its Associate Company, Draftsele (London) Limited, are specialist organizations which are equipped to undertake contracts of any size in any part of the United Kingdom for Suspended Ceilings, Thermal and Structural Insulation, Acoustical Correction and Sound Deadening. Needless to say the experience of the two companies covers the most advanced developments in all these fields. As far as Suspended Ceilings are concerned, recently-completed contracts include outstandingly successful examples of the following:-

### **BURGESS-SULZER HEATED ACOUSTICAL CEILINGS**

These are a modern development in economical space heating and acoustical control. Coils of pipe, suspended between a thermal acoustic pad and the acoustic ceiling tiles (which are available in a wide range of colours) are heated by the circulation of water at mean temperatures between 170° and 185° F. In their turn, the coils heat the ceiling tiles by radiation and convection and the tiles themselves become radiating bodies emitting heat. Incidentally the latest Burgess Electrically-heated Ceilings have been installed in the offices of Draftsele (London) Ltd., at 47 The Parade, Leamington Spa, where they can be inspected by appointment,

### **FULLY-ILLUMINATED CEILINGS**

These can be constructed in either Corrugated Translucent Vinyl Sheeting (Lumenated Ceilings) or Handslite "Luve Tiles." With either of these materials, the whole, or parts of the ceiling provide the source of light thus offering endless possibilities in regard to the combination of ultra-modern appearance with practical lighting efficiency. Preliminary consultations on the installation of these and other modern ceilings can be arranged entirely without obligation, on application to:-

### DRAFTSELE LIMITED

(Insulation Division) 44 DEAN STREET NEWCASTLE upon TYNE 1. Telephone: 23696/7

Contractors to: THE ADMIRALTY, THE WAR OFFICE, THE AIR MINISTRY, THE UNITED KINGDOM ATOMIC ENERGY AUTHORITY, PRINCIPAL GOVERNMENT DEPARTMENTS. COUNTY AND MUNICIPAL AUTHORITIES AND LEADING INDUSTRIAL CONCERNS

ASSOCIATE COMPANY: DRAFTSELE (LONDON) LTD., 47 The Parade, Leamington Spa, Warwickshire. Phone: 1771

between the tubes and the Diffulite should not be less than 1 ft. 6 in. The angle of light cut-off is 45°. Finish: Standard off-white or any of

14 standard colours. Approximate cost: Nett ex works for Approximate cost: Nett ex works for quantities between 100 and 1,000 sq. ft. either off-white or one of 14 standard colours: Panels up to 4 ft. by 2 ft., 538. 1 d., sq. yd. Larger panels, 41s. 7 d., sq. yd.

Above or below these quantities there will be a reduction or increase

in cost respectively.

For special shapes there will be an increase of 50 per cent on the

### TRANSLUCENT DIFFUSERS Atlas Lighting Ltd.

Sylvalume (based on a system developed by Sylvania Electric Pro-



ducts Inc. in the USA) Material: Vinyl coloured diffusers or

acoustic baffles, 9. Size: 3 ft. by 3 ft.

Joint: A 3 ft. by 3 ft. grid of aluminium extrusions supports the vinyl pans, showing a projecting V cover strip which catches the light and

strip which catcher reduces joint glare. Weight: 1 lb. sq. ft. approx. (com-

Light source: This system consists of an upper structure of primary and secondary wiring and control gear ducts with a flexible arrangement of fluorescent tube sockets, from which is suspended a secondary grid of extruded aluminium ceiling supports.
Provided that the distance between the tubes and diffuser is not less than 1 ft. 3 in. the rows of tubes may be at 3 ft. centres.


For small areas or where the depth of void is between 1 ft. 6 in. and 2 ft., standard batten holders may be fitted direct to the parent structure

(and wiring duets omitted). Finish: Vinyl diffusers (see illustration) white, pink or blue. Acoustic baffles white, black or red.

Approximate cost: Entire ceiling, including framework, diffuser panels, suspension and some baffles (ex-cluding lighting system), is about

### Courtney, Pope (Electrical) Ltd.

Glolite 1 Infill: 'Dogtooth' profile Fibreglass sheets.



10. Courtney, Pope's Glolite fittings. Top and lower left, details of Glolite 1. Bottom right, the same wiring duct supporting Glolite 2 infill

Size: 2 ft. 10 in. by 3 ft. Joint: 5 in. by 1½ in. by 16 gauge inverted m.s. wiring duets, 10, at

2 ft. 111 in. centres suspended on rod hangers and fitted with projecting studs to support the infill panels. The panels may be laid continuous or broken by cross channels or solid

panets.
Weight: 2 lb. sq. ft.
Finish: White Fibreglass, and in
colours at extra cost.
Approximate cost: 117s./sq. yd.

Glolite 2 Infill: Corrugated PVC.

Infili: Corrugated PVC.
Size: 3 ft. wide by required length.
Joint: 5 in. by 1½ in. by 16 gauge inverted m.s. wiring ducts at 3 ft. 1½ in. centre supported on rod hangers and fitted with 1 in. by 1 in. m.s. U channels each side to receive m.s. C channels each side to receive infill panels, 10. The panels may be laid continuous or broken by cross channels or solid panels. Weight: 2 lb./sq. ft. Finish: White PVC

Finish: White PVC.

Approximate cost: 72s,/sq. yd.

This firm also produce open
'egg-crate' louvres in metal with
2 in, by 2 in, by 1½ in, 2 in, by 2 in,
by 2 in, and 3 in, by 3 in, by 3 in,
sizes, and moulded white opal plastic louvres 12 in. by 12 in. with 13 in. by 13 in. cells 1 in. deep, all of which may be made up into any required

### Crompton Parkinson Ltd.

Modulume (based on a system developed by the Wakefield Company, Vermillion, Ohio, USA)
Material: PVC copolymer pans or corrugated vinyl sheet.
Size: Pans 3 ft. by 3 ft. Sheet 3 ft. by

up to 30 ft. Expanded styrene panels 3 ft. square by 1 in. are also



11. example of Modulume ceiling at Coventry Civic Theatre.

MODULUME

12. Modulume criting.

available for opaque sound-absorbent infilling. For setting out 2 in. must be added to the module dimension in both directions. Where the room in both directions. Where the room size does not conform exactly, the ceiling may float free of the walls, or be furred out vertically to the ceiling or horizontally to the wall, 11 and 12. Joint: Fluted extruded aluminium H sections normally visible, but may be covered by a vertical clip-on sound absorption baffle. Visible cross Hs are used with pans only.

Weight: Pans and structure complete -1½ lb./sq. ft. Strip and structure complete-1½ lb./sq. ft. Light source: Fluorescent tubes are

fixed in continuous rows 3 ft. apart to wiring trunking, which in turn is fixed to the parent structure at approximately 15 ft. centres. The distance between the diffusers and tubes should not be less than 1 ft. 2 in. Finish: Pans are available in trans-lucent white or strong colours with a non-reflective under surface and may be fitted to project upwards (i.e. coffered) or downwards. Corrugated

Size: 3 ft. wide by a manageable length. Re-lamping and cleaning becomes difficult with very long

Joint: Extruded aluminium H section Joint: Extruded aluminium H section rumers, showing a 1.80 in. cover strip, or designed to take a clip-on sound-absorbent fin. Hangers are required at from 6 ft. to 8 ft. centres. Weight: No information supplied. Light source: Not less than 8 in. from

the diffuser, 15. Finish: No information supplied. Approximate cost: 9s/sq. ft., supply



13. Ionlite ceiling

vinyl strip is translucent white. Approximate cost: Ceiling plus electrical equipment 15s. to 21s.,sq. ft. (supply only and excluding wiring). (supply only and exchaing wiring). Framework and diffusers account for 50 per cent of this price.

Sound absorption: Perforated metal fins in 3 ft. lengths and filled with

Fibreglass may be clipped on to aluminium H sections in parallel lines or a complete rectangular grid.

### Ionlite Ltd.

Ionlite suspended ceiling Infill: Perspex (plain, moulded or with a regular design). PVC sheets with a regular design. Hardboard (plain or with perforations). Treetex sound-absorbent panels of various types, 13 and 14. Size: 2 ft. by 2 ft. grid or 2 ft. by

any length. (Other grid dimensions are possible.)

Joint: A pressed steel channel stove enamelled in any required colour can be sus-pended either way up to expose either pro-jecting fins with dished buttons on every intersection, a deeply recessed joint with circular plates cover-ing intersection, or, when this is fitted with a slide-in cover strip, a ceiling flush with the supporting grid. Cold cathode tubes are recom-


mended. Weight: No informa-

tion supplied. Light source: No special require-ments. This ceiling may be, but is not necessarily, fully illuminated.
Finish: The variety of possible infill panels is quite familiar and no special properties are claimed.
Approximate cost: 6s. 6d sq. ft.

supply only, the suspension and grid, ex works. 10s. sq. ft. supply only, as above but with PVC diffusers.

### **Lumenated Ceilings Limited**

Lumenated ceiling Infill: Corrugated vinyl diffuser.



14, construction of Ionlite ceiling showing inverted wiring channels.

Lumenator Module Material: Vacuum-formed vinyl or aerylie pans, 15. Size: 2 ft. by 2 ft. trays or 2 ft. wide

diffusers.

Joint: Visible V-shaped extruded aluminium track which is high-lighted and therefore not obvious,

Hangers are at 6 ft. to 8 ft. by 2 ft. centres.


Weight: 6 oz. sq. ft. complete with suspension.

suspension.

Light source: Fluorescent tubes should be more than 8 in. from the trays, and in any case this distance should be related to the distance between tubes by the ratio 1:14.


Finish: There are three standard. Finish: There are three standard pans—plain or moulded in concentric squares (see illustration). Specials to order.

Approximate cost: 9s./sq. ft. (supply



15, construction of Lumenated ceiling.

### SHILL



Scaffolding (Great Britain) Ltd. Metal Lathing Division, with lighting by Courtney, Pope (Electrical) Ltd.

SGB Flexible Grid ceiling Infill: Solid panels with recessed tungsten fittings or plastic or metal louvred fluorescent fittings to fit the

Size: Standard grid sizes are 2 ft. 3 in. by 2 ft. 3 in., 4 ft. 3 in. by 4 ft. 3 in. or 6 ft. by 3 ft.

Joint: A grid of 4 in. by 21 in. by 11 in. by 14 gauge galvanized pressed mild steel conduit channel is sus-

mild steel conduit channel is suspended from the parent structure, showing a projecting fin.

Weight: Varies as the ceiling is often arranged with only 50 per cent infilling (2 to 5 lb./sq. ft.).

Light source: The fittings are built into the panel infillings.

Finish: The grid is normally light in colour and since the light fittings do not rely on structural ceiling reflection, both ceiling and hangers are obscured by dark decoration if some panels are omitted. panels are omitted.

Approximate cost: Supply and fix Approximate cost: Supply and fix a grid ceiling based on a module of 6 ft. by 3 ft.—66s. 6d./sq. yd. Supply and fix a grid ceiling based on a module of 2 ft. by 2 ft.—102s./sq. yd. Other grid sizes pro rata.

### Tube Lamination & Engineering Ltd.

Plasmatic diffuser panels Material: Anti-static treated poly-

styrene extrusion with small corrugations

Size: 10½ in. by up to 4 ft. (2 ft. and 4 ft. lengths standard), 19. Joint: Deeply recessed V (lapped).

Weight: 10 oz./sq. ft. Light source: Independent fluorescent tubes 4½ in. above joints (10½ in. centres).

Finish: Clear or translucent opal.

Approximate cost: 50s./sq. yd.

If the panels are over 4 ft. wide then intermediate extruded poly-styrene translucent supporting Ts will be required, but they are normally intended to span between the extruded aluminium sections of standard suspended ceilings. The manufacturers claim that the material has been tested to the equivalent of 7,200 hours brilliant sunshine without vellowing.

### **Electrically heated** ceilings

Only two electrically heated ceilings have come to hand at the ceilings have come to hand at the time when this article was compiled, and both of these are adaptations of non-heated ceilings. The first, the Burgess system, consists of heating cables haid over the firm's standard metal tiles and backed with an insulating quilt. The second, the Heatacoust by Petradene Ltd., is a prefabricated plaster ceiling, and involves the bedding of the heated element in the plaster tile which is element in the plaster tile which is

identical in appearance (when seen from below) to the same firm's standard Supacoust tile. The latter is one of the few heated ceilings which have been designed in this country, and has a logic and tidiness about it which has great appeal.

### Burgess Products Company Ltd.

Electrically Heated, Acoustic Tile Ceiling

The metal pan tiles and spring steel
Ts are identical to those described in the previous article, but mineral insulated electric cables are fixed to the general suspension and can be connected to the normal power circuit with a thermostatic control which gives a quick response. The usual sound absorbent blanket is unrolled over chicken wire above the electric cables to provide thermal



20. wiring circuit of Burgess electrically heated

Wattage is 20 watts per sq. ft. (average).

The surface temperature of the tiles is 90° to 100° F.

The temperature of the cable is 180° to 200° F and that of the void between tiles and blanket is 140° to 150° F. This gives a room temperature of from 60° to 65° F. Approximate cost: 75s. to 100s./sq. yd. supplied and fixed.

### Petradene Ltd.


Heatacoust

These tiles are identical in appearance to the Plaster of Paris 'Supercoust' tiles described in the previous article, but a cupro-nickel wire wound around a silken core and insulated with PVC is embedded in the tiles between each row of per-forations. This continuous heating torations. This continuous neating wire terminates at a plug in the centre of the tile (with removable brass prongs for packing) so that a junction box (with socketed leads) fitted to the structural slab above can neatly serve groups of up to four tiles without demanding any precision in initial electrical work, 21.

The system operates on an air temperature of approximately 55 F the manufacturers recommend one-third Heatacoust and two-thirds Supacoust.

Size of tiles: 2 ft. by 2 ft. or 1 ft. 8 in. by 1 ft. 8 in. (specials to order). Watts: 60, 75 or 100 per tile. Surface temperature: 105 to 110 F.

Approximate cost: Based on an area of 1,000 sq. yds. and assuming onethird Heatacoust and two-thirds



21, Heatacoust heating by Petradene.

Supacoust the cost for supplying and fixing would be approximately 63s. sq. yd.

### Water-heated ceilings

By comparison with the electrical heating systems these seem rather clumsy, but while the capital costs are evidently higher they are no doubt cheaper to run at present, even if there is the need for fuel storage and stoking. Looking ahead, however, one always hopes that electricity will get cheaper, and certainly one cannot foresee any similar hopes for solid fuel.

In all three systems it is important to have a really good contact between the tiles and the heating coils so that the heat is conducted to the radiating surfaces.

The Frenger ceiling would seem to be the most straightforward, and has certainly been widely used. More light fittings manufacturers claim to make modular fittings suitable for this type of ceiling than any

other.

Despite the co-operation of three firms, the Stramax ceiling can wind up with three separate suspension systems, which surely seems rather


In the Burgess Sulzer ceiling, the spring T bars which hold the tiles are not connected to the heating coils but must be held firmly against them, and this would seem to call for considerable precision.

The prices quoted do not include electrical installation, light fittings or connecting up to the heating

### Burgess Products Ltd.

Burgess-Sulzer Heated Ceiling

The Burgess metal pans and fixing Ts are identical to those described in the previous article, but the Ts are supported by cleats to M.S. angles which are suspended from the parent structure. Hooked rod hangers from the M.S. angles support sinuous heating tubes at 6 in. centres which



22. Burgess-Sulzer heated acoustic ceiling.

must be in contact with the Burgess spring steel T bars. A sound absorbent and heat insulating blanket is laid over the heating coils, 22. Three light fitting manufacturers can supply module fittings specifically adapted for this ceiling. Hopes Heating and Engineering Ltd. are one firm of heating contractors who will supply and fix this ceiling. cost: 110s, sq. yd. Approximate supplied and fixed.

### Frenger Ceilings Ltd.


Frenger Suspended Heated and Acoustic Ceiling

Although this ceiling may be used without heating (i.e. the heating coils left dry) it is essentially a heated


coils left dry) it is essentially a nearca-ceiling system.

‡ in. M.S. rod hangers (at approxi-mately 4 ft. centres) hang from a radial fixing box to take up tolerances. On the hangers are suspended 1 in. by 1½ in. by 18 SWG channels which are welded

[continued on page 206



### SILILI continued from page 204]



23. Frenger suspended heated ceiling

to the i in. O.D. sinuous heating coils (at 2 ft.  $0\frac{1}{2}$  in. centres). 2 ft. by 2 ft. nominal pressed aluminium Pyluminized plain or perforated pans are shaped on two parallel edges to fit around the heating coil tubes and held firmly in position by spring steel clips, 23. These flanges being in direct contact with the tubes act as radiators. Bitumen bonded fibre-glass 14 in, thick, faced with staple tissue on the underside, is laid in tissue on the underside, is faid in strips over the coils, and apart from heat insulation this gives a rever-beration absorption coefficient which is highest in the middle range of


frequencies (i.e. 0.70 at 500 c/s.), The panels are normally painted with flat oil paint after erection, and some eleven light fitting manu-facturers produce module fittings specially adapted for use with this particular system.

particular system.
Thermal capacity: Extremely low at about 0.45 BTU's per sq. ft.
Approximate cost: 81s./sq. yd. supplied and fixed would be a typical

price for a well insulated building in the London area. (This is based on a ceiling of 4,500 sq. ft.)

# Stramax Ceilings (GB) Ltd., Clark and Fenn Ltd., and AEI Lamp and Lighting Company, Ltd.

Stramax Heated Ceiling (developed



24. Stramax heated ceilir

by Stra-Max International Research

by Strat-Max International Research and Development Centre, Zurich). Stramax \(\frac{1}{2}\) in. I.D. pipe coils are suspended by rustless hangers (which need not be permanent) from the parent structure, and a separate system of secretly suspended steel Ts support the 2 ft. by 2 ft. de-mountable Clark and Fenn gypsum plaster ceiling tiles (see previous article) which for the heated part of the ceiling are fitted with an aluminium alloy cradle which must touch the heating pipes and be attached to them by a slotted saddle clip, 24. A mineral wool blanket insulation is placed over the heating coils and separate sound absorbent pads and separate sound absorbent pads are fitted in perforated tiles. The AEI Lamp and Lighting Company can supply module fittings specially adapted for this ceiling and independently suspended.

Weight (without light fittings) approx. 6 lb. per sq. ft.

With a mean water temperature of 150° F and a ceiling surface temperature of 100° F the room temperature will be 65° F.

Annovalumate cost. 90s. to 108s so.

Approximate cost; 90s, to 108s, sq. yd. average (supplied and fixed). Large well insulated areas 81s. sq. yd. Small poorly insulated areas in a Small poorly insulated areas in a remote district might run to 135s. sq.

### THE INDUSTRY

### **Bath Production**

Bilston Foundries Ltd., the makers of the Atlanta bath, have overflowing order books. Seeing that present pro-duction methods were unable to meet demand, the company decided to install completely new plant in new premises. The most startling change accomplished was that the number of man-hours per bath dropped by as much as 75 per cent. The fully mechanized plant produces one bath every working minute and so far as is known it is the only one which has been built from scratch for the sole purpose of producing baths. The intention is to increase production of the Atlanta bath in all sizes, 54 in., 60 in., 61 in. (available in two widths), 66 in. and 72 in. lengths. In the future new designs will be produced in response to demand.

Bilston Foundries Ltd., Highfields, Staffs.

### Window Catalogue

James Gibbons Ltd. have issued a James Gibbons Ltd. have issued a new window catalogue which deserves attention. It is divided into parts, each of which has an ingenious method of referencing so that win-dows incorporating various metal sections may be appreciated without constant page turning. One part is devoted to double glazing units, and there is also a section describing the there is also a section describing the Windowall system of curtain walling. The whole catalogue is bound so that it lies flat on a desk or drawing board, and generally should be found useful. James Gibbons Ltd., 74 Southampton Row. W.C.1.

### **Guidance on Slates**

Redland Stonewold Interlocking slates have been available for some time, and are becoming increasingly popular. Our attention has been drawn to a new brochure illustrating drawn to a new brochure illustrating these slates. The point of interest is the low roof pitch. In the past they have been used successfully at 20 degrees, but the makers cannot undertake to guarantee them as waterproof at this pitch, though they are prepared to do so at 221 degrees. provided that the supporting roof structure conforms to their specification. The cost of natural slate being so high relative to other materials, Redland slates offer a very welcome alternative. The brochure gives tech-nical information in a clear and readable manner together with drawings of a complete suggested roof system. The interlocking slates are available in three colourings, Lichen Green, Moorland Stone, and Slate Grey, and the weight per Square is approximately 9½ ewt. The size of each slate is 17 in. by 15 in., minimum headlap being 3 in. Another Redland product recently introduced to the Pantile, which, like all Redland products, is guaranteed for 50 years. A brochure illustrating this product has also recently been issued. The tiles are available in eight colours.

Redland Tiles Ltd., Castle Gate, Reigate, Surrey.

### **School Light Fitting**

A difficulty about choosing light fittings for schools is that the more

[continued on page 208



### THE DARLINGTON INSULATION CO. LTD.

specialise in: SUSPENDED DECORATIVE & ACOUSTIC CEILINGS ARCHITECTURAL ACOUSTICS, SOUND ABSORBING DEVICES & NOISE REDUCTION


.... to benefit from their know-how and experience, simply write to:

THE DARLINGTON INSULATION CO. LTD.

Tynos Works, Scotswood, Newcastle-upon-Tyne, 5.

Telephone: Lemington 674658

CONTRACTORS FOR THE CELOTEX SYSTEMS



Architect: Ronald Fielding, A.R.I.B.A.

Consulting Engineers: W. S. Atkins & Partners

Building Contractors: Richard Costain Ltd.

Approximately 10,000 yards of BISON Plank Flooring and Roofing (delivered only) incorporated in Consulting Engineers' frame Design. 25 yds. of Plank were raised at each hoist direct from lorry.



BISON floors, beams and concrete frame structures

CONCRETE LIMITED are the largest structural precast concrete manufacturers in the world

CONCRETE LIMITED Green Lane, Hounslow, Middlesex Hounslow 2323 and Dovehouse Fields, Lichfield, Staffs. Lichfield 3555 London Sales Office: 16 Northumberland Avenue, W.C.2 Whitehall 5504
CONCRETE (NORTHERN) LIMITED Stourton, Leeds 10 Leeds 75421 Manchester Office: 40 King Street West, Manchester 3 Blackfriars 5676
CONCRETE (SCOTLAND) LIMITED Elmbank Street, Glasgow C.2 City 3292

CON, 109a

### continued from page 206]

pleasant ones tend to be too expenpleasant ones tend to be too expen-sive. A useful addition to the range of choice is Siemens Edison Swan Ltd.'s 'school fitting.' An opal glass bowl is held by three knurled head



1. Siemenz Edison Swan opal glass light bowl

screws to an aluminium gallery, which may be fixed to the ceiling or suspended. The glass bowl has a generous hand hole which makes lamp replacement easier, and hence increases the chance of actually getting defective bulbs replaced by caretakers—a practical point which can save much annoyance. Prices are not unreasonable and the fitting is available in 200 watt and 150 watt sizes. Clearly its use is not limited to schools and it is to be hoped that, though not spectacular, it may sometimes be used to replace the globe which hovers so ubiquitously in offices and schools,

Siemens Edison Swan Ltd., 155 Char-ing Cross Road, London, W.C.2.

### More Small Patterns in Mela-

Last month we welcomed a new

range of melamine sheet using very small-scale patterns, as this seemed to us the right way to use this smooth, hard—and quite unprecedented— material. Now another small-scale pattern range has come in, 'chosen in collaboration with' Ward and Austin





(a firm of architects who have often contributed articles to the AR). This is the new Decorplast range, mar-keted by Holoplast Ltd. It consists fected by Hotopiast Ltd. It consists of 47 new colours and patterns and these are to be joined (and, by the time you read this, will have been joined) by seven photographic wood veneers. Three of the patterns we illustrate, to full size, above. It will readily be seen that patterns with

this degree of delicacy require that the architect should show a corresponding delicacy in his detailing. The days of the clumsy cover-strip ought to be over.

Holoplast Ltd., 116 Victoria Street, S.W.1.

### Dohm Decor


A new and interesting material for A new and interesting material for achieving brilliant colour externally has just been marketed, known as Dohm Decor. It is a finish which can be sprayed on to a prepared surface of concrete, brickwork, render, wood, etc., and produce a permanent decorative and waterperiod coating. It is inexpensive when compared with natural facing ma-terials (exclusive of labour, the cost is between 3s. and 4s. 6d. per square yard) and it may also be glazed. Basically it is conceived as a decora-tive protective finish which may be applied to most building materials. The colour is good. The finished surface is granular, and may be cleaned down by normal methods. It would appear to be a useful addi-tion to the range of internal and external colour finishes, and might be employed very successfully on old and new work alike. Time will expose any weaknesses, but in the mean-while it has the great advantage of being easy to handle. Normal spraying techniques are used and no special equipment is required. Dohm Ltd., 167 Victoria Street,

London, S.W.1.

### Consumers Control Unit for Underfloor Heating

It is a sign of the times that underfloor heating by electric off-peak load is sufficiently common for the manufacturers of equipment to produce ancillary fittings specifically for it. We illustrate below Midland Electric's consumer control unit for a heating circuit only. The same firm also produce a version which incorporates both according to the company of the company of the control o both normal day load and night load





introl unit for heating circu [continued on page 210





APPOINTMENT TO HER MAJESTY THE OUTEN SUPPLIERS OF WALLPAPERS AND PAINTS JOHN UNE & SONS LTD

## JOHN LINE & SONS LTD

MAKERS OF FINE WALLPAPERS & PAINTS

213-216 TOTTENHAM COURT ROAD LONDON · W.1

Our showrooms with a display of up-to-date schemes, are at your service and a competent sales staff will gladly render you and your clients every assistance

OUR SHOWROOM SERVICE

\* Nearest branch showroom address sent on request



# people are beginning to expect warmth and comfort — peace and quiet with

FIBREGLASS

FIBREGLASS LTD.,

ST. HELENS, LANCS

· ST. HELENS 4224

### continued from page 2081

off-peak switching. As you can see, the unit is neat: it is also small, being only 12 in. by 12 in. by 5 in. It is cased in sheet steel and the cover is sealable.

Midland Electric Manufacturing Co. Ltd., Reddings Lane, Tyseley, Birmingham.

### CONTRACTORS etc

Offices at Birmingham. Architect: Erno Goldfinger. Assistant Architect: John Duncan. Quantity Surveyor: Davis, Bellield & Everest. Engineer: Dr. K. Hajnal Konyi. General Contractor: C. Bryant & Son. Soil exploration: Ground Explorations Ltd. Piling: Cementation Co. Stahlton floors: Costain Concrete Co. Precust concrete: Liverpool Artificial Stone Co. Asphalt tanking and roofing: Neuchatel Asphalte Co. Thermoplastic floor: Neuchatel Asphalte Co. Marble floors: Anselm Odling & Sons. Suspended ceilings: Clark & Fenn Ltd. Partitioning: The Morris Singer Co. Thermal insulation in ducts: Celeon Ltd. Metal windows: Williams & Williams Ltd. Glazing: Aygee Ltd. Armourplate doors and plate glass: James Clark & Eaton Ltd. Metalwork: Wessex Guild Ltd. Ironmongery: J. D. Beardmore & Co. Paint: T. & W. Farmiloe Ltd. Services: Heating and hot water: Etna Lighting & Heating Co. Radiators: Copperad Ltd. Ventilation: Hopes Heating & Engineering Ltd. Electrical and electrical floor warming: L. H. Banks. Sanitary fittings: Stitsons Sanitary Fittings Ltd. Lifts: Bennie Lifts Ltd. Furniture: Hampton & Sons Ltd.

Nottingham University, Portland Building. Contractors on the section

designed by John Wright, F.R.I.B.A., as follows: Main contractor: Trollope & Sons (London) Ltd. Carpets: L. and C. Steele Ltd. Wallpapers: Cole & Sons Ltd. Chairs: L.M. Furniture Ltd. Curtain fabrics: Edinburgh Weavers Ltd. Fibrous plaster: F. Dejong & Co. Light fittings: General Electric Co.

Nottingham University, Fine Art Wing.
Architect: H. T. Cadbury-Brown,
F.R.I.B.A. General contractor: John
Laing & Son. Acoustic ceiling tiles:
Tentest Fibre Board Co. Spot
light fittings and plastic egg-crate
ceiling: Harris & Sheldon Ltd.
Colour-matching fluorescent light
tubes: General Electric Co. Standard
light fittings: Merchant Adventurers
Ltd.: Geo. Forrest & Son. Metal
shelves and gallery: Sankey-Sheldon
Ltd. Gallery brackets and balustrade,
circular stairs, aluminium picture
rails: G. Johnson Bros. Ltd. Fabric
wall covering (Canotex): Arthur Sanderson & Sons. Carpets: Hampton &
Sons Ltd. Wallpaper: Primavera Ltd.
Tables, desks, cupboards, settees (designed by the architect): Trevor,
Page & Co. Fibreglass chairs: Aidron
Duckworth. Upholstered chairs: Hille
of London Ltd. Door furniture: W. J.
Rinns Ltd.

Offices at Davies Street, W.I. Architects: J. M. Austin-Smith & Partners. Main contractor: Holloway Bros. Ltd. Sub-contractors: Venetian blinds: Horsley Smith & Co. Electrical work: Buchanan & Curwen Ltd. Suspended ceiling: John Dale Ltd. Iron staircase: H. & C. Davis & Co. Ironmongery: G. & S. Allgood. Fireproof door: Dreadnought Fireproof Doors. Flooring: Inlaid Rubolin. Door handles: Comyn Ching & Co. Carpets and curtain fabrics: Heal & Son. Light fittings: Flurosel Ltd. Furniture: Libertys. Special typists' chairs: Office Machinery Ltd.

Factory at Berkhamsted. Proprietor:
Lake & Cruickshank Ltd. Architects: Architects: Co-Partnership.
General contractor: J. L. Constantine & Co. Factory foundations and reinforced concrete: London Ferro-Concrete Co. Bricks: Pratt (Watford) Ltd. Structural steel: A. A. Thornton (Teddington) Ltd. Special roofings: W. H. Walker & Co.; H. Newsum & Co.Roofing felt: William Briggs & Sons. Patent glazing: Williams & Williams. Patent and woodblock flooring: Hollis Bros. Ltd. Central heating systems: Weatherfoil Heating Systems Ltd. Electrical installations: Rashleigh Phipps & Co. Sanitary fittings: Adamsez Ltd. Door funiture: A. G. Roberts Ltd. Fireproof doors: Gliksten Doors Ltd.

Theological College in London. Architects: Yorke, Rosenberg and Mardall. General contractors: Bovis Ltd. Subcontractors: Ironmongery: H. & C. Davis. Electrical work: B. French Ltd. Tiling and tile mural: Carter (London) Ltd. Steel windows: Aygee Ltd. Metal work: Wessex Guild Ltd. Sanitary fittings: Stitson's Sanitary Fittings Ltd. Block and strip flooring: Hollis Bros. Ltd. Cork floors: Jos. F. Ebner (1953) Ltd. Roofing: William Briggs & Sons Ltd. Fire protection: Associated Fire Alarms Ltd.; Read & Campbell Ltd. Flush doors: Gliksten Doors Ltd. Roller shutters: Haskins Ltd. Light steel trusses: R. Smith (Horley) Ltd. Heating, ventilation and plumbing: R. J. Audrey Ltd. Duet covers: Broads Manufacturing Co. Portland stone: South Western Stone Co. Lift: Keighly Lifts Ltd. Curtains: Heal's Contracts Ltd.; Russell Furniture Ltd.; Hille of London Ltd. Purposemale furniture: Lord Roberts Workshops; H. Ventress. Light fittings:

Merchant Adventurers of London Ltd.; Fredk. Thomas & Co.

House at Coventry. Architect: Duncan Kay. General contractors: E. Harris & Son. Sub-contractors: Copper roofing: Hugh Twaddle & Son. Heating and hot water, warm-air heating with V. oil-fired unit: Radiation Ltd. Sanitary fittings: Griffin Fireplace & Sanitary Fittings Ltd. Wood blocks: Hollis Bros. Ltd. Lino floors: Limmer & Trinidad Lake Asphalte Co. Windows and ironmongery: James Gibbons Ltd.

Flats at Lambeth. Architect: Leslie G. Creed. General contractors: Wates Ltd. Sub-contractors: Slate cills: Bow Slate & Enamel Co. Refuse chutes: Broads Manufacturing Co. Radio and TV installation: British Relay Wireless Ltd. Vermiculite screed: E. E. Cheeseman & Sons. Heating stoves: Caledo.' Metahwork: Clark, Hunt & Co. Glazing: Faulkner Green & Co. Lightning conductor installation: J. W. Gray & Son. Insulation quilt: Haine & Corry Ltd. Lift installation: Hammond & Champness Ltd. Steel cills and ventilators: Henry Hope & Sons Ltd. Storage lank: Newton Chambers & Co. Tiling: H. H. Nutman Ltd. Partition slabs: Oakes Bros. Bricks: R. Passmore & Co. Asphaltroofing and paving: Ragusa Asphalte Co. Joinery: Rippers Ltd.; John Sadd & Sons. Flooring tiles: Semtex Ltd. Sanitary fittings: Stitsons Sanitary Fittings Ltd. Flue linings: True-Flue Ltd. Electrical: F. H. Wheeler Ltd. Ironmongery: Yannedis & Co.

### Advertisement

DUROMIT TILES—Decorative and Industrial. The only Tile with the diamond hard aggregate. Agents wanted. Box No. 9980





furnished by

Contracts, Third Floor

Harrods

Specialists in the planning & furnishing of executive suites and offices

HARRODS LTD

SLOane 1234

LONDON SWI



# How will you operate your air conditioning and heating plant? The right answer is THERMOCONTROL

### THERMOCONTROL serves:

Architects
Consulting Engineers
Heating and Air Conditioning
Contractors
Factory and Property Owners

### THERMOCONTROL has achieved:

Temperature and humidity control for human comfort for scientific processes for substantial savings in fuel

### THERMOCONTROL manufactures:

The most complete range of British manufactured electronic controls for Air Conditioning Heating Refrigeration Boiler Plant

Electronic Control of Heating and Air Conditioning, Boiler House Instruments by THERMOCONTROL.

### THERMOCONTROL provides:

An unparalleled advisory service by qualified electrical, combustion, air conditioning and chemical engineers.




Have you read the THERMOCONTROL Compendium, Section I
"The field of Automatic Control in Modern Industry?" If not, please write for a copy,



THERMOCONTROL INSTALLATIONS CO. LTD., 2-10 Valentine Place, London, S.E.I.

Telephone: WATerloo 7356

# WHEN NO MERE SUBSTITUTE WILL DO



### SUSSEX HYPALON FLOOR TILES

Over 50 years of experience and research in elastomer technology, have enabled the Sussex Rubber Co. Ltd. to create this superb HYPALON Tile.

Stringent tests have proved the "HYPALON" to have amazing resilience; resistance to staining, cracking, fading in direct sunlight, and movement in extremes of temperature. Sussex Hypalon Tiles are available 3113333 in a wide range of beautiful colours, attractively marbled, INDUSTRIAL DIVISION 12" x 12" x 1 "thick, and are IDEAL for outdoor use. SERVICE TO

### SUSSEX RUBBER FLOOR TILES

These first-quality rubber floor tiles, obtainable in a wide range of attractive colours, are hardwearing, resilient and economical.

For full information please write to SUSSEX RUBBER COMPANY LIMITED . SCHOOL ROAD . LONDON N.W.10



GEO. H. GASCOIGNE CO. LTD., GASCOIGNE HOUSE, READING, BERKS Telephone READING 54417 (3 lines)

# FRENGER HEATED & ACOUSTIC CEILINGS


# do you realise

MILLIONS of square feet are erected EACH YEAR

on MARCH 1st we REDUCED our PRICE by  $12\frac{1}{2}\%$ 

Luton & South Bedfordshire College of Further Education.

Architects: Norman & Dawbarn, F.R.I.B.A.
Heating Engineers: G. N. Haden & Sons Ltd., London.



Write for more details to

FRENGER CEILINGS LTD · 7-12 TAVISTOCK SQUARE · LONDON · W.C.I · Telephone: EUSton 6084/8
12 HARTER STREET, MANCHESTER, I. CENTRAL 46/2 · 65 BALFOUR AVENUE, BELFAST. BELFAST 28768

### GEORGE PARNALL

AND COMPANY LIMITED



The Specialists in



Store Modernisation

4 BEDFORD SQUARE · LONDON · WCI · MUSEUM 7101 WORKS: BRISTOL




# RADIATORS BY CRANE

Bishop's House, the fine modern building which is part of the new Holborn development scheme, is heated throughout by Crane Pall Mall radiators – some 490 units in all. The types used comprise 2, 4 and 6 column in heights 18", 24" and 36". Crane Radiators are made in cast iron. As well as doing a first class job of maintaining a comfortable temperature everywhere, harmonising unobtrusively with their surroundings, they give long, hardworking service, free of maintenance costs.

Trehearne & Norman, Preston & Partners, London, W.C.2
HEATING ENGINEERS

Young, Austen & Young Ltd., London, W.C.I

CONSTRUCTORS
Token Construction Company Ltd., London, W.1



# CRANE HEATING EQUIPMENT

CRANE LTD., 15-16 RED LION COURT, FLEET STREET, LONDON, E.C.4. WORKS: IPSWICH Branches: Birmingham, Brentford, Bristol, Glasgow, London, Manchester

### RECOMMENDED BY THE BOOK SOCIETY

# THE ENGLISHNESS OF ENGLISH ART




## by Nikolaus Pevsner

THE 1955 REITH LECTURES, re-written to almost twice their original length, and fully annotated. With 130 illustrations in line and halftone. Demy 8vo. 208 pages.

Price 16s. net, postage 1s. 2d.

THE ARCHITECTURAL PRESS, 9-13 QUEEN ANNE'S GATE, WESTMINSTER, S.W.1.

Shanks







# a new development in steel by Sankey-Sheldon

of course!

'Picture Window' steel partitions, with their wide, unimpeded spans of glass, create a sense of space and visual freedom in keeping with modern architectural concepts while retaining all the practical advantages of Sankey-Sheldon flush partitioning. Apart from the new scope provided for more effective interior design, the admission of maximum daylight is an important functional advantage in view of the current trend towards larger floor areas. Assembled from standard component parts, 'Picture Window' partitions are economical and competitively priced. You are invited to write to Sankey-Sheldon for further information.





Sheldon

LIMITED

A member of the Guest, Keen & Nettlefolds Group of Companies

46 Cannon Street, London, E.C.4 - Telephone: City 4477 (18 lines) - Telegrams: Sankeshel, Cannon, London.

STEEL DESKS . TABLES . CHAIRS . FILING CABINETS . FILING SYSTEMS

CUPBOARDS . CLOTHES LOCKERS . SHELVING . STORAGE BINS

LIBRARY EQUIPMENT . UNISTRUT METAL FRAMING SYSTEM

Branches in: Belfast, Birmingham, Bristol, Cardiff, Coventry, Edinburgh, Glasgow, Leeds, Leicester, Liverpool, Manchester, Newcastle-upon-Tyne and Sheffield.



here's where POLICROME scores ....

... from ONE tin of Policrome a beautiful multi-coloured pattern is sprayed with one gun. Policrome is ready for use in the tin-you see the pattern when you lift the lid. Policrome is not just a paint - it's a decorative scheme in itself - and extremely tough and hard wearing too. If you haven't full details of Policrome at hand please write to us today.

Flame Eternal. Symphony and Nocturne from the range of 17 Policrome patterns were used for the interior of the South Eastern Gas Board's Croydon Showrooms.

Walter Watson A.R.I.B.A. Contractors: J. Garrett & Sons Ltd.,

# International Paints Ltd.

GALLERY 7070 (15 LINES)
FAST CARDIFF GLASGOW
NEWCASTLE SOUTHAMPTON



MAIN FACTORY IN U K -FELLING-ON-TYNE

ASSOCIATED FACTORIES IN



# HOPE'S

# Standard Reversible Windows

CAN BE CLEANED, GLAZED AND PAINTED FROM WITHIN

PATENT APPLIED FOR



1. Open for ventilation



2. Releasing the casement



3. Reversing the casement



4. Cleaning the outside

Specially Designed to Reduce Maintenance on Multi-storey Dwellings

Send for List No. 352

HENRY HOPE & SONS LTD

Smethwick, Birmingham & 17 Berners Street, London, W.1

MEMBER OF THE METAL WINDOW ASSOCIATION



Now the Gliksten companies listed below supply Britain's wood-using industries with a wide and ever-expanding range of woods and allied products.

In addition, they offer specialised facilities such as kiln-drying, and technical advice on the best and most economical use of timber.

Whatever your needs in wood, get in touch with

### J. GLIKSTEN & SON LTD.

Carpenters Road, Stratford, London, E.15.

Telephone: AMHerst 3300

THE COMPANIES OF THE GLIKSTEN GROUP: Hardwoods: J. GLIKSTEN & SON LIMITED. Softwoods: MEREDITHS LIMITED Plywood: THE NATIONAL PLYWOOD CORPORATION. Decorative Veneers: J. GLIKSTEN & SON LIMITED Building & Insulating Board: GLIKSTEN BUILDING MATERIALS. Doors: GLIKSTEN DOORS LIMITED





sal, Senior), Car and Cycle Shelters, Tool Lockers, Adjustable Steel Shelving.

Please write for illustrated Catalogue AR 2

ABIX (METAL INDUSTRIES) LT

POOL ROAD, EAST MOLESEY, SURREY

Phone: Molesey 4361 3

Grams: Abix, East Molesey

### THE LOWEST COST ANSWER TO LARGE SCALE CLEAN AIR ZONE CONVERSIONS



# SUNBEAM CLEAN-AIR FIRE

The Sunbeam Clean-Air Fire is specifically designed for use in Smoke Control Areas where large scale conversions etc., necessitate the provision of a fully approved fire at the lowest possible cost. It complies with all requirements laid down under British Standard Specification 2845/1957, and can consequently be safely specified without need for further confirmation.

The Sunbeam Clean-Air Fire does not require additional deepening bars or extension plates, and resulting from its simplicity of design the previous need for fire bricks, separate bottom grate legs etc., has been eliminated. These factors allow for reduced breakage and fitting risk, simplified later maintenance, and an appreciable reduction in the necessary stocks of spare parts carried.



The Sunbeam Clean-Air Fire carries the British Standards Institution "Kite Mark" which indicates certification of compliance with B.S.2845 [1957. This certificate provides for independent examination and inspection of manufacture in our works, and is consequently a further assurance of quality.



PRICE **£2 - 17 - 6** (INCLUDING GAS IGNITION)

USUAL TRADE DISCOUNTS


about the

Sunbeam

Smoke-Consuming STOVE?



CHATWINS LTD., TIPTON, STAFFS



# Paragrid dile

### A NEW TYPE OF LUMINOUS CEILING UNIT

GOOD LIGHTING knows no frontiers but draws inspiration from good practice the world over. This wide outlook is typical of Harris & Sheldon, who introduced Luve-tile and Luveline to this country and are now again collaborating with Wilsons of Canada to produce Paragrid-tile, another superb tool for the lighting designer.

# "Paragrid-tile" combines elegant appearance with superb luminous and diffusing qualities.

The unique construction and slender proportions of the  $16^{\circ} \times 16^{\circ}$  polystyrene tile are clearly shown in the above photograph. The advantage of a louvered ceiling is maintained, yet at the same time the small sized cells give an appearance of a translucent diffusing panel.

\* There is a Handslite lighting fitting for almost every lighting application, and we specialise in the design of fittings to suit individual requirements.

Write for fully illustrated lighting the suit individual requirements.



#### THE BEST OF BOTH WORLDS



### Harris & Sheldon (Electrical) Ltd.

RYDER STREET, BIRMINGHAM 4. Telephone: Central 6272 London Office: 46 GT. MARLBOROUGH STREET, W.1. Telephone; GERrard 0969

Complete Lighting Specialists and Manufacturers of Lighting Fittings and Control Gear

DHB 7323

# GYPROC solved the

acoustic problem in the Restaurant

of the Tate Gallery with . . .



These 2 ft. square, attractive bevel-edged tiles are high quality precision products. The slots which are the distinctive feature of the tile have been designed to provide optimum sound absorption when used with a suitable porous backing. As the tiles are manufactured from 1° thick gypsum plasterboard there is a high measure of fire protection. The tiles themselves present pleasant decorative elements. The slots and the 45° bevels on all face edges supplement a decorative scheme. All facts on sound absorption co-efficients, fire resisting characteristics, and methods of fixing, will be sent on request. Write for leaflet ARP 361

Architect: W. KENDALL, A.R.I.B.A.

Senior Architect in the Chief Architects' Division, Ministry of Works.

Gyproc Slotted Acoustic Tiles erected by Gyproc Products Ltd., Contracts Department.

### GYPROC PRODUCTS LIMITED

Head Office: Singlewell Road, Gravesend, Kent. Gravesend 4251/4 Glasgow Office: Gyproc Wharf, Shieldhall, Glasgow S.W.1. Govan 2141/3 Midland Sales Office: 11 Musters Road, West Bridgford, Nottingham. Nottingham 82101 London Office: Bath House, 82 Piccadilly, London W.1. Grosvenor 4617/9 S/A.G.—



### LIGHTING AT LLOYD'S OF LONDON



# 'THE ROOM'

The General Electric Co. Ltd. has supplied the majority of the lighting fittings for Lloyd's—London's largest new building. 'The Room' is illuminated by approximately 15,000 ft. of Osram cold cathode tubing installed in the laylights and 600 circular fittings.

Architect: T. E. HEYSHAM, F. R. I.B.A.
Consultants: OSCAR FABER & PARTNERS
Contractors: HIGGINS & CATTLE LTD.



The General Electric Co. Ltd., Magnet House, Kingsway, London, W.C.2

The solution to Your problem may be a...



A FLEXIBLE SYSTEM OF PREFABRICATED CONSTRUCTIONS

ENKAST

**∠**building

For Details and Full Technical Service


KENKAST CONCRETE LIMITED ASTLEY . MANCHESTER

Telephone: ATHERTON 729




Write for Catalogue to:

JOHN WILLIAMS & SONS (CARDIFF) LTD EAST MOORS ROAD CARDIFF



Today the graces are entering public places. There's a new awareness of the importance of surroundings, in offices, schools, hospitals, clubs, hotels, and factories. Whether you need a boardroom chair that's in tune with your firm's philosophy, or a complete scheme worked out for you from drawing board and blueprint to curtains and carpets, Liberty Contracts are the people to consult. Here you will find wide experience, sound knowledge of design and an enviable reputation for quality and friendly service. Liberty & Co Ltd, Regent Street London W1. Regent 1234.





Head Office, Works and Showroom: WATTVILLE ROAD, HANDSWORTH, BIRMINGHAM, 21
London Showroom: 25 MUSEUM STREET, W.C.1



"In this act 'dark smoke' means smoke which, if compared . . . with a chart known . . . as the Ringelmann Chart, would appear to be as dark as or darker than Shade 2 on the chart."

### No. 3 RINGELMANN

IS A FLAGRANT OFFENCE UNDER THE ACT

#### No. 2 RINGELMANN

FAILS TO COMPLY WITH THE ACT

### No. 0 RINGELMANN

IS ASSURED WITH THE:

# **OLDBURY**

### CHAIN GRATE STOKER

which anticipated the Clean Air Act by 14 years

Today more than 5,000 Oldbury Stokers are serving industry, burning solid fuels in the widest variety, EFFICIENTLY, SMOKELESSLY. Leave nothing to doubt. To comply with the Act, consult Edwin Danks at Oldbury or the nearest Branch Office.




### **EDWIN DANKS & CO**

(OLDBURY) LTD.

OLDBURY near BIRMINGHAM

Tel.: (Stoker Division) Brierley Hill 7731

LONDON • CARDIFF • GLASGOW • LEEDS
MANCHESTER • NEWCASTLE-ON-TYNE



"To a chap like me – and I'm proud of my work – my pencil's my living.

The pencils I use have to stand up to fast hard work, their grading's got to be absolutely spot on – not almost or nearly but bang on the dot every time.

The leads must hold their points and flow smoothly throughout a long line—no crumbling or 'clinkers' mark you!—and if I erase a line it must go cleanly—there's no 'furrow' left in my paper so you won't find ghost lines in prints—made off my drawings. As a matter of fact you can tell from a print when it is my drawing—the print's always first class."


"What pencils do I use?"

"Venus drawing pencils of course, the ones with the crackle finish!—how else do you think I keep up my high standard?"



\*VENUS Drawing pencils are made in 17 accurate grades from 9H to 6B.

THE VENUS PENCIL CO. LTD., LOWER CLAPTON RD., LONDON E.5



### Look at it from every Angle



LOADMASTER is Tops!

The DORMAN LOADMASTER Miniature Circuit Breaker offers outstanding advantages in quality, performance and price. Take a look at the performance figures, that's the right angle to start with Examine it from a quality angle and see what a high degree of compactness and durability has been achieved. Lastly, the angle which many of us feel acutely, that of price, single pole units only 18 8d. each, double pole units 6o - each and triple pole units 96 - each, list. Units available in ratings of 5, 10, 15, 30, and 50 amps.

S. P. & N. Distribution Boards up to 16 way, T. P. & N. Boards up to 12 way.

SINGLE POLE UNITS

This Catalogue is FREE-Send for your copy



### DORMAN & SMITH LTD.

PRESTON Atherton W'ks, Blackpool Rd., Preston Tel: PRESTON 86785 (6 lines)

LONDON 125 High Holborn, W.C. 1.

Tel: CHAncery 6431

BIRMINGHAM 2/3 Graham St., Birmingham 1

GLASGOW 249 St. Vincent Street, Glasgow, C.2.


Tel: CENtral 2479

To: Dorman & Smith Ltd., Atherton Works, Blackpool Road, Preston, Lancashire Please send latest Miniature Circuit Breaker Catalogue

NAME

POSITION

FIRM



# The world's largest Generators will help to fill the demand for still more power

The development of nuclear energy for generating electricity is still front-page news. Less publicised, though no less outstanding, are new developments in "conventional" generating plant. The turbo-alternator shown here is a 550,000 kilowatt unit - twice the capacity of the next largest on order for the Central Electricity Generating Board. It has been designed for the projected new power station at Thorpe Marsh. For Blythe 'B' another new station, 275,000 kilowatt in-line units are on order. They will be powered by steam at 2,350 lb. per sq. in. and 1,050°F, with reheat to 1,000 F.


Nuclear power will play an important part in meeting the ever-increasing demand for electricity. Work is now in progress on the first three nuclear power stations, at Bradwell, Berkeley and Hinkley Point. By 1966 7 some 5 to 6 million kilowatts of nucleargenerated electric power will be available.


Though these projects will not be completed for some time, the Central Electricity Generating Board plays an important part in today's fight against inflation. Power stations are being built at a cost no greater than in 1948 - £50 per kilowatt installed. And, although the output of the industry has doubled since 1948, the increase in manpower is only about one-third.

By providing today for the power we shall need in years to come, the Central Electricity Generating Board is building a secure foundation for our future prosperity.




THE CENTRAL ELECTRICITY GENERATING BOARD











Since 1868 John Barker & Sons have helped to serve consumer and

industrial requirements for Roller
Shutters in wood, steel and now aluminium,
for Electric Lifts, for Hand Lifts
and for Self-landing Delivery Hoists. In
this way, we have contributed to better
universal living and working standards by
the introduction of improved designs executed
by first class craftsmen. For full details of Barker
products send for illustrated literature

AX



JOHN BARKER & SONS

(ENGINEERS) LTD

Union Street • Ancoats • Manchester 4 • Telephone: COLlyhurst 2018 London: Beacon Works, Strawberry Vale, Twickenham Tel: POPesgrove 0794

# O O | Put the sun into your ceilings

# UU

Step outside into sunshine from a normally heated room, you feel more comfortable don't you? That is because sun heat is RADIANT heat. Radiant heat and a low air temperature keep the body warm naturally, comfortably. Other types of heating systems can't do this, STRAMAX Radiant heating CAN.





COPIES OF ARCHITECTS JOURNAL INFORMATION SHEET NO. 29.HS SENT ON REQUEST

### HEATING · SOUND ABSORPTION · COOLING



A Stramax system in the ceiling keeps the room surfaces warmer than the enclosed air—the ideal conditions for health and comfort. Stramax radiant heating scores from the design angle too.

It's independent of the main building structure—doesn't need to be 'embedded'. Ceiling heating leaves the floor and walls entirely free from ugly pipes and heaters and it's suitable for any size of room.


STRAMAX Radiant heating is easy on fuel as well, it warms up quickly, and is easier to control thermostatically.

STRAMAX CEILINGS (G.B.) LIMITED
19 REA STREET SOUTH, BIRMINGHAM 5
Telephone:
MIDland 4674
Telegrams:
STRAMAX BIRMINGHAM 5

# EN-TOUT-GAS

### Hard Lawn Tennis Courts

Another new En-Tout-Cas 'Everede' Court has recently been constructed at The All England Club, Wimbledon.




Final of a Doubles Championship at Wimbledon

Bowling Greens
Football Grounds
Cricket Pitches
Running Tracks
Swimming Pools
Squash Rackets
Courts

### THE EN-TOUT-CAS CO. LTD.

SYSTON, LEICESTER (SYSTON 3322-7) London Office: Harrods (4th Floor) Knightsbridge, S.W.1



WATERFORD GLASS LIMITED, WATERFORD, IRELAND Enquiries for Britain, Australia and New Zealand should be directed to the Sale Agents

J. WUIDART & CC. LTD., 15 RATHBONE PLACE, LONDON, W.1

### Waterford Chandeliers

Beautifully hand cut from full lead crystal, Waterford Chandeliers are available in sizes suitable for modern interiors. Chandeliers can be supplied from stock in original Waterford designs or in new designs in the highest Waterford tradition. Waterford Glass are also glad to make up chandeliers to architects' own specifications. Particulars of this service will be sent on request.







### SUTCLIFFE'S SPECIALISE in the manufacture of TIMBER STRUCTURAL UNITS of all types to INDIVIDUAL requirements

Bow String Trusses, Lattice Girders, Shell Roofs, Roof and Floor Decks, Box Beams, Portal Frames, Laminated Beams, Plain and Glazed Curtain Walling, Doors, Windows.

Consultant Mr. D. W. CHOPER R.Sc., A.M.I.STRUET, E., F.ISST, W.Sc.

Technical Data available on request to

F. & H. SUTCLIFFE LTD.

96 Wood Top HEBDEN BRIDGE Tel. 217 (3 Lines) YORKSHIRE

### ready shortly: a new book by the author of 'Tomorrow's Landscape'

# The Landscape

# of Power

THIS BOOK is addressed to everyone who cares about Britain's landscape. Sylvia Crowe, the eminent landscape architect, is not a preservationist. She accepts the fact that you cannot put the clock back; she accepts the essential need for the construction of immense oil refineries, nuclear Sylvia Crowe P.I.L.A. reactors, power stations, and the network of the electricity grid. 'This network of power' she says, 'opens up a prospect of future wealth for the country, of clean industry and more efficient agriculture.' What she will not accept is that the introduction of these vast new structures into the landscape need necessarily ruin it, and in this practical, lucidly written handbook she calls for more thoughtfulness among those who are responsible for their construction. She shows, with text, photographs and diagrams, that giant buildings and their accessories can be incorporated in the landscape without destroying it-indeed, that given skilful design and sensitive siting they can in some circumstances enhance the natural scene.

> There are nine chapters in the book and they deal with The New Industrial Age; Power and National Parks; Nuclear Power Stations; Hydro-Electric Power; Electric Transmission; Oil; Airfields; New Industries in Old Areas; Conclusion. Size 81 in. by 51 in. 116 pages including over 70 diagrams and halftone illustrations. Price 16s. net,

The Architectural Press 9-13 Queen Anne's Gate Westminster S.W.1

### GATWICK AIRPORT

for Ministry of Transport and Civil Aviation





Metal windows supplied and fixed to 1st floor of the Pier, G.P.O. Block and Boiler House and Metal Ventilator Inserts to the cladding to the Terminal Building.

### MELLOWES & CO.LTD. LONDON

Consulting Engineers : Frederick Snow & Partners Architects: Messrs Yorke, Rosenberg & Mardall OLDHAM Main Contractors: Turriff Construction Co. Ltd.

# BYBNET Craftsmen in Laboratory Furniture

# RECENT IMPORTANT CONTRACTS

include laboratory installations for -

Beecham Maclean Limited-New Research Laboratories, Brentford. Salford Grammar School. Architects-Taylor & Young. F.A.R.I.B.A.

Philblack Limited—Laboratories at Avonmouth.

Architects-Sir Percy Thomas & Son. F.A.R.I.B.A.

Royal Grammar School, Newcastle-Science Block extension.

Architects-Spence & Price, A.R.I.B.A.

Transparent Paper Limited-Bury.

University College, London.

Architects-Corfiato, Thomson & Partners, F/A.R.I.B.A.

Warwickshire County Council—Polesworth School.

Department of Health for Scotland-Brown Trout Research Laboratories, Pitlochry.

Natural Sciences Building, Swansea.

Architects-Sir Percy Thomas & Son. F.A.R.I.B.A.

North Western Gas Board, Lostock Hall, Preston and at Denton.

Dunlop Cotton Mills Ltd.-Rochdale.

THE MARK OF THE

Send for full details now.



Built to meet the most exacting demands, "CYGNET" Benches, with heat and acid-resisting tops, Racks, Fume Cupboards, Cabinets and Shelving, are made in a large range of standard units or to specification.

CYGNET JOINERY LTD, DEPT. ARJ, HIGHER SWAN LANE, BOLTON


# LOOK....

# **KING-PIN**

advantages,

SIMPLE FUSE CHANGING!





out tools or coins and the

removable contact pins en-

sure easy and safe wiring.

The latest D.S. electrical

accessories catalogue gives

full details of plugs, sock-

ets, cooker control units

and industrial accessories.

Send for your copy today:

it is FREE.

EASY AND SAFE WIRING

No other fused plug offers the advantages of the D.S. King-pin both to the electrical contractor and his customers. This D.S. Plug, to B.S.S. 1363, permits fuse changing in 5 seconds with-

- Fuse immediately exposed by pressing hinged pin. No tools or coins required.
- \* All pins removable for easy wiring.
- ★ As contact pins are of the floating type they are self-aligning—no strain on sockets.
- Attractive modern design, high quality durable materials throughout.
- ★ Brown or ivory-white non-track plastic moulding.

\* NOW AVAILABLE

Latest D.S. Plugs Consolidated Price List.
A copy will be sent by return

D.S. PLUGS LTD

Head Office: Atherton Wks., Blackpool Rd., Preston, Lancs.
Works: Salterbeck, Workington.
Also at London, Glasgow, and Birmingham.

LATEX and PLASTIC FOAM
CUSHIONING for
LONG LENGTH SEATING

- . HOTELS, BARS & CLUBS
- . MUNICIPAL BUILDINGS
- RECEPTION AND
  WAITING ROOMS
  - SCHOOLS AND
     LECTURE HALLS
    - BAYS AND ALCOVES
    - EXHIBITION STANDS

Dunlopillo cushions and backrests supplied to any specification, uncovered or covered and ready for installation on site.

SEND FOR ILLUSTRATED LIST

LATEX UPHOLSTERY LTD.

THE LEADING SPECIALISTS
41, LONSDALE ROAD, LONDON, W.II

JAMES make good METAL WINDOWS

W. JAMES & CO. LTD. Hythe Rd. Willesden Junction LADbroke 6471 (6 lines) N.W.10



hille

Architects for the Gatwick Airport terminal buildings Yorke, Rosenberg and Mardall F/FRIBA's Consultant Engineers: Frederick S. Snow & Partners

### FURNITURE DESIGNED BY ROBIN DAY AT THE NEW GATWICK AIRPORT

Enquiries to showrooms Hille of London Ltd. 39-40 Albemarle Street London W.1 HYD 9576

24 Albert Street Birmingham 4 Midland 7378/9

### SEWAGE PURIFICATION

for Country Houses



Installation for a Housing Scheme

### TUKE & BELL LTD.

1 Lincoln's Inn Fields London, W.C.2


Works: Lichfield, Staffs

### THE WESSEX GUILD LTD

MANTON STREET · SWINDON · WILTS

TELEPHONE - SWINDON 2026

Architectural and Industrial Metalworkers



We were privileged to carry out the Architectural Metalwork at Messrs. Carr & Co's. new Office block to the designs and instructions of Ernö Goldfinger, DPLG, LRIBA

# A quicker and easier method of assembly

Already used for a great many applications in the Building industry the 'Pop' Riveting System is now achieving even greater success in the fixing of suspended ceilings. By virtue of its very simplicity, it is faster, more economical in cost and labour and provides one of the easiest methods of fixing yet evolved.

As the setting of the rivet is controlled by the mandrel, which can break only when the joint is tight and the rivet head fully formed, uniformity of setting is achieved thereby elimininating damage and distortion of the structure.

Send for a copy of our catalogue which describes in detail the many advantages of the 'Pop' Riveting System.









The photograph above shows 'Pop' Rivets being used for fixing suspended ceilings.

TUCKER POPRIVETS



Geo. TUCKER EYELET Co. Ltd. Walsall Road • BIRMINGHAM 22

Telephone: BIRchfields 4811 (9 lines) [Telegrams: EYELETS, BIRMINGHAM Consultants: AIRCRAFT MATERIALS LTD., Midland Road, London, N.W.I

The trade mark "POP" is registered in respect of rivets in the United Kingdom and many other countries in the name of the Geo. I tacker Eyelet Co. Ltd.

Exhibition model of Hydro-Electric Power Station, Fenosa-Los Peares Scheme, scale 1 50th.

Made to the order of the British Thamson-Houston Co. Ltd.

See it
BEFORE
you build!



Second thoughts can be costly when a major project is under construction. Forestall this possibility with a Bassett-Lowke true-to-scale model. A 3-dimensional model brings the whole project right into the Board Room, where problems can be finally solved and the latest developments incorporated into the design before a brick is laid—that way lies true economy.

The Bassett-Lawke brochure S.M.54 is well worth the serious attention of Executives and Purchasing Agents.

It is free of charge.

### BASSETT-LOWKE LTD

Head Office and Works

NORTHAMPTON

LONDON 112 High Holborn, W.C.I MANCHESTER: 28 Corporation Street

C. BRYANT &
SON, LTD
were the main
Contractors for the
New Offices of
MESSRS CARR & CO


IN SHIRLEY, SOLIHULL, WARWICKSHIRE

C. BRYANT & SON, LTD., SMALL HEATH, BIRMINGHAM 10

Telephone: VICtoria 2333 (10 lines)

BUILDING AND CIVIL ENGINEERING CONTRACTORS

LGB



It is the consistent high quality and fault-less finish of McKechnie Extrusions that has made them the choice of industry throughout the world. Whether sections in brass, bronze, nickel silver or copper from over 20,000 dies available or brass rods in straight lengths or coils for high speed turning and screwing. McKechnie can meet every production need.

### Mc KECHNIE

HIGH QUALITY
EXTRUDED SECTIONS and
BRASS RODS for Industry



### MCKECHNIE BROTHERS LIMITED

14 Berkeley Street, London, W.I. Telephone: Hyde Park 9841/7. Metal Works: Rotton Park Street, Birmingham 16 and Aldridge, Staffs. Other Factories at Widnes, London, South Africa, New Zealand. Branch Offices at London, Manchester, Leeds, Gloucester, Newcastle-upon-Tyne, Glasgow (Agents J. Hood & Co.), Paris.

### Lord Roberts Workshops

supplied and fixed the students' bed-sitting room furniture at the

JEWS' COLLEGE · MONTAGU PLACE · WI

Architects: Yorke, Rosenberg & Mardall, FF/ARIBA

Other items included the 20' boardroom table and special units

The opportunity to tender for 'built-in' schemes or free-standing furniture to architects' designs will be appreciated

LORD ROBERTS WORKSHOPS

525 FULHAM ROAD · SW6 ·

Fulham 1352

Contractors to Government Departments and Local Authorities

### THE WESSEX GUILD LTD

MANTON STREET · SWINDON · WILTS
TELEPHONE - SWINDON 2026

Architectural and Decorative Metalworkers



We were privileged to carry out Balustrades, Balcony Railings, Area Railings, etc., at Jews College, Montagu Place, W.1., to the design and instructions of Messrs. Yorke, Rosenberg & Mardall, F. FRIBA

# Sunflowers at Sea

Stimulating pattern and colour give a new air to the redecorated Long Gallery of the Union-Castle liner, Pretoria Castle. The scheme is built round the colourings of the Old Glamis printed linen, SUNFLOWERS, used for the curtains. The grey, emerald, apple, canary, and chocolate of this pattern are echoed in the Old Glamis heavy weaves, WHITHORN, IONA and MALVERN which cover the chairs and settees and in the DON QUIXOTE cotton damask used on the high-backed settles. This is a splendid example of the general trend to the lighter and brighter treatment of public rooms.

Architects are welcome visitors to our London or Dundee showrooms. Here we can show you Old Glamis furnishing fabrics which cannot be seen elsewhere; a range prepared exclusively for contract work; designs which can be produced in colours to suit your schemes. Look in, if you can, or write to us about your problems. We will gladly give you the address of your nearest Old Glamis stockist.








### GLAMIS FABRICS OLD

ROXBURGHE HOUSE 287 REGENT STREET, LONDON, W1 (MAYFAIR 1126 / 7) THE OLD GLAMIS FACTORY, DUNDEE (DUNDEE 85263 / 4)

### DESIGNED by designers for DESIGNERS



This illustrates an example of modular recessed lighting, the diffuser being specially made in 030 corrugated perspex, and mounted in an all-white enamelled reflector with 1" wide flange below the ceiling level.



WELBECK WORKS, WELBECK ROAD, SOUTH HARROW, MIDDLESEX . Telephone: BYRON 3273 5

second impression

now ready

#### The Home of Man

by Le Corbusier and François de Pierrefeu Translated by Clive Entwistle and Gordon Holt

Size 8 ins. × 51 ins. 156 pages, containing a large number of drawings by Le Corbusier Price 15s. net (Postage 10d.)

This is the second of the two post-war books by Le Corbusier to be published in English by The Architectural Press (Concerning Town Planning was the first). In this work Le Corbusier has collaborated with François de Pierrefeu who has been closely associated with him for many years,

M. de Pierrefeu contributes the introductory text, in which he outlines the principles that should be followed in the design and planning of the towns and homes of the new world so that the resources of science are fully applied to providing the best environment for the ordinary man. Le Corbusier's section of the book follows the same theme. It consists of illustrations drawn in his own inimitable style, accompanied by his own commentary, and forms the principal contents of the book.

THE ARCHITECTURAL PRESS

9-13 QUEEN ANNE'S GATE, WESTMINSTER, SWI

Part of the landscaping at Hallfield flats for the Metropolitan Borough of Paddington.

Architects: Drake & Lasdan, F. 4. R.I.B.4. All specialist landscape contractor's work and planting by William Wood & Son Ltd.



By appointment to H.M. Queen Elizabeth II Garden Contractors and Horticultural Builders William Wood & Son Ltd.



By appointment to H.M. Queen Elizabeth the Queen Mother Garden Contractors and Horticultural Builders William Wood & Son Ltd.



### Landscape Service for Architects

Nine acres of land immediately surrounding the new flats at Hallfield were the subject of carefully considered landscape treatment. William Wood & Son carried out the final preparation and grading and sowed the grass seed, made the paths and did all the planting. Some remodelling of contours was carried out on the planting areas with surplus spoil to provide relief to the general flatness of the land opposed to the tall buildings.

William Wood & Son Limited TAPLOW BUCKINGHAMSHIRE

-FEATURED IN THIS ISSUE— THE NEW OFFICES FOR MESSRS. CARR & CO. LTD., SHIRLEY, BIRMINGHAM

Architect:
Erno Goldfinger, L.R.I.B.A., D.P.L.G.

# ECHOSTOP PLASTER ACOUSTIC TILES

used to form

SUSPENDED CEILINGS

ACOUSTIC DIVISION.

CLARK & FENN LTD

16 OLD TOWN • LONDON • S.W.4 TELEPHONE—MACAULAY 2455-9

# "IF YOU WERE ILL... would your income be safe

Most people face a big drop in income sooner or later if they cannot work from illness or accident. Are YOU insured against this risk?



### "HOW DO I INSURE MY INCOME?"

By taking out a PERMANENT SICKNESS INSURANCE POLICY to provide a weekly income if illness or accident stops you working.

### "HOW LONG DOES THE INSURANCE LAST?"

It is usual to take a policy that goes on to age 65 so that you are protected throughout normal working life.

#### "CAN I CLAIM MORE THAN ONCEP"

Yes. As often and for as long as necessary. If you are so ill that you cannot work again, the payments continue as long as the insurance lasts.

#### "CAN THE POLICY BE CANGELLED BY THE COMPANY IF I CLAIM HEAVILY P"

NO. No matter how much benefit you draw the Company cannot cancel or amend the Policy on this account.

### "HOW MUCH DOES IT COST?"

That depends on your age at entry and the type of benefit. If you do not need payments to begin until you have been off work for six months you can secure

### £5 a week

UP TO AGE 65 FOR £5 A YEAR

if you are under 32 now and can pass a medical examination. (You can start at any age up to 50).

8	THE PERMANENT SICKNESS INSURANCE CO. LTD
i	3 CAVENDISH SQUARE, LONDON, W.1 Tel: LANgham 0341 (4 lines)
	Please send me full particulars of Permanent Sickness Insurance:
	NAME
	ADDRESS
	E

# PERSPECTIVIST

By R. Myerscough-Walker. The making of a perspective is a highly skilled task, and can often be the deciding factor when an architect submits a scheme. In this unique book, the author not only covers every aspect of the subject (including costing, copy-right and architect-client relationships), but goes further and presents his own deeply philosophical attitude to his art. The clarity and impact of his writing and the countless illustrations make this a rare and unusual book. From booksellers, 60/- net.

PITMAN


Parker St., Kingsway, London, W.C.2

THERE'S A STAIRTREAD FOR EVERY TYPE OF STAIR \* 19 different nosings : extruded from pure aluminium: plastic-filled in 9 colours (brown, green, lino brown, blue, maroon, black, white, silver, red): also available fabric-filled: suitable for all types of stairway: can be supplied to fit almost any curve or bend. To Small & Parkes Ltd. (Stairtreads Dept.), Manchester 9
PLEASE SEND ME YOUR ILLUSTRATED CATALOGUE
GIVING DEPAULS OF NOSINGS, COLOURS & DIMENSIONS
OF DON STAIRTREADS—and names of depots and suppliers.

NAME

ADDRESS

Not just a desk . . .




SHALL & PARKES LTD . Hendham Vale Works . Manchester 9 London: 76 Victoria Street, S.W.I

### ... A COMPLETE SUITE



Architects who have a voice in the furnishing of business premises will welcome the introduction of the Harvey 400-Style Suite. A basic design of exceptional merit has been adapted to a full range of complementary units, providing for the utmost flexibility in modern office planning whilst preserving harmony and dignity throughout.



### 400-STYLE

a matching suite of office furniture in steel




G. A. HARVEY & CO. (LONDON) LTD., WOOLWICH ROAD, LONDON, S.E.7. GREenwich 3232 (22 lines)

HARVEY



CHAMBERLIN WEATHERSTRIPS LIMITED 436 HOOK ROAD, CHESSINGTON, SURREY . Tel: Lower Hook 1181 (3 lines)



Architects are discovering new ways of using tiles in contemporary building and decorating, and Malkin are playing their part by introducing their newly developed REDHILL tiles for exterior and interior use in an interesting variation of design and colour.

write for further details to:

THE MALK'N TILES (Burslem) Ltd., Burslem, Stoke-on-Trent
Telephone: Stoke-on-Trent 87287

Members of the Glassed and Floor Tile Manufacturers' Association

### harder use for greater comfort easier cleaning

Three important factors influenced Ernest Race in his design for these new chairs and settees for shipping, hotel and commercial use



The upholstery of the entire arms, sides and back -where abrasion, scuffing and wear is at its greatest—is a rich hide; the frame is of tubular steel. The legs are of polished mahogany and fitted with Armstrong footrests

### Cleaning

The back and seat cushions are removable and their covers can quickly tached for cleaning (Cushion coversand spare sets are available in a wide range of fabrics: all treated for non-fray during

The seats and back cushions are of thick latex: the seat cushion is on Pirelli webbing More? The design is typically Race: clean, elegant, practical—throughout. And ost? No comparable chair ould give such good value

### RACE furniture London

Write for our illustrated list 22 Union Road Clapham SW4 Telephone: MACaulay 2215/7

# IN THE NEW SINGAPORE ium Satin Silver Anodised Kinrod Grilles installed on the American International Assurance Building bring the triple advantage of pleasing design, perfect visibility, and complete security Precision-built, they are guaranteed for workmanship and



By the makers of-GRILLES Kinnear Shutters & Kinylon Grilles

Please send for illustrated leaflet 10B ARTHUR L. GIBSON & CO. LTD Twickenham, Middlesex, Telephone Popesgrove 2276. Birmingham: Highbury 2804. Glasgow Halfway 2928. Manchester: Central 1008. Cardiff: 51428.

### ALPHABETICAL LIST TO ADVERTISERS

			PAGE
Abix (Metal Industries), Ltd.			CKVIII
A.E.I. Lamp & Lighting Co. Ltd.			1xviii
Allied Ironfounders, Ltd.			lxix
Anderson, D. & Sons, Ltd.			XXIV
Architectural Press, Ltd.		X, EXXV	III, CXXXIV
Atlas Asbestos Cement Co. Ltd.			XXI
Atlas Lighting Co. Ltd.			Iviii
Aygee, Ltd.			XC1
Barker, John, & Son (Engineers),	Ltd.		CXXVI
Barking Brassware Co. Ltd.			alvin
Bassett-Lowke, Ltd.			UNANH
Best & Lloyd, Ltd.			EXXIII
			XXIII
Bilston Foundries, Ltd.			22
B.I.P. Reinforced Products, Ltd.			IXXVII
Bitmetals, Ltd.			1.1
B.I.P. Reinforced Products, Ltd. Birmetals, Ltd. Black Sheathing Felt			8.711
posten, Jonn, & Sons (Botton), Li			INI
Bow State & Enamel Co. Ltd.			33
British Reinforced Concrete Engi- Ltd.			
British Titan Products Co. Ltd.			CAL
			fix
Bryant, C., & Son, Ltd. Burgess Products Co. Ltd.			XCVII
			YCAH
Canadian Government			XXXVIII
Cape Building Products, Ltd.			XXXI
Carrier Engineering Co. Ltd			JANXIX
Central Electricity Authority			CXXV
Chamberlin Weatherstrips, Ltd.			EXXXVII
Chatwins, Ltd			CXZIG
Clark & Penn, Ltd.			CXXXV
Loncrete, Ltd.			NULL
Crane, Ltd.			188816
Crittall Manufacturing Co. Ltd.			YER
Cullum, Horace W., & Co. Ltd.			NNIN
Cygnet Joinery, Ltd.			CXXXIX
			LEXIS
Danks, Edwin, & Co. (Oldbury), I.	til.		CX31V
Darlington Insulation Co. Ltd.			3.CVIII
Davies, A., & Co. (Shopfitters), Lt.	d.		Exiv
De La Rue, Thomas, & Co. Ltd.			111
Dohm, Ltd.			XXVI
Donald Bros., Ltd.			EXXXIV
Dorman Long, Ltd.			INSH.
Dorman & Smith, Ltd.			CXXV
Dover, Ltd Draftsele, Ltd			SXXVII
Draftsele, Ltd			81.53
D.S. Plugs, Ltd.			CNNX
Effort, Samuel, & Sons (Reading),	Ltd.		li
Engravers Guild, Ltd			XAXIY
En Tout Cas Co. Ltd.			CXXVII
Evode, Ltd.			hi
Farmilioe, T. & W., Ltd.			XXII
Fibreglass, Ltd.			1.3
Firth Vickers Stainless Steels, Ltd.			X.

				PAC
Frenger Ceilings, Ltd.				EA
Gardiner, Sons & Co. Ltd.				V
Gascoigne, George H., Co. I	tel			( )
Gaskell & Chambers, Ltd.				CXV
Gay, R., & Co General Electric Co. Ltd.				lxx
General Electric Co. Ltd.			1x	XVIII, CX
Gent & Co. Ltd. Gibson, Arthur L., & Co. L.				XXV
Gibson, Arthur L., & Co. I.	td.			CXXXV
Glazed & Floor Lie Manuf.	acture:	S As		71
Gliksten, L., & Sons, Ltd. Greenwood & Airvac Ventil	The Assessment of the Indian	C . T	4.5	XXX
Gyproc Products, Ltd.	ating	COL		1.5
Cyproc Products, Ltd.				
Hammond & Champness, L.	tel.			3331
Hardwood Flooring Man-			Assor	
ciation				13.3
Harris & Sheldon, Ltd.				CAL
Harrods, Ltd				
Harvey, G. A., & Co. (Lond	long, L	101.		17888
Haywards, Ltd.				3
Heal's Contracts, Ltd. Hermaseal Acoustics, Ltd.				XXV
Heywood, W. H., & Co. Lte.				111
Hickman Ltd				
Hickman, Ltd. Hill, Richard, Ltd. Hille of London, Ltd.				Jaxis
Hille of London, Ltd.				CXXX
Fills (West Bromwich), Ltd.				laxi
Holmes, W. C., & Co. Ltd.				XXX
Holoplast, Ltd. Hope, Henry, & Sons, Ltd.				811
Hope, Henry, & Sons, Ltd.				CX1
Hope's Heating & Engineers	ng Lt	I.		183
Horsley Smith & Co. (Have				Iv
Hunter, Douglas (Great Brit	ami, i			3.7
Bestock Brick & Tile Co. Ltd.	d.			lxxx
Ideal Boilers & Radiators, I.				SIV, XI
Imperial Chemical Industries				xb
Intermit, Ltd.				lsvi
International Paints, Ltd.				UXIV
Iota Services, Ltd				713
1 M. 4 1				
James, W., & Co. Ltd.				13.53
Jenson & Nicholson, Ltd.				XXXV
Kenkast Concrete, Ltd.				CXXII
Key Engineering Co. Ltd.				XXXIX
Latex Upholstery, Ltd.				ESSX
Leigh, W. & J., Ltd				VI
Liberty & Co. Ltd.				CX310
Limmer & Trinidad Lake As	phait			183891
Line, John, & Sons, Ltd.	Lot			
Linoleum Manufacturing Co. Lord Roberts Workshops	1.10.			CXXXIII
read wooders workshops				-AAAIII
Malkin Tiles, Ltd.				CENTER
Mallinson William, & Sons, I	td.			Ivii
Matthew Hall & Co. Ltd.				XXV

				PAGE
McKechnie Bros. Ltd				CXXXIII
Mellowes & Co. Ltd				CNNIN
Midland Silicone, Ltd				MOLV
Montgomerie Stobo & Co. Lto	1.			liv
				3/111
Newalls Insulation Co. Ltd.				XII
Parnall, George, & Co. Ltd.				cviii
Parnall, George, & Co. Ltd. Permanent Sickness Insurance	Co	1 4.4		CNNNV
Filkington Bros., Ltd		1.00		lx, lxi
Pilkington Tiles, Ltd.				lxxxiii
Pitman, Sir Isaac, & Sons, Lt				CNNNVI
Printing the Page , & Sours, Est				
Race, Ernest				CXXXVII
Rawlplug Co. Ltd.				XIX
Redpath Brown, Ltd.				IXXXI
Robertson, Thain, Ltd.				lxxx
Rotaflex, Ltd.				lxx
Sankey Sheldon, Ltd				CXII, CXIII
Semtex, Ltd. Shanks & Co. Ltd.				lxxxII
Shanks & Co. Lid.				(X)
Siemens Edison Swan, Ltd.				ix, xh
Simpson, W. B., & Sons, Ltd. S.L.R. Electric, Ltd.				IV
				CXXXIV
Small & Parkes, Ltd				CXXXVI
Spectra Glaze				xlvii
Sposs Products, Ltd.				XVIII
Steel Bracketing & Lathing, I				lxxm
Still, W. M., & Sons, Ltd.				XCII
Stramax Ceilings (G.B.), Ltd. Sussex Rubber Co.				CXXVL
Sussex Rubber Co. Sutchife, F. & H., Ltd.				CXAVIII
softmar, r. & r., Liu.				CXXVIII
Thermalite, Ltd.				lxxxvm
Thermocontrol Installations Co				CIV
Troughton & Young (Lighting				XCV
Trussed Concrete Steel Compar				aliv
Inbe Lamination & Engineeric				XXX
Fucker, Eyelet (George) Co. L.	42			* X X X II
Tuke & Bell, Ltd.				EXXXI
United Steel Structural Co. Lt.	1			1
Universal Metal Furring & La	thine	Col		lxiii
Vafbania, Ltd.				
Venus Pencil Co. Ltd.				CXXIV
Walker, Crosweller & Co. Ltd.				lxxv
Wall Paper Manufacturers, Lto			XV	i, lxxxxii
Warerite, Ltd.				xlix
Wates, Ltd.				lxvi
Weatherfoil Heating Systems,	1.171			XCHI
Wessex Guild, Ltd.			188	XI. (XXIII
West's Piling & Construction (				CXXXVIII
Williams, John & Sons (Cardiff	LIN			CXXII
Wood, William, & Sou, Ltd.				CXXXV
Wuidart, J. & Co.				CXXVII
7 31 4 4 4 4 1				




a book on stability...

A publication of great value to all who may be concerned with the design of new buildings or extensions, particularly those imposing great weight per unit of area occupied. Dealing in simple terms with thescience of soil mechanics and outlining problems associated with the construction of firm foundations, the book also illustrates the application of West's Shell Piling System—a modern mobile method which combines a precast shell with a cast-in-situ core.

### WRITE FOR YOUR COPY TO:

WEST'S PILING & CONSTRUCTION CO. LTD Foundation Specialists. Design & Construction in Reinforced Concrete. BATH ROAD, HARMONDSWORTH, MIDDX. TEL: SKYPORT 5222 BRANCHES IN LONDON . BIRMINGHAM . MANCHESTER . GLASGOW

Australasia: West's Shell Piling (Aisia) Ltd, Melbourne and Sydney Southern Africa: The Roberts Construction Co., Ltd, Johannesburg France: Compagnie Générale de Construction de Fours, Paris Ireland: Farrans Ltd, Dunmurry, Belfast



NOW

Suspended Acoustic Cellings with



CULLUM

BRITAIN'S MOST EXPERIENCED ACOUSTIC ENGINEERS



HORACE W. CULLUM & CO. LTD.

THE ACOUSTIC CENTRE
58 HIGHGATE WEST HILL, LONDON, N.6.
FITZROY 1221 (P.B.X.)

Reinforced Concrete for strength with lightness

BR

Specialists in Reinforced Concrete Design

and Suppliers of Reinforcement



THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD

London, Birmingham, Bristol, Leeds, Leicester, Liverpool, Manchester, Newcastle, Cardiff, Glasgow, Dublin, Belfast, Bulawayo, Calcutta, Johannesburg, Singapore, Vancouver. Export Sales: 54 Grosvenor Street, London W.1